

SUMMARY OF QUANTITIES

FAI-74 VERMILION CO. RURAL INTERSTATE 100% STATE MINOR STRUCTURE REPAIR	FAI-74 VERMILION CO. RURAL INTERSTATE 100% STATE MINOR STRUCTURE REPAIR
0014 S.N. 092-0001	0014 S.N. 092-0002

100% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	55.0	27.5	27.5
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N-105	TON	138.0	69.0	69.0
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SQ YD	192.0	96.0	96.0
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1185.0	592.5	592.5
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2.0	1.0	1.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	0.5	0.5
70400100	TEMPORARY CONCRETE BARRIER	FOOT	900.0	450.0	450.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	900.0	450.0	450.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	990.0	495.0	495.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12.0	6.0	6.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12.0	6.0	6.0
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	542.0	271.0	271.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	14.0	14.0
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0	0.5	0.5
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1167.0	583.5	583.5
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	15.0	7.5	7.5
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	30.0	15.0	15.0
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	173.0	86.5	86.5
Z0021906	SILICONE JOINT SEALER, 1.5"	FOOT	149.0	74.5	74.5
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0	1.0	1.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0	1.0	1.0

* SPECIALTY ITEMS

FILE NAME =	USER NAME = simsgm	DESIGNED - GMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw_work\pwidot\simsgm\d0187665\d59093	3 Bridge Repairs.dgn	DRAWN - GMS	REVISED -			74	(92-9BR)-1	VERMILION	15	3	
	PLOT SCALE = 40.0001' / IN.	CHECKED -	REVISED -			CONTRACT NO. 90963					
	PLOT DATE = 10/18/2010	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					