

801.FED/201.STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	607	607		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	18281	18281		
40600300	AGGREGATE (PRIME COAT)	TON	366	366		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	7678	7678		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	505	505		
40600990	TEMPORARY RAMP	SQ YD	142	142		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	15356	15356		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	422	422		
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	182808	182808		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	5746	5746		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	1104	1104		
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	308	308		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5245	5245		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	25380	25380		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	145009	145009		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2115	2115		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	145009	145009		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	793	793		
* 88600100	DETECTOR LOOP, TYPE I	FOOT	154	154		
* X0300780	PIEZO ELECTRIC SENSOR CABLE IN CONDUIT	FOOT	45	45		
* X0323015	PIEZO ELECTRIC AXLE SENSOR, CLASS II	FOOT	26	26		
X0323016	ELECTRIC CABLE IN CONDUIT = 14-7STRAND XHHW XLP-600V	FOOT	102	102		
X4421000	PARTIAL DEPTH PATCHING	TON	6313	6313		
X4422000	PARTIAL DEPTH REMOVAL (VARIABLE DEPTH)	SQ YD	28184	28184		
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	7	7		
Δ Z0076600	TRAINEES	HOUR	500	500		

Δ 0042
*Specialty Items

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	TOTAL SHEET NO.	
c:\pwork\pwork\teasleyck\20240815\074985-shr-500.dgn		DRAWN -	REVISED -			116	120RS-2, 4RS-3	Jasper	18	3	
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 94985					
PLOT DATE = 10/27/2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					