

PAVING													
STATION	OFFSET	SIDE	LOCATION	PAVEMENT REMOVAL	PROTECTIVE COAT	CONCRETE MEDIAN SURFACE, 4 INCH (SPECIAL)	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	BITUMINOUS MATERIAL (PRIME COAT)	SUB-BASE GRANULAR MATERIAL, TYPE A	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	INCIDENTAL HOT-MIX ASPHALT SURFACING
				SQ YD	SQ YD	SQ FT	SQ YD	GALLON	TON	TON	TON	SQ YD	TON
17+38.68 TO 17+64.81			WEST TIE IN					7				77	9
17+64.81 TO 22+35.16			PORTER RD	1348				644	1349	564	158		
18+89.21 TO 19+06.92			WEST ISLAND		8	70							
19+57.00 TO 20+43.00			CENTER ISLAND		372		372						
19+58.00 TO 20+42.00			CENTER ISLAND						89				
20+93.08 TO 21+10.79			EAST ISLAND		8	69							
22+35.16 TO 22+55.16			EAST TIE IN					6				60	7
50+19.83 TO 52+35.19			SIMMONS RD	716				389	831	340	96		
50+93.08 TO 51+10.79			NORTH ISLAND		8	68							
52+35.19 TO 52+50.26			NORTH TIE IN					5				48	5
TOTALS:				2064	396	207	372	1051	2269	904	254	185	21

SIDEWALK						
STATION	SIDE	SIDEWALK REMOVAL (SPECIAL)	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	HOT-MIX ASPHALT SIDEWALK	DETECTABLE WARNINGS	SUB-BASE GRANULAR MATERIAL, TYPE C 6 INCH
		SQ FT	SQ FT	SQ FT	SQ FT	TONS
18+55.89 TO 21+53.82	RIGHT	4660		3897		177
18+90.00 TO 51+05.00	LEFT		974			
19+01.68 TO 19+11.31	LEFT				20	
19+03.68 TO 19+13.35	RIGHT		68		20	
19+07.34 TO 19+17.57	CENTER				40	
20+82.45 TO 20+92.64	CENTER				40	
20+86.88 TO 20+96.64	LEFT				20	
20+87.52 TO 20+97.15	RIGHT		68		20	
50+82.45 TO 50+92.61	CENTER				40	
50+85.88 TO 50+95.71	LEFT				20	
50+88.75 TO 50+98.37	RIGHT				20	
51+50.00 TO 21+05.00	RIGHT/LEFT		972			
TOTALS:		4660	2082	3897	240	177

CURB AND GUTTER								
STATION	OFFSET	SIDE	LOCATION	PROTECTIVE COAT	COMBINATION CONCRETE CURB AND GUTTER TYPE B (SPECIAL)	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER TYPE B-9.18 (SPECIAL)	COMBINATION CONCRETE CURB AND GUTTER TYPE M-2.12
				SQ YD	FOOT	FOOT	FOOT	FOOT
17+64.81 TO 52+35.19	15	LT	NW QUAD	133		388.5		
17+64.81 TO 22+35.16	15	RT	SOUTH QUAD	169		493.5		
18+89.21 TO 19+34.49			WEST ISLAND	25	104.5			
19+56.50 TO 20+43.50			CENTER ISLAND	51				273.5
19+73.50 TO 20+26.50			CENTER ISLAND	53			166.5	
20+65.27 TO 21+11.41			EAST ISLAND	25	105.0			
50+65.42 TO 51+10.79			NORTH ISLAND	25	104.0			
52+35.19 TO 22+35.16	15	RT/LT	NE QUAD	135		392.5		
TOTALS:				616	313.5	1274.5	166.5	273.5

LAST SAVED = 11/1/2018
PEN TABLE = VB-Hotf.ab
PLOT DRIVER = TR-VBpdf-Black-Half.plt

FILE NAME =	USER NAME = sdonehue	DESIGNED -	REVISED -
\\0012900\cad\1\p\p\05_08XXXXX-Sht-Schedule.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -
PLOT SCALE = 48.0018 / IN.			
PLOT DATE = 11/1/2018 1:17:48 PM			



SCHEDULES OF QUANTITIES

SCALE: NTS SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.U. 9170
PORTER / SIMMONS ROADS
SECTION 08-0060-00-PV
CONTRACT 97408

TOTAL SHEETS	SHEET NO.
36	7