

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 90% FED 10% STATE 0004	SIGNAL 90% FED 10% STATE 0021	90% FED 10% STATE 0021 (INTERCONNECT)	100% WEST CHICAGO F.D. E.V.P. 0021	100% STATE 0005
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	60	60				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	75	75				
20200100	EARTH EXCAVATION	CU YD	372	372				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6	6				
20800150	TRENCH BACKFILL	CU YD	32	32				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	136	136				
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	469	469				
21400100	GRADING AND SHAPING DITCHES	FOOT	125	125				
25100125	MULCH, METHOD 3	ACRE	0.4	0.4				
25100630	EROSION CONTROL BLANKET	SQ YD	1690	1690				
28000305	TEMPORARY DITCH CHECKS	FOOT	20	20				
28000400	PERIMETER EROSION BARRIER	FOOT	1000	1000				
28000510	INLET FILTERS	EACH	15	15				
28100105	STONE RIPRAP, CLASS A3	SQ YD	15	15				
28200200	FILTER FABRIC	SQ YD	15	15				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 90% FED 10% STATE 0004	SIGNAL 90% FED 10% STATE 0021	90% FED 10% STATE 0021 (INTERCONNECT)	100% WEST CHICAGO F.D. E.V.P. 0021	100% STATE 0005
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	6	6				
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	545	545				
35501314	HOT-MIX ASPHALT BASE COURSE, 7 1/2"	SO YD	326	326				
35600706	HOT-MIX ASPHALT BASE COURSE WIDENING, 7 1/2"	SO YD	127	127				
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	2035	2035				
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	5460	5460				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	76	76				
40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	TON	334	334				
40605026	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE STONE MATRIX ASPHALT, 9.5, MIX "F", N80	TON	793	793				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	7631	7631				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	116	116				

FILE NAME =	USER NAME = hssomn	DESIGNED -	REVISED -
pw:\N\dot-pw\benley.com\PI\DOT\Documents\1007 - Office\101\101\Projects\PI29915\CADData\Design\PI29915-st1-502		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1in	CHECKED -	REVISED -
	PLOT DATE = 10/22/2021	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL-59 AT GARY'S MILL ROAD
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	2020-028-TS		61	4
CONTRACT NO. 62K99			REVISED SHEET 1/5/2022	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

* SPECIALTY ITEM

REV-SEP

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 90% FED 10% STATE 0004	SIGNAL 90% FED 10% STATE 0021	90% FED 10% STATE 0021 (INTERCONNECT)	100% WEST CHICAGO F.D. E.V.P. 0021	100% STATE 0005
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	130	130				
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SO YD	50	50				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	50	50				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	70	70				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	60	60				
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SO YD	150	150				
* 54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1				
* 54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
* 550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	51	51				
* 550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	133	133				
* 55100500	STORM SEWER REMOVAL 12"	FOOT	32	32				
* 55101200	STORM SEWER REMOVAL 24"	FOOT	91	91				
* 60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2	2				
60108204	PIPE UNDERDRAINS, TYPE 2, 4"	FOOT	500	500				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 90% FED 10% STATE 0004	SIGNAL 90% FED 10% STATE 0021	90% FED 10% STATE 0021 (INTERCONNECT)	100% WEST CHICAGO F.D. E.V.P. 0021	100% STATE 0005
* 60200105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	9	9				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1				
60260100	INLETS TO BE ADJUSTED	EACH	5	5				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2.38	2.38				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	62	62				
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	220	220				
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3				
63200310	GUARDRAIL REMOVAL	FOOT	416	416				

FILE NAME =	USER NAME = hssom	DESIGNED -	REVISED -
pw\N\dot-pw\benfrey.com\PI\DOT\Documents\DOT - Office\District\Projects\PI29915\NCAD\Design\PI29915-st-502		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL-59 AT GARY'S MILL ROAD
SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	2020-028-TS		61	5
CONTRACT NO.			62K99	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

2 REVISION SHEET 1/3/2022

SPECIALTY ITEM

REV-SEP