



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 10, 2022

SUBJECT FAU Route 2943 (Burnham Ave)
Project STP-NHPP-FZ9U(690)
Section 2021-079-RS&SW
Cook County
Contract No. 62P16
Item No. 127, January 21, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page i of the Table of Contents to the Special Provisions
3. Revised pages 111-113 of the Special Provisions
4. Revised Sheets 2, 5, 6, 8, 10, 11 & 58 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D1)	2
STATUS OF UTILITIES (D1)	2
PUBLIC CONVENIENCE AND SAFETY (D1)	11
TRAFFIC CONTROL PLAN (D1)	11
CONSTRUCTION LAYOUT SPECIAL FOR RESURFACING WITH ADA AND STAND ALONE ADA (D1)	13
FRICTION AGGREGATE (D1)	14
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1)	17
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	18
ADJUSTMENTS AND RECONSTRUCTIONS (D1)	23
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (D1)	24
CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1)	25
HOT-MIX ASPHALT REMOVAL (SPECIAL)	27
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	27
MAINTENANCE OF EXISTING TRAFFIC SIGNAL AND FLASHING BEACON INSTALLATION	28
RAILROAD SPECIAL PROVISIONS	32
DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS)	97
REBUILD EXISTING HANDHOLE	101
REBUILD EXISTING DOUBLE HANDHOLE	101
RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	102
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	102
DRAINAGE STRUCTURES AND STORM SEWERS TO BE CLEANED	109
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	109
HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	110
REMOVE AND REINSTALL SIGN PANEL	111
TEMPORARY INFORMATION SIGNING	114
TRAFFIC CONTROL AT AT-GRADE RR CROSSINGS	115
TRAFFIC CONTROL IN THE VICINITY OF A RAILROAD GRADE CROSSING	116
WASHOUT BASIN	116
RAILROAD PROTECTIVE LIABILITY INSURANCE	116

Revised 1/10/2022

REMOVE AND REINSTALL SIGN PANEL

This work shall consist of removal and storage of existing sign panels, posts, hardware and appurtenances and reinstallation of each at the completion of construction. This work shall be performed in accordance with the applicable Articles of Section 723 of the Standard Specifications, and as described herein:

The Contractor shall remove and store each sign panel, posts, mounting hardware and all other appurtenances and reinstall each upon completion of the project. Care shall be taken to preserve the condition of the sign, post, hardware and appurtenances. Damaged signs, posts shall be replaced by the Contractor at their expense. The signs will be reinstalled at the locations shown in the plans and as directed by the Engineer.

All equipment and labor required to remove, store and reinstall sign panels will be paid for at the contract unit price square foot for REMOVE AND REINSTALL SIGN PANEL.

Revised 1/10/2022

This page intentionally left blank

Revised 1/10/2022

This page intentionally left blank

Revised 1/10/2022