



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 11, 2022

SUBJECT: FAI Route 57 (I-57)  
Project HBIR-NHPP-34FV(643)  
Section [(139)VB,HB-3]BR,139R  
Kankakee County  
Contract No. 66F74  
Item No. 161, January 21, 2022 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 21 of the Special Provisions.
2. Revised sheet 220 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

### **REMOVE EXISTING FLARED END SECTION**

Description. This work shall consist of the removal and disposal of flared end sections at locations shown on the plans, in accordance with the applicable portions of Section 551 of the Standard Specification, and as directed by the Engineer.

Method of Measurement. Removal and disposal of existing flared end sections will be measured for payment in units of EACH at the locations designated on the plans.

Basis of Payment. The work shall be paid for at the contract unit price EACH for REMOVE EXISTING FLARED END SECTION.

### **RELOCATE EXISTING FLARED END SECTION**

Description. This work shall consist of the removal, storage, and reinstallation of existing flared end sections at the locations described in the plans and as directed by the Engineer.

Construction. Removal of the existing end sections shall be in accordance with the applicable sections of Section 551 of the Standard Specifications. Installation of the existing end section at locations as described in the plans shall be in accordance with the applicable sections of Section 550 of the Standard Specifications. If the existing end section is damaged during removal or storage, the Contractor shall replace it with a new end section at their own expense.

Method of Measurement. This work will be measured for payment in units of EACH.

Basis of Payment: The work shall be paid for at the contract unit price EACH for RELOCATE EXISTING FLARED END SECTION.

### **REMOVE HIGH TENSION CABLE MEDIAN BARRIER AND TERMINALS**

Description. This work shall consist of furnishing all equipment, materials, and labor required for the removal and satisfactory disposal of the existing high-tension cable median barrier (HTCMB) and HTCMB terminals.

The existing cable median barrier and its terminals shall be removed in their entirety. All material shall be removed from the right of way and become the property of the contractor. Resulting holes shall be properly backfilled and tamped to the satisfaction of the Engineer.

During the removal process, at no cost to the Department, when tension is removed from the existing cable, 12-inch wide vertical barricades (verticades) or drums shall be placed at the edge of shoulder on 250-foot centers until new cable median barrier and terminals are in place. However, if other traffic control is in place for other work, the vertical barricades or drums will not be required.

Revised January 11, 2022