

Δ 0042

100% CITY

### SUMMARY OF QUANTITIES

\*\* PPS 6-00571-0000, 3P, STA 2260+37.05 TO STA 2461+41.57= STA 16+83.00  
 \*\*\* PPS 6-73370-0000, NEW CONSTRUCTION / RE-CONSTRUCTION, STA 16+83.00 TO STA 100+60.00  
 \*\*\*\* PPS 6-00674-0000, 3P, STA 100+60.00 TO STA 237+19.16, US 67 STA 151+34.00 TO 171+21.00

STP - RURAL - STATE

NHPP-STATE STP-STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	PIKE **	PIKE ***	PIKE ***	MORGAN ***				MORGAN ****	MORGAN ****	MORGAN ****	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED / 20% STATE				80% FED 20% CITY	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% CITY
				ROADWAY 0005	ROADWAY 0001	MC GEE CREEK BRIDGE SN 075-0128 0014	ROADWAY 0001	ILLINOIS RIVER BRIDGE SN 069-0525 0010	WASHINGTON ST BRIDGE SN 069-0522 0008	RET WALL SN 069-7900 SN 069-7901 0040	SIDEWALK 0021	ROADWAY 0005	ROADWAY 0005	SIDEWALK 0021
50201124	COFFERDAM (TYPE 2) (LOCATION - 4)	EACH	1					1						
50201125	COFFERDAM (TYPE 2) (LOCATION - 5)	EACH	1					1						
50201126	COFFERDAM (TYPE 2) (LOCATION - 6)	EACH	1					1						
50300225	CONCRETE STRUCTURES	CU YD	8,459.2			108.7	200.8	8,026.3	123.4					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	4,557.8			366.5		3,425.7	292.5	473.1				
50300260	BRIDGE DECK GROOVING	SO YD	11,796.1			897.1		10,183	716					
50300265	SEAL COAT CONCRETE	CU YD	3,979.0				103.0	3,876.0						
50300280	CONCRETE ENCASEMENT	CU YD	22.3			14.1		8.2						
50300300	PROTECTIVE COAT	SO YD	15,619			1,114	28	12,571	851	1,055				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			0.020		0.967	0.013					
50500505	STUD SHEAR CONNECTORS	EACH	36,039			3,600		29,550	2,889					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,492,950			98,990	53,540	2,188,870	85,400	66,150				
50800515	BAR SPLICERS	EACH	854			649		89	116					
50800530	MECHANICAL SPLICERS	EACH	1,012					1,012						

Rev. 1-7-15

\P\2014\12\15\100% CITY\100% CITY\SHEET 8 OF 12

FILE NAME *	USER NAME * #USER#	DESIGNED - JB	REVISED -
#FILE#		DRAWN - MDN	REVISED -
exp U.S. Services Inc.		CHECKED - MD	REVISED -
PLDT SCALE * #SCALE#		DATE - 8/5/2014	REVISED -
PLDT DATE * #DATE#			

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**  
 FAP ROUTE 745 / IL ROUTE 104

SUMMARY OF QUANTITIES 8	
SCALE:	SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
745	10SR5-6, 123RS-3, *	MORGAN/PIKE	782	12
* 123B-2, 124RS-8		CONTRACT NO.	72858	
ILLINOIS FED. AID PROJECT				