

COOK COUNTY EASTBOUND SIGN SCHEDULE

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1 (SQ FT)	REMOVE SIGN PANEL-TYPE 2 (SQ FT)	REMOVE SIGN PANEL-TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REMOVAL OF SIGN LIGHTING, NO SALVAGE (EACH)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)											
EB-PM-32B	354+50	TRUCKS - USE - RIGHT - 2 - LANES	4.0	5.0	4.0	5.0											
EB-WP-32C	361+79	W4-1R	4.0	4.0	4.0	4.0		20.0							18.0		
EB-PM-32D	372+34	R2-1 (55 MPH)	4.0	5.0	4.0	5.0		20.0					20.0				
EB-CL-33	378+80	EXITS 14A-B - ST CHARLES RD - 3/4 MILE	19.0	8.5	19.0	8.5			161.5					161.5			1.0
EB-PM-33A1	380+23	M3-2	2.5	1.3	2.5	1.3	3.1					3.1					
EB-PM-33A2	380+23	M1-1-3 (I 290)	PER MUTCD STD (9FT ²)		PER MUTCD STD (9FT ²)		9.0					9.0					
EB-CL-34	394+40	"EXIT 14A - WEST - ST CHARLES RD - 1/4 MILE - TRUCKS PROHIBITED"	19.0	12.0	19.0	12.0			228.0					228.0			1.0
EB-TR-35	401+40	"EXIT 15A - I 294 SOUTH TOLLWAY - INDIANA - RIGHT 3/4 MILE"	13.0	12.0	13.0	12.0			156.0					156.0			1.0
EB-TR-36	401+40	EXIT 14B - EAST - ST CHARLES RD - 1/4 MILE	19.0	12.0	19.0	12.0			228.0					228.0			1.0
EB-TR-37	401+40	EXIT 14A - WEST - ST CHARLES RD	23.0	12.0	19.0	12.0		276.0						228.0			1.0
EB-TS-37A	406+11	W13-3 (30 MPH)	3.0	4.0	4.0	5.0						20.0			18.0		
EB-WP-38	407+60	EXIT - 14A	7.5	5.0	7.0	5.0							35.0	36.0			
EB-WP-38A	411+76	W4-1R	4.0	4.0	4.0	4.0							16.0	18.0			
EB-BM-39	414+30	EXIT 14B - EAST - ST CHARLES RD	20.5	8.0	20.5	8.0		164.0					164.0				1.0
EB-TS-39A	417+77	W13-3 (30 MPH)	3.0	4.0	4.0	5.0						20.0			18.0		
EB-WP-40	418+20	EXIT - 14B	7.5	5.0	7.0	5.0							35.0	36.0			
EB-WP-40A	421+32	W4-1R	4.0	4.0	4.0	4.0							16.0	18.0			
EB-TS-40B1	431+44	M3-2	2.5	1.3	2.5	1.3			1.0			3.1				18.0	
EB-TS-40B2	431+44	M1-1-3 (I 290)	PER MUTCD STD (9FT ²)		PER MUTCD STD (9FT ²)					1.0		9.0					
EB-CL-41	433+40	TO I 88 WEST TOLLWAY - AURORA - EXIT 15A	14.5	9.5	14.5	9.5			137.8					137.8			1.0
EB-CL-42	437+40	EXIT 15A - I 294 SOUTH TOLLWAY - INDIANA - 1/8 MILE	14.5	16.0	14.0	12.5			232.0					175.0			1.0
EB-TR-43	445+40	I 290 EAST - CHICAGO	17.0	10.5	17.0	10.5			178.5					178.5			1.0
EB-TR-44*	445+40	EXIT 17 - 12 20 45 - MANNHEIM RD - 1 MILE - EXIT ONLY	17.5	15.0	17.5	15.0			262.5					262.5			1.0
EB-TR-45*	445+40	EXIT 15A - I 294 SOUTH TOLLWAY - INDIANA	14.0	10.5	14.0	10.5		147.0						147.0			1.0
EB-WP-46	447+90	EXIT - 15A	7.5	5.0	7.0	5.0							35.0	36.0			
EB-WP-46A	457+02	W4-1R	4.0	4.0	4.0	4.0							16.0	18.0			
EB-CL-47	468+60	EXIT 17 - 12 20 45 - MANNHEIM RD - EXIT ONLY	17.0	12.0	17.5	12.0		204.0						210.0			1.0
EB-TS-47A	486+00	R3-5R	4.0	5.0	4.0	5.0							20.0			18.0	
EB-TS-47B1	486+00	R3-4	4.0	4.0	4.0	4.0							16.0			18.0	
EB-TS-47B2	486+00	EXCEPT - AUTHORIZED - VEHICLES	4.0	2.7	4.0	2.7							10.6				
COOK COUNTY EASTBOUND SUBTOTAL							13	40	2375	2	12	25	191	2381	180	90	12


MILE POST MARKER ASSEMBLY - DUPAGE COUNTY

DIRECTION	EACH
EASTBOUND	4
WESTBOUND	4
TOTAL	8

MILE POST MARKER ASSEMBLY - COOK COUNTY

DIRECTION	EACH
EASTBOUND	5
WESTBOUND	5
TOTAL	10

*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -	 LIN ENGINEERING, LTD. Consulting Engineers Chatham, Illinois Westmont, Illinois	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL	DRAWN - SEW	REVISED -						290	2009-099BR	COOK/DUPAGE	394	313
USER NAME = #USER*	CHECKED - FML	REVISED -			SCALE: N.T.S. SHEET NO. 4 OF 4 SHEETS STA. TO STA.			CONTRACT NO. 60157				
PLOT DATE = #DATE*	DATE - 12/2009	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							