SIGN DETAIL

1:75

EB-TR-35
STA. 401+40

FONT:
(1) ClearviewHwy-5-W
(2) ClearviewHwy-5-W-R

SIGN NUMBER	name
WIDTH x HGHT.	13'-0" x 12'-0"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	12.2	66	45	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)											LENGTH	SERIES-SIZE
E	X	I	T	1	5	A						ClearviewHwy-5-W
55.9	66.1	79.8	85.7	104.4	116.3	130.4					88.6	12,15
S	O	U	T	H								ClearviewHwy-5-W
73.6	88.3	103.7	116.6	128.8							64.4	15,12
T	O	L	L	W	A	Y						ClearviewHwy-5-W-R
67.1	76.3	88.5	97	104.4	118.9	129.3					70.9	10
I	n	d	i	a	n	a						ClearviewHwy-5-W-R
32.6	41	56.5	72.9	80.4	96.4	111.6					90.8	1613
R	I	G	H	T	3/4	M	I	L	E			ClearviewHwy-5-W
11.3	24.4	31	45.7	58.4	79.1	110.3	123.4	129.3	138.4		133.5	12,15,10

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING,LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 12 OF 58 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2009-099BR	COOK/DUPAGE	394	340
		CONTRACT NO. 60157		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		