SIGN DETAIL

1:75

EB-BM-72
STA. 672+30

FONT:
(1) ClearviewHwy-5-W
(2) ClearviewHwy-5-W-R

SIGN NUMBER	name
WIDTH x HGHT.	20'-6" x 9'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1-1100A-2-22-10(2)		23.1	34.2	39.3	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)																																		LENGTH	SERIES/SIZE
L	E	F	T																																ClearviewHwy-5-W
18	28.8	40.5	50.6																															41.2	12
E	X	I	T	2	1	B																													ClearviewHwy-5-W
70.1	80.4	94.1	100	118.6	132.8	145.5																												86.8	12,15
H	a	r	l	e	m		A	v	e																										ClearviewHwy-5-W-R
78.4	94.9	110.9	121.9	130.1	146.3	164.4	179.9	196.4	211.1																									144.5	16/13
L	E	F	T																																ClearviewHwy-5-W
54.6	65.4	77.1	87.2																															41.2	12
1	¾	M	I	L	E	S																													ClearviewHwy-5-W
110.8	122.6	153.8	166.9	172.8	181.9	190.8																												87.2	15,10

FILE NAME =	DESIGNED - SEW	REVISED -	
$FILEL$	DRAWN - SEW	REVISED -	
USER NAME = $USER$	CHECKED - FML	REVISED -	
PLOT DATE = $DATE$	DATE - 1/25/10	REVISED -	

LIN ENGINEERING,LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 1 OF 34 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3131, ETC., 3435) RS-6	COOK	215	133
		CONTRACT NO. 60K10		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		