

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	TRAFFIC SIGNS	SURVEILLANCE	
					90% FED 10% STATE	SN 016-0084 SN 016-0095	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
					URBAN				
					CONSTRUCTION TYPE CODE				
					I000-2A	X271-2A	Y002-1C	Y032-1F	
	44213000	PATCHING REINFORCEMENT	SQ YD	1,506	1,506				
	44213200	SAW CUTS	FOOT	1,099	1,099				
	48300100	PORTLAND CEMENT CONCRETE SHOULDERS 6"	SQ YD	60	60				
	50102400	CONCRETE REMOVAL	CU YD	47.0		47.0			
	50157300	PROTECTIVE SHIELD	SQ YD	191		191			
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	47.0		47.0			
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,860		4,860			
	50800515	BAR SPLICERS	EACH	44		44			
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	288.0		288.0			
Δ	55039700	STORM SEWERS TO BE CLEANED	FOOT	1,560	1,560				
	58700300	CONCRETE SEALER	SQ FT	50,652		50,652			
	60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	142.5	142.5				
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	142.5	142.5				
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3,420	3,420				
*	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' ^{FOOT} POSTS	FOOT	250	250				
*	63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	25	25				
*	63100041	TRAFFIC BARRIER TERMINAL, TYPE 1B	EACH	1	1				
*	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1				
	63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	25	25				
	64200105	SHOULDER RUMBLE STRIP	FOOT	65,713	65,713				
	67100100	MOBILIZATION	L SUM	1	1				
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	31	31				
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,867	3,867				
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,400	2,400				
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2,749	2,749				
*	72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	62			62		
*	72000205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	935			935		
*	72000305	SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	5,295			5,295		
*	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	6			6		
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	288			288		
*	73000105	WOOD SIGN SUPPORT, SPECIAL	FOOT	486			486		
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	391	391				
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	42,267	42,267				
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	542	542				
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	25,246	25,246				

Δ NON-PARTICIPATING
 • SPECIALTY ITEMS
 ** FOR LOCATIONS AND EXTENT OF WORK NOT SHOWN IN THE PLANS, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND CONTACT RICK WANNER, ROADSIDE DEVELOPMENT ARCHITECT, IDOT ROADSIDE DEVELOPMENT UNIT AT (847) 705-4172 AT LEAST 72 HOURS PRIOR TO STARTING WORK.