

## INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-5	TRAFFIC STAGING PLAN
6-15	BRIDGE REPAIR PLANS (SN 016-0235)
16	FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-8)
17	SINGLE AND MULTI-LANE WEAVE (TC-9)
18	TRAFFIC CONTROL FOR SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)
19	ARTERIAL ROAD INFORMATION SIGN (TC-22)

## LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' to 24" FROM PAVEMENT EDGE
701301-04	LANE CLOSURE 2L, 2W SHORT TIME OPERATIONS
701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-06	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-07	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > 45 MPH
701446-02	TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
701606-07	URBAN LANE CLOSURE, MULTILANE, <del>1W OR 2W</del> <b>MOUNTABLE MEDIAN WITH NONTRAVERSABLE MEDIAN</b>
701801-04	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
704001-06	TEMPORARY CONCRETE BARRIER

## GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "C.U.A.N." (CHICAGO UTILITY ALERT NETWORK) AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF CHICAGO.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

CONCRETE SUPERSTRUCTURE SHALL HAVE A SEVEN DAY MINIMUM CURE.

SLIPFORMING OF PARAPETS IS NOT ALLOWED.

ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 (FOR ARTERIALS) AND (847) 705-4151 (FOR EXPRESSWAYS) A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

THE "ARTERIAL ROAD INFORMATION SIGN (TC-22)" IS APPLICABLE ONLY TO ARTERIAL ROADS AND SHALL NOT BE APPLIED TO EXPRESSWAYS.

THE CONTRACTOR SHALL PROVIDE TEMPORARY ADA ACCESSIBLE RAMPS TO BE USED WITH STANDARD 701801. RAMP DETAILS SHALL BE APPROVED BY THE ENGINEER. COST OF RAMPS ARE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION (SPECIAL).

FILE NAME =	USER NAME = gorengautab	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>OGDEN AVE. OVER I-290 (EISENHOWER EXPRESSWAY) INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pe_work\p1dot\gorengautab\0213343\178218-sht-plen.dgn	DRAWN -	REVISED -	3542			2010-066-1	COOK	19	2	
PLOT SCALE = 1/8" = 1' IN.	CHECKED -	REVISED -	<b>CONTRACT NO. 60L48</b>							
PLOT DATE = 11/24/2018	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.