

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	1
		ILLINOIS	CONTRACT NO. 80B13	

FOR INDEX OF SHEETS AND HIGHWAY STANDARDS, SEE SHEET NO. 2

THIS PROJECT IS LOCATED IN THE CITY OF JOLIET


PROPOSED
HIGHWAY PLANS

FAP ROUTE 112: IL 53 (BROADWAY STREET)
BLUFF STREET TO TEALE WOODS TRAIL (SOUTH OF ILL 7)
SECTION: 2025-1086-RS
PROJECT: NHPP-B61R(764)
STANDARD OVERLAY, ADA IMPROVEMENTS
WILL COUNTY

TRAFFIC DATA

2023 ADT BROADWAY ST (RUBY ST TO TEALE WOODS TRAIL) = 16,200 VPD
2023 ADT RUBY ST (BROADWAY ST TO BLUFF ST) = 21,300 VPD
POSTED SPEED LIMIT = 30 MPH - 35 MPH
OTHER PRINCIPAL ARTERIAL

C-91-246-25



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.


J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1-800-892-0123
OR 811

PROJECT ENGINEER: VESELIN VELICHKOV (847) 705-4432
PROJECT MANAGER: FAWAD AQUEEL

CONTRACT NO. 80B13

PROJECT ENDS
STA 70+04

PROJECT BEGINS
STA 13+75



GROSS LENGTH = 5,629 FT. = 1.07 MILE
NET LENGTH = 5,629 FT. = 1.07 MILE



Alexander Lane
ALEXANDER CARL LANE, P.E.
R. LIC. NO. 062-063261
EXP: 11/30/2027
DATE: 12/9/2025

INFRASTRUCTURE
ENGINEERING | INCORPORATED
1 South Wacker | Suite 2650 | Chicago, IL 60606
P 312.421.1560 | F 312.421.5564 | www.infrastructure-eng.com
CONTACT: ALEXANDER LANE (312) 477-0620

PRINTED BY THE AUTHORITY
OF THE STATE OF ILLINOIS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
SUBMITTED Dec 4th 2025
Jesse R. K... IR
REGIONAL ENGINEER
January 23 2026
S... E...
ENGINEER OF DESIGN AND ENVIRONMENT
January 23 2026
D...
DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5-6	TYPICAL SECTIONS
7-9	ROADWAY AND PAVEMENT MARKING PLANS
10-22	ADA RAMP DETAILS
23-29	TS-05: STANDARD TRAFFIC SIGNAL DESIGN DETAILS
30	TS-07: DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING
31-36	TRAFFIC SIGNALS - IL 53 (BROADWAY ST)
37	BD-08: DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
38	BD-22: PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
39	BD-24: CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
40	BD-32: BUTT JOINT AND HMA TAPER DETAILS
41	BD-33: HMA TAPER AT EDGE OF P.C.C PAVEMENT
42	PD-01: PROJECT DETAILS FOR SINGLE PREPENDICULAR CURB RAMPS
43	PD-02: PROJECT DETAILS FOR SINGLE PREPENDICULAR CURB RAMPS
44	PD-04: PROJECT DETAILS FOR SINGLE PREPENDICULAR CURB RAMPS
45	TC-10: TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
46	TC-11: TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
47	TC-13: TYPICAL PAVEMENT MARKINGS
48	TC-14: TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
49	TC-16: SHORT TERM PAVEMENT MARKING LETTERS AND SYMBOLS
50	TC-22: ARTERIAL ROAD INFORMATION SIGN
51	TC-26: DRIVEWAY ENTRANCE SIGNING

HIGHWAY STANDARDS

STANDARD NO.	DRAWING NAME
000001-09	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
424001-12	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
424006-06	DIAGONAL CURB RAMPS FOR SIDEWALKS
442201-04	CLASS C AND D PATCHES
606001-09	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701101-05	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 M) TO 24' (600 MM) FROM PAVEMENT EDGE
701427-05	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS ≤ 40 MPH
701602-10	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701606-10	URBAN SINGLE LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701611-01	URBAN HALF ROAD CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-10	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-06	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-11	TRAFFIC CONTROL DEVICES
780001-05	TYPICAL PAVEMENT MARKINGS
781001-04	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
886001-01	DETECTOR LOOP INSTALLATIONS
886006-01	TYPICAL LAYOUTS FOR DETECTION LOOPS

GENERAL NOTES

1. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
2. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO BEGINNING CONSTRUCTION AND ORDERING MATERIALS.
3. THE CONTRACTOR SHALL CONTACT KALPANA KANNAN-HOSADURGA, THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT KALPANA.KANNAN-HOSADURGA@ILLINOIS.GOV A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
4. TEN (10) FOOT TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURBS AND GUTTER AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN.
5. ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
6. LOCATION OF COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT [OR COMBINATION CURB AND GUTTER (THE TYPE SPECIFIED ON THE PLANS)], WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
7. DRAINAGE ADJUSTMENT OR RECONSTRUCTION LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
8. FRAMES AND GRATES ADJUSTMENT OF PRIVATE UTILITIES WITHIN THE LIMITS OF THE IMPROVEMENTS SHALL BE DONE BY THEIR RESPECTIVE OWNERS AND ARE NOT PART OF THIS CONTRACT.
9. THE CONTRACTOR SHALL BE REQUIRED TO KEEP A RECORD OF THE LOCATIONS OF THE BURIED STRUCTURES ACCORDING TO THE STATION AND DISTANCE LEFT OR RIGHT OF THE CENTERLINE OF PAVEMENT. UPON COMPLETION OF THE WORK, THE CONTRACTOR SHALL DELIVER THE RECORD TO THE ENGINEER.
10. EXISTING BROKEN FRAMES AND LIDS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND LIDS WILL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.
11. PAVEMENT MARKING TAPE, TYPE IV SHALL BE USED FOR SHORT TERM PAVEMENT MARKINGS ON ALL FINAL SURFACES.
12. THE RESIDENT ENGINEER SHALL CONTACT ERIC CAMPOS, AREA TRAFFIC FIELD ENGINEER, VIA EMAIL AT ERIC.CAMPOS@ILLINOIS.GOV A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
13. BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXISTING LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE SHOWN ON THE PLANS OR AS DIRECTED BY THE RESIDENT ENGINEER.
14. OVERNIGHT LANE CLOSURES SHALL NOT BE ALLOWED FOR REHABILITATION PROJECTS INVOLVING DAYTIME MILLING AND RESURFACING OPERATIONS AND CLASS D PATCHING UNLESS OTHER CONDITIONS WARRANT EXTENDED LANE CLOSURES AS DETERMINED AND APPROVED IN WRITING BY THE RESIDENT ENGINEER OR AS PROVIDED IN THE CONTRACT SPECIFICATIONS.
15. ALL MILLED SURFACES SHALL BE A UNIFORM CROSS SLOPE PER LANE AND FREE OF RIDGES BETWEEN PASSES. ANY DEVIATIONS SHALL BE CORRECTED AT NO COST TO THE DEPARTMENT.
16. THE "ROAD CONSTRUCTION AHEAD" SIGNS SHALL REMAIN INSTALLED UNTIL THE COMPLETION OF THE PROJECT OR WHEN NO ROADWAY HAZARDS REMAIN WITHIN THE WORK ZONE.
17. TEMPORARY PAVEMENT MARKINGS OR SHORT TERM PAVEMENT MARKINGS ON INTERMEDIATE SURFACES SHALL NOT BE REMOVED UNLESS DIRECTED BY THE ENGINEER.

MODEL: Default
FILE NAME: P:\P-2022-4675-00 (DOT Various Phase 2 (PTB 208-002))\WO 34 80B13\03\GNV\CADD_Sheets\80B13-SHT-GENNOTES.dgn

<div><div>INFRASTRUCTURE ENGINEERING INCORPORATED</div><div>1 South Wacker Suite 2650 Chicago, IL 60606 P 312.425.9560 F 312.425.9564 www.infrastructure-eng.com</div></div>	USER NAME = ALane	DESIGNED - HA	REVI SED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET NO.	
		DRAWN - HA	REVI SED -			1 2	2025-1086-RS	WILL	51	2
		CHECKED - ACL	REVI SED -			CONTRACT NO. 80B13				
	PLOT DATE = 12/1/2025	DATE = 09/12/2025	REVI SED -			ILLINOIS FED. AID PROJECT				
	SCALE: NTS		SHEET 1 OF 1 SHEETS			STA. TO STA.				

MODEL: Default
FILE NAME: P:\P-22\22-4675-00\DOT Various Phase 2 (PTB 205-002)\WO 34 80B13\DGNCADD Sheets\80B13-SHT-SQC-01.dgn

				CONSTRUCTION CODE			
				0005 ROADWAY		0021 TRAFFIC SIGNAL	
PAY ITEM NUMBER	DESIGNATION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STA TE	100% STA TE	80% FEDERAL 20% STA TE	
20200100	EARTH EXCAVATION	CU YD	55	55			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	86	86			
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3		
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3		
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3		
	25100630	EROSION CONTROL BLANKET	SQ YD	109	109		
*	25200110	SODDING, SALT TOLERANT	SQ YD	86	86		
*	25200200	SUPPLEMENTAL WATERING	UNIT	5	5		
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25	25		
	35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	6	6		
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	18,853	18,853		
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	17,153	17,153		
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	41	41		
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	67	67		
	40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	165	165		
	40602985	HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70	TON	334	334		
	40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	TON	1,328	1,328		
	40604172	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N70	TON	2,658	2,658		
	42001300	PROTECTIVE COAT	SQ YD	1,204	1,204		
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5,229	5,229		
	42400800	DETECTABLE WARNINGS	SQ FT	302	302		
	44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	2,980	2,980		
	44000600	SIDEWALK REMOVAL	SQ FT	5,108	5,108		

* = SPECIALTY ITEM

				CONSTRUCTION CODE			
				0005 ROADWAY		0021 TRAFFIC SIGNAL	
PAY ITEM NUMBER	DESIGNATION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STA TE	100% STA TE	80% FEDERAL 20% STA TE	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	24	24			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	621	621			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	162	162			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,500	1,500			
56109210	WATER VALVES TO BE ADJUSTED	EACH	5	5			
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3			
60266600	VALVE BOXES TO BE ADJUSTED	EACH	7	7			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7			
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	55	55		
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2		
*	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1		
*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1		
*	66901006	REGULATED SUBSTANCES MONITORING	CAL DA	12	12		
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	23,846	23,846			
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	4,908	4,908			
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	182	182			
70300221	TEMPORARY PAVEMENT MARKING - LINE 4" - PAINT	FOOT	37,659	37,659			
70300241	TEMPORARY PAVEMENT MARKING - LINE 6" - PAINT	FOOT	581	581			

 <div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312 425 9560 F 312 425 9564 www.infrastructure-eng.com</div>	USER NAME = ALane	DESIGNED - HA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - HA	REVISED -					112	2025-1086-RS	WILL	51	3
		CHECKED - ACL	REVISED -		SCALE: NTS			SHEET 1 OF 2 SHEETS			CONTRACT NO. 80B13	
	PLOT DATE = 12/1/2025	DATE - 09/12/2025	REVISED -		STA. TO STA.			ILLINOIS FED. AID PROJECT				

MODEL: Default
FILE NAME: P:\P-22\22-4675-00\DOT Various Phase 2 (PTB 205-002)\WO 34 80B13\0GNCADD_Sheets\80B13-SHT-SOC-02.dgn

				CONSTRUCTION CODE			
				0005 ROADWAY		0021 TRAFFIC SIGNAL	
PAY ITEM NUMBER	DESIGNATION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STA TE	100% STA TE	80% FEDERAL 20% STA TE	
70300251	TEMPORARY PAVEMENT MARKING - LINE 8"- PAINT	FOOT	98	98			
70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	3,316	3,316			
70300281	TEMPORARY PAVEMENT MARKING - LINE 24"- PAINT	FOOT	896	896			
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	14,722	14,722			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12,553	12,553			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	194	194			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	572	572			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,106	1,106			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	299	299			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	298	298			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	298	298			
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA	FOOT	144			144	
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4			4	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2,756			2,756	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	940			940	
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	190			190	
* 87900200	DRILL EXISTING HANDHOLE	EACH	19			19	
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	16			16	
* 89500200	RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	1			1	
* 89502200	MODIFY EXISTING CONTROLLER	EACH	4			4	
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	616			616	
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	3			3	


* = SPECIALTY ITEM

				CONSTRUCTION CODE			
				0005 ROADWAY		0021 TRAFFIC SIGNAL	
PAY ITEM NUMBER	DESIGNATION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STA TE	100% STA TE	80% FEDERAL 20% STA TE	
* 89502376	REBUILD EXISTING HANDHOLE	EACH	14			14	
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1			
X0327611	REMOVE AND REINSTALL BRICK PAVER	SQ FT	391	391			
* X1400367	PEDESTRIAN SIGNAL POST, 10 FT.	EACH	2			2	
* X1400378	PEDESTRIAN SIGNAL POST, 5 FT.	EACH	17			17	
X2010350	TREE REMOVAL, ACRES (SPECIAL)	ACRE	1.9	1.9			
X2100002	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	UNIT	5.5	5.5			
X4060995	TEMPORARY RAMP (SPECIAL)	SQ YD	422	422			
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	7,110	7,110			
X4400501	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET	FOOT	833	833			
X4400503	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT GREATER THAN 10 FEET	FOOT	1,036	1,036			
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1,200		1,200		
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50			
X6700407	ENGINEER'S FIELD OFFICE, TYPE A (D1)	CAL MO	12	12			
X7200061	TEMPORARY INFORMATION SIGNING	SQ FT	129	129			
* X8760200	ACCESSIBLE PEDESTRIAN SIGNALS	EACH	34			34	
* X8780012	CONCRETE FOUNDATION, TYPE A 12-INCH DIAMETER	FOOT	76			76	
* X8860105	DETECTOR LOOP REPLACEMENT	FOOT	1,334			1,334	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	80		80		
* Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	4			4	
Ø Z0076600	TRANEES	HOURL	500	500			
Ø Z0076604	TRANEES - TRAINING PROGRAM GRADUATE	HOURL	500	500			

0042


	USER NAME = ALane	DESIGNED - HA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - HA	REVISED -					112	2025-1086-RS	WILL	51	4
		CHECKED - ACL	REVISED -					CONTRACT NO. 80B13				
	PLOT DATE = 12/1/2025	DATE - 09/12/2025	REVISED -					ILLINOIS FED. AID PROJECT				
SCALE: NTS		SHEET 2 OF 2 SHEETS		STA.		TO STA.						

MODEL: Default
FILE NAME: P:\P-22-222-4675-00 IDOT Various Phase 2 (PTB 2025-02)\WO 34 80B13\DNVCADD_Sheets\80B13-SHT-TYPICAL-01.dgn




EXISTING TYPICAL CROSS SECTION

HMA RESURFACING
STA. 13+74 TO STA. 15+55




EXISTING TYPICAL CROSS SECTION

HMA RESURFACING
STA. 15+55 TO STA. 19+12



PROPOSED TYPICAL CROSS SECTION

HMA RESURFACING
STA. 13+74 TO STA. 15+55



PROPOSED TYPICAL CROSS SECTION

HMA RESURFACING
STA. 15+55 TO STA. 19+12

LEGEND

- (A) EXISTING HOT-MIX ASPHALT, +/- 11-1/2"
- (B) EXISTING P.C.C. BARE SURFACE COURSE, +/- 12"
- (C) EXISTING P.C.C. BASE COURSE, +/- 10"
- (D) EXISTING AGGREGATE BASE COURSE, +/- 4"
- (E) EXISTING SUB-BASE GRANULAR MATERIAL, VARIES
- (F) EXISING COMBINATION CONCRETE CURB AND GUTTER
- (G) PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VAR. DEPTH)
- (1) POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N70, 1 3/4"
- (2) HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70, 2"
- (3) POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50, 1"

PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VAR. DEPTH)

HOT-MIX ASPHALT REMOVAL, 3 3/4"

NOTES:

- THE CONTRACTOR SHALL PATCH BEFORE MILLING.
- THE LONGITUDINAL JOINT SEALANT SHALL BE PLACED UNDER HOT-MIX ASPHALT SURFACE COURSE.





* REFER TO DESIGN DETAIL BD-33, HMA TAPER AT EDGE OF PCC PAVEMENT FOR TRANSITION AT EXISTING CURB AND GUTTER.

HOT-MIX ASPHALT MIXTURE REQUIREMENTS		QUALITY MANAGEMENT PROGRAM (QMP)
MIXTURE TYPE	AIR VOIDS @ Ndes	
STANDARD OVERLAY - FIRST HMA OVERLAY ON BARE PCC PAVEMENT		
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N70 1-3/4"	4% @ 70 GYR	QCP
POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50 1"	3.5% @ 50 GYR	QC/QA
DESIGNED OVERLAY - OVER HMA PAVEMENT		
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N70 1-3/4"	4% @ 70 GYR	QCP
HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70 2"	4% @ 70 GYR	QC/QA
PATCHING		
CLASS D PATCHES (HMA BINDER IL-19 mm)	4.0% @ 70 GYR	QC/QA
TEMPORARY RAMP, SPECIAL		
HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70, VARIABLE DEPTH	4.0% @ 70 GYR	QC/QA
QMP DESIGNATION: QUALITY CONTROL / QUALITY ASSURANCE (QC/QA): QUALITY CONTROL FOR PERFORMANCE (QCP): PAY FOR PERFORMANCE (PFP)		

MIXTURE REQUIREMENT NOTES:

- THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN.
- THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76 -22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64 -22" UNLESS MODIFIED BY RECLAIMED MATERIALS SPECIFICATIONS.

<div></div> <div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com</div>	USER NAME = ALane	DESIGNED - HA	REVISED -	<div>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</div>	<div>TYPICAL SECTIONS IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL</div>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - HA	REVISED -					112	2025-1086-RS	WILL	51	5
		CHECKED - ACL	REVISED -					CONTRACT NO. 80B13				
	PLOT DATE = 1/6/2026	DATE - 09/12/2025	REVISED -		SCALE: NTS	SHEET 1 OF 2 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				



LEGEND

- (A) EXISTING HOT-MIX ASPHALT, +/- 11-1/2"
(B) EXISTING P.C.C. BARE SURFACE COURSE, +/- 12"
(C) EXISTING P.C.C. BASE COURSE, +/- 10"
(D) EXISTING AGGREGATE BASE COURSE, +/- 4"
(E) EXISTING SUB-BASE GRANULAR MATERIAL, VARIES
(F) EXISING COMBINATION CONCRETE CURB AND GUTTER
(G) PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VAR. DEPTH)
(1) POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N70, 1 3/4"
(2) POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70, 2"
(3) POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50, 1"

PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VAR. DEPTH)

HOT-MIX ASPHALT REMOVAL, 3 3/4"

NOTES:

1. THE CONTRACTOR SHALL PATCH BEFORE MILLING.
2. THE LONGITUDINAL JOINT SEALANT SHALL BE PLACED UNDER HOT-MIX ASPHALT SURFACE COURSE.

* REFER TO DESIGN DETAIL BD-33, HMA TAPER AT EDGE OF PCC PAVEMENT FOR TRANSITION AT EXISTING CURB AND GUTTER.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION


TYPICAL SECTIONS IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL

SCALE: NTS SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	6
CONTRACT NO. 80B13				
ILLINOIS FED. AID PROJECT				

USER NAME = ALane	DESIGNED - HA	REVISED -
	DRAWN - HA	REVISED -
	CHECKED - ACL	REVISED -
PLOT DATE = 12/11/2025	DATE - 09/12/2025	REVISED -

MODEL: Default
FILE NAME: P:\P-22\22-4675-00 IDOT Various Phase 2 (PTB 2016-02)\WO 34 80B13\DNVCADD_Sheets\80B13-SHT-PLAN-01.dgn



PAVEMENT MARKING LEGEND

- | | |
|---|---|
| ① LINE 4", DOUBLE SOLID YELLOW, 2 @ 11" C-C - (TYP) | ⑨ LETTERS & SYMBOLS, SOLID WHITE (TYP) |
| ② LINE 4", SKIP-DASH, WHITE (10' LINE - 30' SPACE) - LANE LINES (TYP) | ⑩ LINE 12", SOLID, YELLOW - MEDIAN DIAGONALS (TYP) |
| ③ LINE 6", SKIP-DASH, WHITE (2' LINE - 6' SPACE) - DOTTED LINES (TYP) | ⑪ LINE 8", SKIP-DASH, WHITE (2' LINE - 6' SPACE) - DOTTED LINES (TYP) |
| ④ LINE 6", SOLID WHITE - CROSSWALK & TURN LANE MARKING (TYP) | |
| ⑤ LINE 8", SOLID, WHITE - GORE LINE (TYP) | |
| ⑥ LINE 12", SOLID, WHITE - MEDIAN DIAGONALS (TYP) | |
| ⑦ LINE 12", SOLID, WHITE - CROSSWALK (TYP) | |
| ⑧ LINE 24", SOLID, WHITE - STOP LINES (TYP) | |

LEGEND



- | | |
|--|----------------------------------|
| | SURFACE REMOVAL BUTT JOINT, 4.5' |
| | - HMA ON RUBY STREET |
| | - PCC ON BROADWAY STREET |

NOTES:

- LIMIT OF RESURFACING ON THE SIDE STREET THROUGHOUT THE PROJECT SHALL BE TO THE RADIUS RETURN, UNLESS OTHERWISE SHOWN ON THE PLANS, OR AS DIRECTED BY THE RESIDENT ENGINEER/TECHNICIAN.
- ALL FINAL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC PAVEMENT MARKINGS (OF THE EXTRUDED TYPE) ON HMA PAVEMENT.
- ALL FINAL PAVEMENT MARKINGS SHALL BE PLACED IN ACCORDANCE WITH TC-13 "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" STANDARD DETAIL.
- ALL RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH TC-11 "TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" STANDARD DETAIL.

<div><div>INFRASTRUCTURE ENGINEERING INCORPORATED</div><div>1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-inc.com</div></div>	USER NAME = ALane	DESIGNED - HA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ROADWAY AND PAVEMENT MARKING PLANS IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - HA	REVISED -		112	2025-1086-RS	WILL	51	7				
		CHECKED - ACL	REVISED -		CONTRACT NO. 80B13								
	PLOT DATE = 12/11/2025	DATE - 09/12/2025	REVISED -		ILLINOIS FED. AID PROJECT								
	SCALE: 1"=50'				SHEET 1 OF 3 SHEETS			STA. TO STA.					

MODEL: Default
FILE NAME: P:\P-22\22-4675-00 DOT Various Phase 2 (PTB 2025-02)\WO 34_80B13\DNVCADD_Sheets\80B13-SHT-PLAN-02.dgn



PAVEMENT MARKING LEGEND

- | | |
|---|---|
| ① LINE 4", DOUBLE SOLID YELLOW, 2 @ 11" C-C - (TYP) | ⑨ LETTERS & SYMBOLS, SOLID WHITE (TYP) |
| ② LINE 4", SKIP-DASH, WHITE (10' LINE - 30' SPACE) - LANE LINES (TYP) | ⑩ LINE 12", SOLID, YELLOW - MEDIAN DIAGONALS (TYP) |
| ③ LINE 6", SKIP-DASH, WHITE (2' LINE - 6' SPACE) - DOTTED LINES (TYP) | ⑪ LINE 8", SKIP-DASH, WHITE (2' LINE - 6' SPACE) - DOTTED LINES (TYP) |
| ④ LINE 6", SOLID WHITE - CROSSWALK & TURN LANE MARKING (TYP) | |
| ⑤ LINE 8", SOLID, WHITE - GORE LINE (TYP) | |
| ⑥ LINE 12", SOLID, WHITE - MEDIAN DIAGONALS (TYP) | |
| ⑦ LINE 12", SOLID, WHITE - CROSSWALK (TYP) | |
| ⑧ LINE 24", SOLID, WHITE - STOP LINES (TYP) | |

LEGEND

- | | |
|--|----------------------------------|
| | SURFACE REMOVAL BUTT JOINT, 4.5' |
| | - HMA ON RUBY STREET |
| | - PCC ON BROADWAY STREET |

NOTES:

- LIMIT OF RESURFACING ON THE SIDE STREET THROUGHOUT THE PROJECT SHALL BE TO THE RADIUS RETURN, UNLESS OTHERWISE SHOWN ON THE PLANS, OR AS DIRECTED BY THE RESIDENT ENGINEER/TECHNICIAN.
- ALL FINAL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC PAVEMENT MARKINGS (OF THE EXTRUDED TYPE) ON HMA PAVEMENT.
- ALL FINAL PAVEMENT MARKINGS SHALL BE PLACED IN ACCORDANCE WITH TC-13 "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" STANDARD DETAIL.
- ALL RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH TC-11 "TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" STANDARD DETAIL.



**INFRASTRUCTURE
ENGINEERING** INCORPORATED
1 South Wacker | Suite 2650 | Chicago, IL 60606
P 312.475.9500 | F 312.475.9594 | www.infrastructure-eng.com

USER NAME	= ALane
DESIGNED	- HA
DRAWN	- HA
CHECKED	- ACL
DATE	- 09/12/2025
PLOT DATE	= 12/11/2025

DESIGNED	- HA
DRAWN	- HA
CHECKED	- ACL
DATE	- 09/12/2025
REVISED	-

REVISED	-
REVISED	-
REVISED	-
REVISED	-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ROADWAY AND PAVEMENT MARKING PLANS
IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL**

SCALE: 1"=50'


SHEET 2 OF 3 SHEETS

STA.

TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	8
CONTRACT NO. 80B13				
ILLINOIS FED. AID PROJECT				

MODEL: Default
FILE NAME: P:\P-22\22-4675-00 DOT Various Phase 2 (PTB 2016-02)\WO 34 80B13\DNVCADD_Sheets\80B13-SHT-PLAN-03.dgn



PAVEMENT MARKING LEGEND

- | | |
|---|---|
| ① LINE 4", DOUBLE SOLID YELLOW, 2 @ 11" C-C - (TYP) | ⑨ LETTERS & SYMBOLS, SOLID WHITE (TYP) |
| ② LINE 4", SKIP-DASH, WHITE (10' LINE - 30' SPACE) - LANE LINES (TYP) | ⑩ LINE 12", SOLID, YELLOW - MEDIAN DIAGONALS (TYP) |
| ③ LINE 6", SKIP-DASH, WHITE (2' LINE - 6' SPACE) - DOTTED LINES (TYP) | ⑪ LINE 8", SKIP-DASH, WHITE (2' LINE - 6' SPACE) - DOTTED LINES (TYP) |
| ④ LINE 6", SOLID WHITE - CROSSWALK & TURN LANE MARKING (TYP) | |
| ⑤ LINE 8", SOLID, WHITE - GORE LINE (TYP) | |
| ⑥ LINE 12", SOLID, WHITE - MEDIAN DIAGONALS (TYP) | |
| ⑦ LINE 12", SOLID, WHITE - CROSSWALK (TYP) | |
| ⑧ LINE 24", SOLID, WHITE - STOP LINES (TYP) | |

LEGEND



- | | |
|--|----------------------------------|
| | SURFACE REMOVAL BUTT JOINT, 4.5' |
| | - HMA ON RUBY STREET |
| | - PCC ON BROADWAY STREET |

NOTES:

- LIMIT OF RESURFACING ON THE SIDE STREET THROUGHOUT THE PROJECT SHALL BE TO THE RADIUS RETURN, UNLESS OTHERWISE SHOWN ON THE PLANS, OR AS DIRECTED BY THE RESIDENT ENGINEER/TECHNICIAN.
- ALL FINAL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC PAVEMENT MARKINGS (OF THE EXTRUDED TYPE) ON HMA PAVEMENT.
- ALL FINAL PAVEMENT MARKINGS SHALL BE PLACED IN ACCORDANCE WITH TC-13 "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" STANDARD DETAIL.
- ALL RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH TC-11 "TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" STANDARD DETAIL.

	INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com	USER NAME = ALane	DESIGNED - HA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ROADWAY AND PAVEMENT MARKING PLANS IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			DRAWN - HA	REVISED -					112	2025-1086-RS	WILL	51	9
			CHECKED - ACL	REVISED -					CONTRACT NO. 80B13				
		PLOT DATE = 12/11/2025	DATE - 09/12/2025	REVISED -		SCALE: 1"=50'	SHEET 3 OF 3 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				

MODEL: D:\inf4
FILE NAME: I:\P\222224875-40 IDOT Various Phase 2 (P\B 205-2023)\MO 34 80813\3DGN\CADD_Sheets\80813-SHT-ADA-CD.dgn



REFERENCE BENCHMARK: 2513, ELEV 581.819

BENCHMARK: X CUT AT SIDEWALK 3.5 FT NORTH FROM CORNER BUILDING NEAR EDGE PARKING LOT (CHURCH)

LOCATION: SW CORNER OF BROADWAY ST AND RUBY ST

LEGEND

XX.XX'	EXISTING LENGTH		
()	EXISTING ELEVATION / SLOPE		
	PROPOSED SIDEWALK		RESET BRICK
	DETECTABLE WARNINGS		
	SIDEWALK REMOVAL REPLACE WITH TOPSOIL AND SOD		
	DEPRESSED CURB AND GUTTER		
	PROPOSED SIDE CURB		
	PAVEMENT PATCHES		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ADA RAMP DETAILS
IL 53 (BROADWAY ST) – BLUFF ST TO TEALE WOODS TRAIL

SCALE: 1"=5'

STA. TO STA.


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	12
CONTRACT NO. 80B13				
ILLINOIS FED. AID PROJECT				

INFRASTRUCTURE
ENGINEERING INCORPORATED
1 South Wacker | Suite 2650 | Chicago, IL 60606
P 312.425.9568 | F 312.425.9568 | www.infrastructure-eng.com

USER NAME	= ALane
DESIGNED	- HA
DRAWN	- HA
CHECKED	- ACL
DATE	- 09/12/2025

REVISED	-
REVISED	-
REVISED	-

PLOT SCALE = 10,0000' / in.



REFERENCE BENCHMARK: 2513, ELEV 581.819

BENCHMARK: X CUT AT SIDEWALK 3.5 FT NORTH FROM CORNER BUILDING NEAR EDGE PARKING LOT (CHURCH)

LOCATION: SW CORNER OF BROADWAY ST AND RUBY ST

LEGEND

XX.XX¹

EXISTING LENGTH

()

EXISTING ELEVATION / SLOPE

103

PROPOSED SIDEWALK

RESET BRICK



DETECTABLE WARNINGS

SIDEWALK REMOVAL REPLACE WITH TOPSOIL AND SOD

DEPRESSED CURB AND GUTTER

PROPOSED SIDE CURB



PAVEMENT PATCHES

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**


ADA RAMP DETAILS
IL 53 (BROADWAY ST) – BLUFF ST TO TEALE WOODS TRAIL

SCALE: 1"=5'

STA.	
------	--


TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	15
		CONTRACT NO. 80B13		
		ILLINOIS	FED. AID PROJECT	



ROSS ST

N BROADWAY ST



REFERENCE BENCHMARK: 2680, ELEV 583.773

BENCHMARK: NE BOLT AT F.H.

LOCATION: AT NW CORNER ROSS ST AND BROADWAY ST

LEGEND

- XX.XX' EXISTING LENGTH
- () EXISTING ELEVATION / SLOPE
- PROPOSED SIDEWALK
- DETECTABLE WARNINGS
- SIDEWALK REMOVAL REPLACE WITH TOPSOIL AND SOD
- DEPRESSED CURB AND GUTTER
- PROPOSED SIDE CURB
- PAVEMENT PATCHES
- RESET BRICK

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ADA RAMP DETAILS
IL 53 (BROADWAY ST) – BLUFF ST TO TEALE WOODS TRAIL

SCALE: 1"=5' STA. TO STA.



F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	16
CONTRACT NO. 80B13				
ILLINOIS FED. AID PROJECT				

MODEL: D:\p14
FILE NAME: P:\R22\22-4875-00 IDOT Various Phase 2 (PTB 205-002)\MO 34 80B13\IDOT\CADD_Sheets\80B13-SHT-AD-Ramp.dgn

**INFRASTRUCTURE
ENGINEERING** INCORPORATED
1 South Wacker | Suite 2650 | Chicago, IL 60606
P 312.425.9568 | F 312.425.9568 | www.infrastructure-eng.com

USER NAME	= ALane
DESIGNED	- HA
DRAWN	- HA
CHECKED	- ACL
DATE	- 09/12/2025
REVISIONS	
REVISED	-
REVISED	-

MODEL: D:\inf4
FILE NAME: P:\P222224875-40 IDOT Various Phase 2 (P2B 205-202)\MO 34 80B13\3D\CNCADD_Sheets\80B13-SHT-ADA-40.dgn



REFERENCE BENCHMARK: 3808, ELEV 587.498

BENCHMARK: NE BOLT AT F.H.



LOCATION: AT SW CORNER OF HUTCHINS ST AND BROADWAY ST

LEGEND

- XX.XX' EXISTING LENGTH
- () EXISTING ELEVATION / SLOPE
- PROPOSED SIDEWALK
- DETECTABLE WARNINGS
- SIDEWALK REMOVAL REPLACE WITH TOPSOIL AND SOD
- DEPRESSED CURB AND GUTTER
- PROPOSED SIDE CURB
- PAVEMENT PATCHES
- RESET BRICK

<div></div> <div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.425.9568 F 312.425.9568 www.infrastructure-eng.com</div>	USER NAME = ALane	DESIGNED - HA	REVISED -	<div>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</div>	<div>ADA RAMP DETAILS IL 53 (BROADWAY ST) – BLUFF ST TO TEALE WOODS TRAIL</div>	<table><tr><td>F.A.U. RTE.</td><td>SECTION</td><td>COUNTY</td><td>TOTAL SHEETS</td><td>SHEET NO.</td></tr><tr><td>112</td><td>2025-1086-RS</td><td>WILL</td><td>51</td><td>18</td></tr><tr><td colspan="3">CONTRACT NO. 80B13</td><td colspan="2"></td></tr><tr><td colspan="2">ILLINOIS</td><td colspan="3">FED. AID PROJECT</td></tr><tr><td colspan="5"></td></tr></table>					F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	112	2025-1086-RS	WILL	51	18	CONTRACT NO. 80B13					ILLINOIS		FED. AID PROJECT							
	F.A.U. RTE.	SECTION	COUNTY			TOTAL SHEETS	SHEET NO.																												
	112	2025-1086-RS	WILL			51	18																												
	CONTRACT NO. 80B13																																		
	ILLINOIS		FED. AID PROJECT																																
PLOT SCALE = 10,0000' / in.	DRAWN - HA	REVISED -																																	
CHECKED - ACL	REVIS	REVIS																																	
DATE - 09/12/2025																																			
SCALE: 1"=5'		STA.		TO STA.																															

MODEL: D:\inf4
FILE NAME: P:\P22\22-4875-00 IDOT Various Phase 2 (P2B 205-002)\MO 34 80B13\3D\GN\CADD_Sheets\80B13-SHT-ADA-10.dgn



REFERENCE BENCHMARK: 3808, ELEV 587.498

BENCHMARK: NE BOLT AT F.H.

LOCATION: AT SW CORNER OF HUTCHINS ST AND BROADWAY ST



NOTE

1. CONTRACTOR TO CORRECT CROSS SLOPE TO LESS THAN 2% WITH CROSSWALK WITH THE MILLING MACHINE.

LEGEND

XX.XX'	EXISTING LENGTH
()	EXISTING ELEVATION / SLOPE
	PROPOSED SIDEWALK
	DETECTABLE WARNINGS
	SIDEWALK REMOVAL REPLACE WITH TOPSOIL AND SOD
	DEPRESSED CURB AND GUTTER
	PROPOSED SIDE CURB
	PAVEMENT PATCHES
	RESET BRICK

	USER NAME = ALane		DESIGNED - HA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ADA RAMP DETAILS		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - HA		CHECKED - ACL	REVISED -		IL 53 (BROADWAY ST) - BLUFF ST TO TEALE WOODS TRAIL		112	2025-1086-RS	WILL	51	19
	PLOT SCALE = 10,0000' / in.		DATE - 09/12/2025	REVISED -		SCALE: 1"=5'		CONTRACT NO. 80B13				
						TO STA.		ILLINOIS FED. AID PROJECT				



REFERENCE BENCHMARK: 3808, ELEV 587.498

BENCHMARK: NE BOLT AT F.H.

LOCATION: AT SW CORNER OF HUTCHINS ST AND BROADWAY ST

<div><div></div><div></div><div></div></div> <div><div>INFRASTRUCTURE ENGINEERING</div><div>INCORPORATED</div><div>1 South Wacker Suite 2550 Chicago, IL 60606 P 312.425.9550 F 312.425.9554 www.infrastructure-eng.com</div></div>	USER NAME = ALane	DESIGNED - HA	REVISED -
	PLOT SCALE = 10,000' / 1in.	DRAWN - ACL	REVISED -
		CHECKED - HCL	REVISED -
		DATE - 09/12/2025	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ADA RAMP DETAILS
IL 53 (BROADWAY ST) – BLUFF ST TO TEALE WOODS TRAIL


SCALE: 1"=5'

STA.	TO STA.
------	---------

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	20
		CONTRACT NO. 80B13		
ILLINOIS		FED. AID PROJECT		

MODEL: D:\p14
FILE NAME: P:\R22\22-4875-00 IDOT Various Phase 2 (P1B 205-002)\MO 34 80813\3D\CADD_Sheets\80813-SHT-ADA-12.dgn

REFERENCE BENCHMARK: 4907, ELEV 588.708
BENCHMARK: NE BOLT AT F.H.
LOCATION: AT SW CORNER OF SMITH AVE AND BROADWAY ST



LEGEND

xx.xx'

EXISTING LENGTH

()

EXISTING ELEVATION / SLOPE

PROPOSED SIDEWALK

DETECTABLE WARNINGS


SIDEWALK REMOVAL REPLACE WITH TOPSOIL AND SOD

DEPRESSED CURB AND GUTTER

PROPOSED SIDE CURB

PAVEMENT PATCHES



RESET BRICK

	USER NAME = ALane	DESIGNED - HA	REVISED -
		DRAWN - HA	REVISED -
	PLOT SCALE = 10,0000" / 1in.	CHECKED - ACL	REVISED -
		DATE - 09/12/2025	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ADA RAMP DETAILS			
IL 53 (BROADWAY ST) – BLUFF ST TO TEALE WOODS TRAIL			
SCALE: 1"=5'		STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	21
CONTRACT NO. 80B13				
ILLINOIS FED. AID PROJECT				



REFERENCE BENCHMARK: 5248, ELEV 590.628

BENCHMARK: NE BOLT AT F.H.

LOCATION: AT NW CORNER OF RUSSELL ST AND BROADWAY ST

LEGEND

xx.xx'

()

EXISTING LENGTH

EXISTING ELEVATION / SLOPE

PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL REPLACE WITH TOPSOIL AND SOD

DEPRESSED CURB AND GUTTER

PROPOSED SIDE CURB

PAVEMENT PATCHES

RESET BRICK

SIDEWALK REMOVAL REPLACE WITH TOPSOIL AND SOD

MODEL: D:\p14

FILE NAME: P:\P22\22-4875-00 IDOT Various Phase 2 (PTB 205-002)\MO 34 80813\3D\CNCADD_Sheets\80813-SHT-ADA-13.dgn

INFRASTRUCTURE ENGINEERING INCORPORATED

1 South Wacker | Suite 2650 | Chicago, IL 60606

P 312.425.9568 | F 312.425.9568 | www.infrastructure-eng.com

USER NAME	= ALane
DESIGNED	- HA
DRAWN	- HA
CHECKED	- ACL
DATE	- 09/12/2025
REVISED	-
REVISED	-
REVISED	-

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

ADA RAMP DETAILS

IL 53 (BROADWAY ST) – BLUFF ST TO TEALE WOODS TRAIL

SCALE: 1"=5'

































































































































STA.

TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	22
CONTRACT NO. 80B13				
ILLINOIS		FED. AID PROJECT		

TRAFFIC SIGNAL LEGEND

(NOT TO SCALE)


ITEM	EXISTING	PROPOSED	ITEM	EXISTING	PROPOSED	ITEM	EXISTING	PROPOSED
CONTROLLER CABINET			HANDHOLE -SQUARE -ROUND			SIGNAL HEAD -(P) PROGRAMMABLE SIGNAL HEAD	 P	 P
COMMUNICATION CABINET			HEAVY DUTY HANDHOLE -SQUARE -ROUND			SIGNAL HEAD WITH BACKPLATE -(P) PROGRAMMABLE SIGNAL HEAD -(RB) RETROREFLECTIVE BACKPLATE	 P RB	 P RB
MASTER CONTROLLER			DOUBLE HANDHOLE			PEDESTRIAN SIGNAL HEAD AT RAILROAD INTERSECTIONS		
MASTER MASTER CONTROLLER			JUNCTION BOX			PEDESTRIAN SIGNAL HEAD WITH COUNTDOWN TIMER		
UNINTERRUPTABLE POWER SUPPLY			RAILROAD CANTILEVER MAST ARM			ILLUMINATED SIGN "NO LEFT TURN"/"NO RIGHT TURN"		
SERVICE INSTALLATION -(P) POLE MOUNTED			RAILROAD FLASHING SIGNAL			NUMBER OF CONDUCTORS, ELECTRIC CABLE NO. 14, UNLESS NOTED OTHERWISE. ALL DETECTOR LOOP CABLE TO BE SHIELDED		
SERVICE INSTALLATION -(G) GROUND MOUNTED -(GM) GROUND MOUNTED METERED	 G GM	 G GM	RAILROAD CROSSING GATE			GROUND CABLE IN CONDUIT, NO. 6 SOLID COPPER (GREEN)		
TELEPHONE CONNECTION			RAILROAD CROSSBUCK			ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1/C		
STEEL MAST ARM ASSEMBLY AND POLE			RAILROAD CONTROLLER CABINET			COAXIAL CABLE		
ALUMINUM MAST ARM ASSEMBLY AND POLE			UNDERGROUND CONDUIT (UC), GALVANIZED STEEL			VENDOR CABLE		
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH LUMINAIRE			TEMPORARY SPAN WIRE, TETHER WIRE, AND CABLE			COPPER INTERCONNECT CABLE, NO. 18, 3 PAIR TWISTED, SHIELDED		
SIGNAL POST -(BM) BARREL MOUNTED - TEMPORARY		 BM	SYSTEM ITEM		 SP	FIBER OPTIC CABLE -NO. 62.5/125, MM12F -NO. 62.5/125, MM12F SM12F -NO. 62.5/125, MM12F SM24F		
WOOD POLE			INTERSECTION ITEM		 IP	GROUND ROD -(C) CONTROLLER -(M) MAST ARM -(P) POST -(S) SERVICE		
GUY WIRE			REMOVE ITEM		 R			
SIGNAL HEAD			RELOCATE ITEM		 RL			
SIGNAL HEAD WITH BACKPLATE			ABANDON ITEM		 A			
SIGNAL HEAD OPTICALLY PROGRAMMED			CONTROLLER CABINET AND FOUNDATION TO BE REMOVED		 RCF			
FLASHER INSTALLATION -(FS) SOLAR POWERED	 F FS	 F FS	MAST ARM POLE AND FOUNDATION TO BE REMOVED		 RMF			
PEDESTRIAN SIGNAL HEAD			SIGNAL POST AND FOUNDATION TO BE REMOVED		 RPF			
PEDESTRIAN PUSH BUTTON -(APS) ACCESSIBLE PEDESTRIAN PUSH BUTTON	 APS	 APS	DETECTOR LOOP, TYPE I					
RADAR DETECTION SENSOR			PREFORMED DETECTOR LOOP					
VIDEO DETECTION CAMERA			SAMPLING (SYSTEM) DETECTOR					
RADAR/VIDEO DETECTION ZONE			INTERSECTION AND SAMPLING (SYSTEM) DETECTOR					
PAN, TILT, ZOOM (PTZ) CAMERA			QUEUE AND SAMPLING (SYSTEM) DETECTOR					
EMERGENCY VEHICLE LIGHT DETECTOR			WIRELESS DETECTOR SENSOR					
CONFIMATION BEACON			WIRELESS ACCESS POINT					
WIRELESS INTERCONNECT								
WIRELESS INTERCONNECT RADIO REPEATER								

MODE: Default
FILE: I:\Users\jw3111\OneDrive\Documents\DOT Office\District 1\Projects\DH4542\2x2\ACAD\Drawings\CADsheets\ts05.dgn
25-Apr-2025 11:21:59 AM User:footemj


LOOP DETECTOR NOTES

- EACH PAIR OF LOOP WIRES SHALL BE PLACED IN A SEPARATE EMPTY COILABLE NONMETALLIC CONDUIT FROM THE EDGE OF PAVEMENT TO THE HANDHOLE. SPACING BETWEEN THE HOLES DRILLED IN THE PAVEMENT SHALL NOT BE LESS THAN 6" (150 mm). EMPTY COILABLE NONMETALLIC CONDUIT SHALL BE INCLUDED IN THE COST OF THE LOOP WIRE.
- THE NUMBER OF LOOP TURNS SHALL BE AS RECOMMENDED BY THE AMPLIFIER MANUFACTURER. ALL ADJACENT SIDES OF THE LOOPS SHALL BE INSTALLED IN SUCH A WAY THAT THE CURRENT FLOW IS IN THE SAME DIRECTION TO REINFORCE ITS MAGNETIC FIELDS FOR SMALL VEHICLE DETECTION.
- EACH LOOP LEAD-IN SHALL BE IDENTIFIED AND PERMANENTLY TAGGED IN THE HANDHOLE. EACH LEAD-IN CABLE TAG SHALL INDICATE THE LOCATION OF THE LOOP, LOOP ROTATION (CLOCKWISE/COUNTERCLOCKWISE), LOOP LEAD-IN DIRECTION (IN OR OUT), LOOP CABLE NUMBER AND LOCATION IN CABINET, AND NUMBER OF TURNS IN THE DETECTOR LOOPS IN WATER PROOF INK AS INDICATED ON THE DISTRICT 1 STANDARD TRAFFIC SIGNAL DESIGN DETAIL. THE CONTRACTOR SHALL MARK LOOP LOCATIONS ON RECORD DRAWINGS AND PRESENT TO THE ENGINEER AFTER FINAL INSPECTION. LOOPS SHALL BE MARKED BY LANE AND LOOP NUMBER. SEE DETAIL BELOW.
- ALL LOOP CABLE SHALL BE FASTENED WITH PLASTIC TIE WRAP TO THE HANDHOLE HOOKS.
- IN ASPHALT PAVEMENT, LOOPS SHOULD BE PLACED IN THE BINDER AND DIVEHOLES MARKED AT THE CURB WITH A SAW-CUT. THE SAW-CUT SHALL BE CUT IN ACCORDANCE WITH LOCAL AND E.P.A. DUST CONTROL REQUIREMENTS. DETECTOR LOOP(S) SHALL NOT BE INSTALLED IN WET CONDITIONS AND THE SAW-CUTS MUST BE FREE OF DEBRIS AND RESIDUE SUCH AS DUST AND WATER WHICH IS TO BE ACHIEVED BY THE USE OF COMPRESSED AIR, WIRE BRUSHING AND HEAT DRYING ACCORDING TO SEALANT MANUFACTURER REQUIREMENTS. THE DETECTOR WIRE SHALL BE HELD IN PLACE BY THE USE OF FORM WEDGES. WEDGES SHALL BE SPACED NO MORE THAN 18" (450 mm) APART.
- LOOP SPLICES SHALL BE SOLDERED USING A SOLDERING IRON. BLOW TORCHES OR OTHER DEVICES WHICH OXIDIZE COPPER CABLE SHALL NOT BE ALLOWED FOR SOLDERING OPERATIONS. SEE DETAIL BELOW RIGHT.
- PREFORMED DETECTOR LOOPS SHALL BE USED, AS SHOWN ON THE PLANS, WHERE NEW CONCRETE PAVEMENT IS PROPOSED. THE INSTALLATION OF PREFORMED LOOPS SHALL BE IN ACCORDANCE WITH THE DISTRICT 1 SPECIFICATIONS OR AS DIRECTED BY THE ENGINEER.

LOOP LEAD-IN CABLE TAG




- A. LANE 1 IS THE LANE CLOSEST TO THE CENTERLINE OF THE ROADWAY
- B. LOOP #1 IS THE LOOP IN THE LANE CLOSEST TO THE INTERSECTION.
- C. LABEL LOOP CABLE "IN" OR LOOP CABLE "OUT".
- D. LABEL LOOP CABLE CLOCKWISE OR LOOP CABLE COUNTERCLOCKWISE.




DETECTOR LOOP WIRING SCHEMATIC

- LOOPS SHALL BE SPLICED IN SERIES. SAW-CUTS SHALL BE A MINIMUM WIDTH OF 5/16" (8 mm).
- SAW-CUT DEPTHS SHALL BE 3" (75 mm). IF IN CONCRETE,
- THE SAW-CUT DEPTH SHALL BE TO THE TOP OF THE REINFORCEMENT.
- LOOP CORNERS SHALL BE DRILLED WITH A 2" (50 mm) DIAMETER CORE.




DETAIL "A"
LOOP-TO-LOOP SPLICE




DETAIL "B"
LOOP-TO-CONTROLLER SPLICE

TYPE I LOOP



DETAIL "A"
LOOP-TO-LOOP SPLICE



DETAIL "B"
LOOP-TO-CONTROLLER SPLICE

PRE-FORMED LOOP

LOOP DETECTOR SPLICE

- ① WESTERN UNION SPLICE SOLDERED WITH ROSIN CORE FLUX. ALL EXPOSED SURFACES OF THE SOLDER SHALL BE SMOOTH. THE WESTERN UNION SPLICES SHALL BE STAGGERED.
- ② WCSMW 30/100 HEAT SHRINK TUBE, MINIMUM LENGTH 3" (75 mm), UNDERWATER GRADE.
- ③ WCS 200/750 HEAT SHRINK TUBE, MINIMUM LENGHT 6" (150 mm), UNDERWATER GRADE.
- ④ NO. 14 2/C TWISTED, SHIELDED CABLE.
- ⑤ LOOP CONDUCTOR WITH FLEXIBLE PLASTIC TUBE. PRE-FORMED LOOP
- ⑥ XL POLYOLEFIN 2 CONDUCTOR
- ⑦ BREAKOUT SEALS. TYCO CBR-2 OR APPROVED EQUAL


MODE: Default
FILE: I:\Users\jw3411\OneDrive\Documents\DOT Office\District 1\Projects\District 1\Standard Traffic Signal Design Details\CAD\Sheet\TS05.dgn
25-Apr-2025 11:27:38 AM User:footemj

 <div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312-475-9500 F 312-475-9594 www.infrastructure-eng.com</div>	USER NAME = footemj		DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.						
	PLOT SCALE = 50.0000' / in.		DRAWN -	REVISED -		112	2025-1086-RS	WILL	51	24										
	PLOT DATE = 3/4/2019		CHECKED -	REVISED -		SCALE: NONE			SHEET 2	OF 7 SHEETS	STA.	TO STA.								
			DATE -	REVISED -								ILLINOIS FED. AID PROJECT								
															TS-05			CONTRACT NO.80B13		

MODE: Default
FILE NAME: 2025-1086-RS-05-01-084810NTEC\Illinois.gov\PHUDOT\Documents\DOT Offices\District 1\Projects\DHUS02\232ACAD\Detail\CADsheets\TS05.dgn
P: 312.425.9500 | F: 312.425.9594 | www.illinoisinfrastructure.com

TRAFFIC SIGNAL MAST ARM AND SIGNAL POST


MAST ARM MOUNTED SIGNALS IN EXISTING, PROPOSED OR FUTURE SIDEWALK/BICYCLE PATH AREA. INTERSECTION SHOWN WITH PEDESTRIAN SIGNALS AND PEDESTRIAN PUSHBUTTON DETECTORS.



NOTES:

1. THE SIGNAL HEAD SPACING IS EQUAL TO THE LANE WIDTH OR AS SHOWN ON THE TRAFFIC SIGNAL PLAN.
2. REFER TO THE TRAFFIC SIGNAL EQUIPMENT OFFSET TABLE.
3. PROVIDE A LEVEL ALL-WEATHER SURFACE (CONCRETE SIDEWALK, ASPHALT BICYCLE PATH SURFACE OR MATCHING MATERIAL TO THE ADJACENT SURFACE) UP TO THE MAST ARM SHAFT OR THE SIGNAL POST.
4. THE FACE OF THE PEDESTRIAN PUSHBUTTON SHALL BE PARALLEL TO THE CROSSWALK TO BE USED.
5. THE LOCATIONS AND INSTALLATION OF PEDESTRIAN SIGNAL HEADS AND PEDESTRIAN PUSHBUTTONS SHALL MEET THE REQUIREMENTS OF THE MUTCD AND INFORMATION FOUND IN THE "AMERICANS WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES FOR BUILDINGS AND FACILITIES."


PEDESTRIAN SIGNAL POST
AND
PEDESTRIAN PUSH BUTTON POST



NOTES:

1. REFER TO THE TRAFFIC SIGNAL EQUIPMENT OFFSET TABLE.
2. PROVIDE A LEVEL ALL-WEATHER SURFACE (CONCRETE SIDEWALK, ASPHALT BICYCLE PATH SURFACE OR MATCHING MATERIAL TO THE ADJACENT SURFACE) UP TO THE PEDESTRIAN SIGNAL POST OR THE PEDESTRIAN PUSH BUTTON POST.
3. THE FACE OF THE PEDESTRIAN PUSHBUTTON SHALL BE PARALLEL TO THE CROSSWALK TO BE USED.
4. THE LOCATIONS AND INSTALLATION OF PEDESTRIAN SIGNAL HEADS AND PEDESTRIAN PUSHBUTTONS SHALL MEET THE REQUIREMENTS OF THE MUTCD AND INFORMATION FOUND IN THE "AMERICANS WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES FOR BUILDINGS AND FACILITIES."

RECOMMENDED PUSHBUTTON LOCATIONS



- * WHERE THERE ARE CONSTRAINTS THAT MAKE IT IMPRACTICAL TO PLACE THE PEDESTRIAN PUSHBUTTON BETWEEN 1.5 FT (0.45 m) AND 6 FT (1.8 m) FROM THE EDGE OF THE CURB, SHOULDER, OR PAVEMENT, IT SHOULD NOT BE FURTHER THAN 10 FT (3 m) FROM THE EDGE OF CURB, SHOULDER, OR PAVEMENT.
- ** WHERE THERE ARE CONSTRAINTS ON A PARTICULAR CORNER THAT MAKE IT IMPRACTICAL TO PROVIDE THE 10 FT (3 m) SEPERATION BETWEEN THE TWO PEDESTRIAN PUSHBUTTONS, THE PUSHBUTTONS MAY BE PLACED CLOSER TOGETHER OR ON THE SAME POLE.

NOTES:

1. PEDESTRIAN SIGNAL HEADS SHALL BE MOUNTED WITH THE BOTTOM OF THE SIGNAL HOUSING INCLUDING BRACKETS NOT LESS THAN 8 FT (2.4 m) OR MORE THAN 10 FT (3 m) ABOVE SIDEWALK LEVEL, AND SHALL BE POSITIONED AND ADJUSTED TO PROVIDE MAXIMUM VISIBILITY AT THE BEGINNING OF THE CONTROLLED CROSSWALK.
2. THE BOTTOM OF THE SIGNAL HOUSING (INCLUDING BRACKETS) OF A VEHICULAR SIGNAL FACE THAT IS NOT LOCATED OVER A HIGHWAY SHALL BE AT LEAST 8 FT (2.4 m) BUT NOT MORE THAN 19 FT (5.8 m) ABOVE THE SIDEWALK OR, IF THERE IS NO SIDEWALK, ABOVE THE PAVEMENT GRADE AT THE CENTER OF THE ROADWAY.
3. THE BOTTOM OF THE SIGNAL HOUSING AND ANY RELATED ATTACHMENTS TO A SIGNAL FACE LOCATED OVER ANY PORTION OF A HIGHWAY SHALL BE ACCORDING TO CURRENT STATE STANDARDS 877001, 877002, 877006, 877011 AND 877012 WITH A MINIMUM OF 16 FT (5.0 m) AND A MAXIMUM OF 18 FT. (5.5 m) FROM THE HIGHEST POINT OF PAVEMENT.
4. THE BOTTOM OF THE TEMPORARY SPAN WIRE MOUNTED SIGNAL HOUSING AND ANY RELATED ATTACHMENTS TO A SIGNAL FACE LOCATED OVER ANY PORTION OF A HIGHWAY SHALL BE ACCORDING TO CURRENT STATE STANDARD 880001 WITH A MINIMUM OF 17 FT (5.18 m) FROM THE HIGHEST POINT OF PAVEMENT.
5. THE TOP OF THE SIGNAL HOUSING OF A SIGNAL FACE LOCATED OVER ANY PORTION OF A HIGHWAY SHALL NOT BE MORE THAN 25.6 FT (7.8 m) ABOVE THE PAVEMENT.

TRAFFIC SIGNAL EQUIPMENT OFFSET


TRAFFIC SIGNAL EQUIPMENT	COMBINATION CONCRETE CURB AND GUTTER (MINIMUM DISTANCE FROM BACK OF CURB TO CENTERLINE OF FOUNDATION)	SHOULDER/NON-CURBED AREA (MINIMUM DISTANCE FROM EDGE OF PAVEMENT TO CENTERLINE OF FOUNDATION)
TRAFFIC SIGNAL MAST ARM POLE	6 FT (1.8m)	SHOULDER WIDTH + 2 FT (0.5m), MINIMUM 10 FT (3.0m)
TRAFFIC SIGNAL POST	4 FT (1.2m)	SHOULDER WIDTH + 2 FT (0.5m), MINIMUM 10 FT (3.0m)
PEDESTRIAN SIGNAL POST	4 FT (1.2m)	SHOULDER WIDTH + 2 FT (0.5m), MINIMUM 10 FT (3.0m)
PEDESTRIAN PUSHBUTTON POST	4 FT (1.2m)	SHOULDER WIDTH + 2 FT (0.5m), MINIMUM 10 FT (3.0m)
TEMPORARY WOOD POLE	6 FT (1.8m)	SHOULDER WIDTH + 2 FT (0.5m), MINIMUM 10 FT (3.0m)
CONTROLLER CABINET	6 FT (1.8m) MINIMUM DISTANCE SEE NOTE 2	SHOULDER WIDTH + 6 FT (1.8m), MINIMUM 16 FT (4.9m) SEE NOTE 3.
SERVICE INSTALLATION, GROUND MOUNT	6 FT (1.8m) MINIMUM DISTANCE SEE NOTE 2	SHOULDER WIDTH + 6 FT (1.8m), MINIMUM 16 FT (4.9m) SEE NOTE 3.

NOTES:


1. CONTACT THE "AREA TRAFFIC SIGNAL MAINTENANCE AND OPERATIONS ENGINEER" FOR ASSISTANCE IN LOCATING THE TRAFFIC SIGNAL EQUIPMENT WHEN THERE ARE CONFLICTS WITH DITCHES OR THE MINIMUM OFFSET DISTANCES CANNOT BE MET.
2. MINIMUM DISTANCE FROM THE BACK OF CURB TO THE ROADWAY SIDE OF THE FOUNDATION.
3. MINIMUM DISTANCE FROM THE EDGE OF PAVEMENT TOTHE ROADWAY SIDE OF THE FOUNDATION.
4. ANY CHANGES TO THE OFFSETS OF THE FOUNDATIONS, FROM THE MINIMUM DISTANCES LISTED IN THE "TRAFFIC SIGNAL EQUIPMENT OFFSET" CHART AND THE TRAFFIC SIGNAL INSTALLATION PLAN, COULD EFFECT THE PLACEMENT OF THE SIGNAL HEADS, PEDESTRIAN SIGNAL HEADS AND THE PEDESTRIAN PUSHBUTTONS. THE SIGNAL HEAD PLACEMENT ON THE MAST ARMS SHALL REMAIN AS PER THE TRAFFIC SIGNAL INSTALLATION PLAN AND THE "TRAFFIC SIGNAL MAST ARM AND SIGNAL POST" DETAIL ABOVE. THE PROPOSED MAST ARM LENGTHS MAY NEED TO BE REVISED TO MEET THE ABOVE REQUIREMENTS. THE PEDESTRIAN SIGNAL HEADS AND PEDESTRIAN PUSHBUTTONS MUST MEET THE REQUIREMENTS UNDER THE DETAILS ON THIS SHEET.

 <div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.425.9500 F 312.425.9594 www.illinoisinfrastructure.com</div>	USER NAME = footemj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS	F.A.P. RTE.		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			112	2025-1086-RS	WILL	51	25		
	PLOT SCALE = 50.0000 ' / in.	CHECKED -	REVISED -			TS-05					CONTRACT NO.80B13	
	PLOT DATE = 3/4/2019	DATE -	REVISED -			SCALE: NONE	SHEET 3	OF 7 SHEETS	STA.	TO STA.		
								ILLINOIS	FED. AID PROJECT			

MODE: Default
FILE: I:\Users\jwagner\OneDrive\Documents\DOT Office\District 1\Projects\DH542232\ACAD\Detail\CADsheets\ts05.dgn
11/08/2019 11:29:30 AM User:footen




ELECTRIC SERVICE - PANEL DIAGRAM (TYPICAL FOR POLE AND GROUND MOUNTED SERVICE)
SERVICE INSTALLATION POLE MOUNT (SHOWN)
(NOT TO SCALE)




SERVICE INSTALLATION GROUND MOUNT
(NOT TO SCALE)

CABINET - BASE BOLT PATTERN
(NOT TO SCALE)




NOTES:

1. ELECTRIC SERVICE PANELS SHALL BE CONSTRUCTED TO U.L. STD 508, INDUSTRIAL CONTROL PANEL, AND CARRY THE U.L. LABEL.
2. ALL WIRING SHALL BE NEATLY DRESSED AND SUPPORTED.




HANDHOLE COVER & FRAME - GROUNDING DETAIL
(NOT TO SCALE)



EXISTING HANDHOLE COVER & FRAME - GROUNDING DETAIL
(NOT TO SCALE)


NOTES:
GROUNDING SYSTEM

1. THE GROUNDING SYSTEM SHALL CONSIST OF AN INSULATED CONDUCTOR TYPE XLP, NO. 6 A.W.G., STRANDED COPPER TO BE INSTALLED IN RACEWAYS. THE GROUNDING CABLE SHALL BE INSTALLED IN A CONTINUOUS MANNER AS SHOWN ON THE CABLE PLAN PROVIDED. ALL GROUNDING CONDUCTORS SHALL BE BONDED TO METAL ENCLOSURE (HANDHOLE, POST, MAST ARM, CONTROLLER, ETC.). GROUND ROD SHALL BE 3/4" DIA. x 10'-0" (20mm x 3.0m) LONG, COPPER CLAD. ONE GROUND ROD SHALL BE INSTALLED AT ALL POST FOUNDATIONS, POLE FOUNDATIONS, CONTROLLER CABINET FOUNDATION AND ELECTRICAL SERVICE INSTALLATION AS INDICATED ON THE CABLE PLAN. IF THERE ARE ANY SPECIAL CONDITIONS SUCH AS SUB-SURFACE CONDITIONS OR INSTALLATION PROBLEMS, THE RESIDENT ENGINEER SHALL BE NOTIFIED OR CONTACT THE BUREAU OF TRAFFIC, ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT ONE AT (847) 705-4139.
2. THE NEUTRAL CONDUCTOR AND THE GROUND CONDUCTOR SHALL BE CONNECTED IN THE SERVICE INSTALLATION. AT NO OTHER POINT IN THE TRAFFIC SIGNAL SYSTEM SHALL THE NEUTRAL AND GROUND CONDUCTORS BE CONNECTED.
3. ALL EQUIPMENT GROUNDING CONDUCTORS SHALL TERMINATE AT THE GROUND BUS IN THE CONTROLLER CABINET.
4. THE CONTRACTOR SHALL PROVIDE A GROUND CABLE WITH CONNECTORS BETWEEN THE HANDHOLE COVER AND HANDHOLE FRAME.



NOTES:



- ALL CLAMPS SHALL BE BRONZE OR COPPER, UL APPROVED.
- GROUND CABLE SHALL BE LOOPED OVER HOOKS IN THE HANDHOLES 6.5' (2.0m) SLACK SHALL BE PROVIDED IN SINGLE HANDHOLES 13' (4.0m) OF SLACK SHALL BE PROVIDED IN DOUBLE HANDHOLES. 5' (1.4m) OF SLACK SHALL BE PROVIDED BETWEEN FRAME AND COVER.




MAST ARM POLE / POST-GROUNDING DETAIL
(NOT TO SCALE)

 INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9510 F 312.475.9594 www.infrastructure-eng.com	USER NAME = footenj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000' / in.	DRAWN -	REVISED -						112	2025-1086-RS	WILL	51	26
	PLOT DATE = 3/4/2019	CHECKED -	REVISED -						TS-05		CONTRACT NO.80B13		
		DATE -	REVISED -						SCALE: NONE	SHEET 4	OF 7 SHEETS	STA.	TO STA.

MODE: Default
FILE: I:\Users\j2011\0848\BID\ITC\Illnode.gov\PHUDOT\Documents\DOT Offices\District 1\Project\DH542323\ACAD\DATA\CAD\sheet1505.dgn
4/26/2019 11:29:30 AM User: j2011




TYPE D
FOR GROUND MOUNTED
CONTROLLER CABINET
AND UPS BATTERY CABINET




NOTE:

TOP OF FOUNDATION SHALL
BE HIGHER THAN TOP OF
DOUBLE HANDHOLE



TYPE C
FOR GROUND MOUNTED
SUPER P (TYPE IV) AND SUPER R (TYPE V)
CONTROLLER CABINETS



NOTES:

1. BASED ON CONTROLLER CABINET TYPE IV WITH BASE DIMENSIONS OF 26" x 44" (660mm x 1118mm). ADJUST PLATFORM SIZE TO FIT CABINET BASE DIMENSIONS BEING SUPPLIED.
2. BASED ON UNINTERRUPTIBLE POWER SUPPLY CABINET WITH BASE DIMENSIONS OF 16" x 25" (406mm x 635mm). ADJUST PLATFORM SIZE TO FIT CABINET BASE DIMENSIONS BEING SUPPLIED.
3. PLATFORM SIZE FOR CONTROLLER CABINET TYPE IV.
4. PLATFORM SIZE FOR CONTROLLER CABINET TYPE IV AND UNINTERRUPTIBLE POWER SUPPLY CABINET.
5. DRILLED HOLES THROUGH THE PLATFORM BASE TO MATCH THE CONTROLLER CABINET BOLT TEMPLATE. FASTEN THE CONTROLLER CABINET TO THE PLATFORM WITH CARRIAGE BOLTS, WASHERS AND NUTS.
6. FASTEN ALL SUPPORT WOOD FRAMING TO THE WOOD POSTS WITH 2 LAG SCREWS FOR EACH CONNECTION..

TEMPORARY SIGNAL CONTROLLER
WOOD SUPPORT PLATFORM

CABLE SLACK LENGTH	FEET	METER
HANDHOLE	6.5	2.0
DOUBLE HANDHOLE	13.0	4.0
SIGNAL POST	2.0	0.6
MAST ARM	2.0	0.6
CONTROLLER CABINET	1.5	0.5
FIBER OPTIC AT CABINET	13.0	4.0
ELECTRIC SERVICE AT (CABINET OR SERVICE LOCATION)	1.5	0.5
GROUND CABLE (SIGNAL POST, MAST ARM, CABINET)	1.5	0.5
GROUND CABLE (BETWEEN FRAME AND COVER)	5.0	1.6

CABLE SLACK

VERTICAL CABLE LENGTH	FEET	METER
MAST ARM POLE (MAST ARM MOUNTED SIGNAL HEAD) (L = MAST ARM LENGTH - DISTANCE TO SIGNAL HEAD FROM END OF ARM)	20.0+L	6.0+L
BRACKET MOUNTED (MAST ARM POLE OR SIGNAL POLE)	13.0	4.0
PEDESTRIAN PUSH BUTTON	6.0	2.0
SERVICE INSTALLATION POLE MOUNT TO SERVICE DROP	13.5	4.1
SERVICE INSTALLATION POLE MOUNT TO GROUND	13.5	4.1
SERVICE INSTALLATION GROUND MOUNT	6.0	2.0
FOUNDATION (SIGNAL POST, MAST ARM POLE, CONTROLLER CABINET, SERVICE-GROUND MOUNT)	3.0	1.0

VERTICAL CABLE LENGTH

FOUNDATION	DEPTH
TYPE A - Signal Post	4'-0" (1.2m)
TYPE C - CONTROLLER W/ UPS	4'-0" (1.2m)
TYPE D - CONTROLLER	4'-0" (1.2m)
SERVICE INSTALLATION, GROUND MOUNT, TYPE A - SQUARE	4'-0" (1.2m)


DEPTH OF FOUNDATION


MAST ARM LENGTH	① Foundation Depth	Foundation Diameter	Spiral Diameter	Quantity of Rebars	Size of Rebars
Less than 30' (9.1 m)	10'-0" (3.0 m)	30" (750mm)	24" (600mm)	8	6(19)
Greater than or equal to 30' (9.1 m) and less than 40' (12.2 m)	13'-6" (4.1 m)	30" (750mm)	24" (600mm)	8	6(19)
Greater than or equal to 40' (12.2 m) and less than 50' (15.2 m)	11'-0" (3.4 m)	36" (900mm)	30" (750mm)	12	7(22)
Greater than or equal to 50' (15.2 m) and up to 55' (16.8 m)	13'-0" (4.0 m)	36" (900mm)	30" (750mm)	12	7(22)
Greater than or equal to 55' (16.8 m) and less than 65' (19.8 m)	15'-0" (4.6 m)	36" (900mm)	30" (750mm)	12	7(22)
Greater than or equal to 65' (19.8 m) and up to 75' (22.9 m)	21'-0" (6.4 m)	42" (1060mm)	36" (900mm)	16	8(25)
Greater than or equal to 75' (22.9 m) and up to 85' (25.9 m)	25'-0" (7.6 m)	42" (1060mm)	36" (900mm)	16	8(25)

NOTES:

1. These foundation depths are for sites which have cohesive soils (clayey silt, sandy clay, etc.) along the length of the shaft, with an average Unconfined Compressive Strength (qu) > 1.0 tsf (100 kpa). This strength shall be verified by boring data prior to construction or with testing by the Engineer during foundation drilling. The Bureau of Bridges & Structures should be contacted for a revised design if other conditions are encountered.
2. Combination mast arm assemblies under 55 feet (16.8 m) shall use 36" (900 mm) diameter foundations.
3. Combination mast arm assemblies under 56 feet (16.8 m) through 75 feet (22.9 m) shall use 42" (1060 mm) diameter foundations.
4. For mast arm assemblies with dual arms refer to state standard 878001..


DEPTH OF MAST ARM FOUNDATIONS, TYPE E

 <div>INFRASTRUCTURE ENGINEERING INCORPORATED</div> <div>1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com</div>	USER NAME = footemj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						112	2025-1086-RS	WILL	51	27
	PLOT SCALE = 50.0000' / in.	CHECKED -	REVISED -						TS-05 CONTRACT NO.80B13				
	PLOT DATE = 3/4/2019	DATE -	REVISED -		SCALE: NONE	SHEET 5	OF 7 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			




BOLT PATTERN


NOTE:
1. IF THE PEDESTRIAN SIGNAL POST FOUNDATION IS INSTALLED WITHIN OR BEHIND A BARRIER CURB, THE TOP OF THE FOUNDATION SHALL BE INSTALLED FLUSH WITH THE TOP OF THE BARRIER CURB.




CONCRETE FOUNDATION,
TYPE A 12-INCH DIAMETER



PEDESTRIAN SIGNAL POST, 10 FT.




PEDESTRIAN SIGNAL POST, 5 FT.



R10-3b



R10-3d



R10-3e

SIGN TABLE


SIGN	DIMENSIONS
R10-3b (RAILROAD ONLY)	9" X 12"
R10-3d (RAILROAD ONLY)	9" X 12"
R10-3e	9" X 12"

NOTES:
1. THE SIGN PANELS SHALL BE TYPE AP SHEETING.
2. THE ARROW ON SIGNS FOR PUSH-BUTTONS SERVING TWO DIRECTIONS ON THE SAME PHASE SHALL BE BI-DIRECTIONAL.
3. THE SIGN FOR DUAL-CALL PUSH-BUTTONS SHALL HAVE NO ARROW.

MODEL: Default
FILE: \\na101\share\damcon.dot\illinois.gov\HWD\DOT\Documents\DOT Offices\Dist1et 1\Projects\DUHS\4272\ACADD\BaiCAD\Sheet\1505.dgn

LOOPS NEXT TO SHOULDERS

PROVIDE A PAVEMENT REPLACEMENT
NOTE WHICH SHOULD EQUAL
3' (900 mm) X WIDTH OF
PAVED SHOULDER.




* = (600 mm)

** UNIT DUCT IS TO BE SHOWN ON PLAN SHEETS
BUT SHALL NOT BE INCLUDED IN THE PAY ITEMS.

LEFT TURN LANES WITH MEDIANS
VOLUME DENSITY ("FAR OUT" DETECTION)
ON SAME APPROACH
(PROTECTED / PERMITTED LEFT TURN PHASING)


HANDHOLE LOCATION MAY
VARY DEPENDING ON GEOMETRICS
AND DESIGN OF TRAFFIC SIGNALS.
HEAVY-DUTY HANDHOLES TO BE
USED WHEN THE MEDIAN IS
MOUNTABLE. REFER TO STANDARD
814001 TO ENSURE THAT HANDHOLE
FITS IN MEDIAN.



** UNIT DUCT IS TO BE SHOWN ON PLAN SHEETS
BUT SHALL NOT BE INCLUDED IN THE PAY ITEMS.


NOTE: DUAL LEFT TURNS NOT SHOWN REFER TO
PLAN SHEET FOR DETECTOR LOOP REPLACEMENT

LEFT TURN LANES WITHOUT MEDIANS
VOLUME DENSITY ("FAR OUT" DETECTION)
ON SAME APPROACH
(PROTECTED / PERMITTED LEFT TURN PHASING)




NOTE: DUAL LEFT TURNS NOT SHOWN REFER TO
PLAN SHEET FOR DETECTOR LOOP REPLACEMENT

ARTERIAL-VOLUME DENSITY ("FAR OUT" DETECTION)
CROSS STREET-NON VOLUME DENSITY ("FAR OUT" DETECTION)



DETAIL 1
N.T.S.

ARTERIAL-VOLUME DENSITY ("FAR OUT" DETECTION)
CROSS STREET-NON VOLUME DENSITY ("UPTIGHT" PRESENCE DETECTION)



DETAIL 2
N.T.S.

NOTES:

VEHICLES LOOP DETECTORS

- * ALL LEAD IN CABLE SHALL BE TWO CONDUCTOR NO. 14 TWISTED, SHIELDED.
- * EACH DETECTOR LOOP SHALL HAVE ITS OWN SAW CUT FROM THE LOOP TO THE EDGE OF PAVEMENT OR TO A HANDHOLE IN THE PAVEMENT.
- * EACH DETECTOR LOOP SHALL HAVE ITS OWN ONE INCH (25 mm) UNIT DUCT BETWEEN THE EDGE OF PAVEMENT AND THE FIRST HANDHOLE OR JUNCTION BOX. EACH UNIT DUCT RUN SHALL BE SHOWN ON THE PLANS BY THE DESIGNER, BUT SHALL NOT BE PAID FOR SEPARATLY. THIS ITEM IS INCIDENTAL TO THE PAY ITEM FOR DETECTOR LOOPS.
- * ONE DIMENSION OF ALL DETECTOR LOOPS SHALL BE SIX FEET (1.8 m)
- * EACH LANE OF NON-LOCKING, PRESENCE DETECTION AND EACH LANE OF A DOUBLE LEFT TURN LANE REQUIRES A SEPARATE INDUCTIVE LOOP DETECTOR AND LEAD IN CABLE.
- * WHEN NON-LOCKING, PRESENCE DETECTION IS USED, MORE THAN ONE LOOP PER LANE IS REQUIRED BEHIND THE STOP BAR (i.e. 1-1/2, 1-3/4, 2).

- * WHEN SYSTEM LOOPS ARE REQUIRED ON AN APPROACH OF AN INTERSECTION, THE LOOPS USED FOR VOLUME DENSITY AND INTERSECTION TIMING SHALL ALSO BE USED AS SYSTEM DETECTORS. EACH ONE OF THESE TYPE OF LOOPS REQUIRES A SEPARATE TWO CONDUCTOR NO. 14 TWISTED SHIELDED CABLE AND A SEPARATE INDUCTIVE LOOP DETECTOR WHEN NEW CONTROLLERS ARE UTILIZED. THE DESIGNER SHALL LABEL THESE TYPES OF LOOPS AS "INTERSECTION AND SAMPLING (SYSTEM) DETECTORS" ON THE SIGNAL LAYOUT, THE INTERCONNECT PLAN AND THE SYSTEM CABLE PLAN. WHEN AN EXISTING CONTROLLER IS UTILIZED FOR THIS TYPE OF DETECTION, THE PAY ITEM "INDUCTIVE LOOP DETECTOR WITH SYSTEM OUTPUT" SHOULD BE USED.

PLACEMENT OF DETECTORS

THE FOLLOWING FIGURES REPRESENT THE MOST COMMON DETECTOR LOOP LOCATIONS AND SIZES. ADJUSTMENTS WILL BE NECESSARY FOR SPECIFIC GEOMETRIC CONSIDERATIONS.

LOCATIONS AND DEMENSIONS OF DETECTOR LOOPS ARE REQUIRED ON ALL SIGNAL LAYOUT PLAN SHEETS.

"FAR OUT" DETECTION REFERS TO LOCKING, PRESENCE TYPE DETECTION LOCATED IN THRU LANES, RIGHT TURN LANES, AND RIGHT TURN LANE TAPER AREAS (IF APPLICABLE), USUALLY 250' (75 m) IN ADVANCE OF STOP BARS. "UPTIGHT" DETECTION REFERS TO NON-LOCKING PRESENCE TYPE DETECTION LOCATED IN ALL LANES AND 10'-15' (3.0 m-4.5 m) BEHIND THE CROSSING STREET'S EDGE OF PAVEMENT EXTENDED.



NOTE:

ALL DETAILS AND NOTES SHOWN ARE FROM THE I.D.O.T. DISTRICT 1 TRAFFIC SIGNAL DESIGN GUIDELINES DATED JANUARY 1995

THIS DRAWING HAS BEEN PREPARED TO ASSIST THE RESIDENT ENGINEER FOR ALL ROADWAY RESURFACING OR S.M.A.R.T. PROJECTS WHERE THE DIMENSIONS ARE NOT SHOWN ON THE PLANS AND THE FINAL LOCATIONS FOR CROSSWALKS OR STOP BARS ARE NOT DETERMINED.

 INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9510 F 312.475.9594 www.infrastructure-eng.com	USER NAME = footemj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT 1 – DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING	F.A.P. SECTION COUNTY TOTAL SHEET RTE. 112 2025-1086-RS WILL 51 30				
	PLOT SCALE = 50.0000' / in.	CHECKED - R.K.F.	REVISED -			TS-07 CONTRACT NO.80B13				
	PLOT DATE = 3/4/2019	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
						SCALE: NONE	SHEET 1	OF 1 SHEETS	STA. TO STA.	

MODEL: Default
FILE NAME: P:\P-22\22-4675-00 DOT Various Phase 2 (PTB 2016-02)\WO 34 80B13\DNVICADD_Sheets\80B13-SHT-TS-001.dgn



REMOVAL AND RELOCATION NOTES

THE FOLLOWING TRAFFIC SIGNAL EQUIPMENT SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR OWN EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE EQUIPMENT BID PRICE.

6 EACH PEDESTRIAN PUSH-BUTTON

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR, SAFELY STORED, AND RELOCATED TO THE PROPOSED 10 FT POST.



1 EACH PEDESTRIAN SIGNAL HEAD

NOTES

- CONTRACTOR SHALL PERFORM WORK IN SUCH A WAY TO MINIMIZE THE TIME THE PEDESTRIAN EQUIPMENT IS NOT OPERATIONAL.
- ALL EXISTING TRAFFIC SIGNAL CABLE NO LONGER REQUIRED SHALL BE REMOVED.

TS 7513

 <div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com</div>	USER NAME = ALane		DESIGNED - AMT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC SIGNAL REMOVAL PLAN IL 53 (BROADWAY ST) & RUBY ST			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - AMT		REVIS	ED -					112	2025-1086-RS	WILL	51	31
	CHECKED - ACL		REVIS	ED -		SCALE: 1" = 20'			CONTRACT NO. 80B13				
	PLOT DATE = 1/6/2026		DATE - 09/12/2025	REVISED -		SHEET OF SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				



NOTES:


1. CONTRACTOR SHALL CONFIRM THE FINAL LOCATION OF THE APS EQUIPMENT WITH THE TRAFFIC SIGNAL AREA ENGINEER BEFORE INSTALLATION.
2. APS SHALL BE PLACED PARALLEL TO THE CORRESPONDING CROSSWALK.
3. ALL PUSH BUTTONS SHALL BE APS.
4. EACH DETECTOR LOOP SHALL HAVE ITS OWN 1" COILABLE NON-METALLIC CONDUIT BETWEEN THE EDGE OF PAVEMENT AND THE ADJACENT HANDHOLE AS SHOWN ON THE PLANS AND AS STATED IN THE TRAFFIC SIGNAL SPECIFICATIONS.
5. WORK SHALL MEET THE REQUIREMENTS OF THE SPECIAL PROVISIONS, DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING, RESURFACING, AND PATCHING OPERATIONS).
6. THERE SHALL BE A MINIMUM OF 4' SIDEWALK CLEARANCE NEXT TO TRAFFIC SIGNAL FOUNDATIONS TO BE ADA COMPLIANT.
7. NO PROPOSED PEDESTRIAN POST SHALL EXCEED 10 FT FROM BACK OF CURB.

TS 7513


MODEL: Default
FILE NAME: P:\P-22\22-4675-00 DOT Various Phase 2 (PTB 2019-02)\WO 34 80B13\DNICADD_Sheets\80B13-SHT-TS-002.dgn

<div><div>INFRASTRUCTURE ENGINEERING INCORPORATED</div><div>1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com</div></div>	USER NAME = ALane		DESIGNED - AMT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC SIGNAL MODERNIZATION PLAN IL 53 (BROADWAY ST) & RUBY ST				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			DRAWN - AMT	REVISED -		112	2025-1086-RS	WILL	51	32				
			CHECKED - ACL	REVISED -		CONTRACT NO. 80B13								
	PLOT DATE = 1/6/2026		DATE - 09/12/2025	REVISED -		SCALE: 1" = 20'				SHEET	OF	SHEETS	STA.	TO STA.
										ILLINOIS FED. AID PROJECT				

EXISTING AND PROPOSED
CONTROLLER SEQUENCE



EXISTING AND PROPOSED EMERGENCY
VEHICLE PREMPTION SEQUENCE



LEGEND

- PROTECTED PHASE
- PROTECTED/PERMITTED PHASE
- PEDESTRIAN PHASE
- OVERLAP

NOTE:
1. OVERLAP IS A CONTINUOUS RIGHT TURN ARROW AND SHALL BE TERMINATED WHEN A CALL IS PLACED TO PUSH BUTTONS FOR PHASES 2 AND 4.

SCHEDULE OF QUANTITIES

DESCRIPTION	UNIT	TOTAL
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	122
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1822
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	940
ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	50
DRILL EXISTING HANDHOLE	EACH	5
PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2
DETECTOR LOOP, TYPE I	FOOT	885
RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	2
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	362
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
REBUILD EXISTING HANDHOLE	EACH	5
PEDESTRIAN SIGNAL POST, 10 FT.	EACH	2
PEDESTRIAN SIGNAL POST, 5 FT.	EACH	3
ACCESSIBLE PEDESTRIAN SIGNALS	EACH	10
CONCRETE FOUNDATION, TYPE A 12-INCH DIAMETER	FOOT	20
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1

TRAFFIC SIGNAL ELECTRICAL
SERVICE REQUIREMENTS

EQUIPMENT TYPE	QUANTITY	UNIT WATTAGE	TOTAL WATTAGE
SIGNAL HEAD 1 OR 3-SECTION	3	11	33
4-SECTION	-	14	-
5-SECTION	10	13	130
PROGRAMMABLE 3-SECTION	-	22	-
4-SECTION	-	32	-
5-SECTION	-	28	-
PEDESTRIAN SIGNAL	10	15	150
CONTROLLER	1	150	150
MASTER CONTROLLER	-	100	-
UPS	1	25	25
DETECTION RADAR OR VIDEO	2	20	40
BLANK-OUT SIGN	-	25	-
NETWORK SWITCH II OR III	-	35	-
CELLULAR MODEM	-	15	-
TOTAL UPS SIZING			528
UPS CHARGING	1	225	225
BATTERY HEATER MAT	1	180	180
CABINET HEATER	1	200	200
FLASHER	-	15	-
LED STREET NAME SIGN	-	120	-
LUMINAIRE	-	240	-
TOTAL SERVICE WIRE SIZING			1133

ENERGY COSTS TO:
ILLINOIS DEPARTMENT OF TRANSPORTATION

201 WEST CENTER COURT,
SCHAUMBURG, IL 60196

ENERGY SUPPLY:

CONTACT: NEW BUSINESS DEPARTMENT

PHONE: (866)639-3532

COMPANY: COMMONWEALTH EDISON

ACCOUNT NUMBER:

METER NUMBER:

RUBY ST.

IL 53
(BROADWAY ST.)

BROADWAY ST.

IL 53
(RUBY ST.)

CABLE PLAN

(NOT TO SCALE)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CABLE PLAN, PHASE DIAGRAM, & EMERG. VEH. PREEMPTION
IL 53 (BROADWAY ST.) & RUBY ST

SCALE: NTS SHEET OF SHEETS STA. TO STA.

TS 7513
ECONOLITE ASC/2S-2100



F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	33
CONTRACT NO. 80B13				
ILLINOIS FED. AID PROJECT				

MODEL: Default
FILE NAME: P:\P-22-222-4675-00 DOT Various Phase 2 (PTB 2016-02)\WO 34 80B13\DWG\CADD_Sheets\80B13-SHT-TS-003.dgn

INFRASTRUCTURE
ENGINEERING INCORPORATED
1 South Wacker | Suite 2650 | Chicago, IL 60606
P 312.475.9510 | F 312.475.9514 | www.infrastructure-eng.com

USER NAME = Alane
DESIGNED - AMT
DRAWN - AMT
CHECKED - ACL
DATE - 09/12/2025
PLOT DATE = 1/6/2026

REVIS
REVISE
REVISE
REVISE



REMOVAL AND RELOCATION NOTES

THE FOLLOWING TRAFFIC SIGNAL EQUIPMENT SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR OWN EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE EQUIPMENT BID PRICE.

4 EACH PEDESTRIAN PUSH-BUTTON



NOTES

- CONTRACTOR SHALL PERFORM WORK IN SUCH A WAY TO MINIMIZE THE TIME THE PEDESTRIAN EQUIPMENT IS NOT OPERATIONAL.
- ALL EXISTING TRAFFIC SIGNAL CABLE NO LONGER REQUIRED SHALL BE REMOVED.

TS 7509

MODEL: Default
FILE NAME: P:\P-22-22-4675-00 DOT Various Phase 2 (PTB 2025-02)\WO 34 80B13\DNVCADD_Sheets\80B13-SHT-TS-011.dgn

 <div>1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com</div>	USER NAME = ALane			DESIGNED - AMT	REVISED -	<div>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</div>			<div>TRAFFIC SIGNAL REMOVAL PLAN IL 53 (BROADWAY ST) & INGALLS AVE</div>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				DRAWN - AMT	REVISED -							112	2025-1086-RS	WILL	51	34
				CHECKED - ACL	REVISED -							CONTRACT NO. 80B13				
	PLOT DATE = 1/6/2026			DATE - 09/12/2025	REVISED -							ILLINOIS FED. AID PROJECT				
						SCALE: 1" = 20'			SHEET	OF	SHEETS	STA. 0+00		TO STA. 0+00		




NOTES:

1. CONTRACTOR SHALL CONFIRM THE FINAL LOCATION OF THE APS EQUIPMENT WITH THE TRAFFIC SIGNAL AREA ENGINEER BEFORE INSTALLATION.
2. APS SHALL BE PLACED PARALLEL TO THE CORRESPONDING CROSSWALK.
3. ALL PUSH BUTTONS SHALL BE APS.
4. EACH DETECTOR LOOP SHALL HAVE ITS OWN 1" COILABLE NON-METALLIC CONDUIT BETWEEN THE EDGE OF PAVEMENT AND THE ADJACENT HANDHOLE AS SHOWN ON THE PLANS AND AS STATED IN THE TRAFFIC SIGNAL SPECIFICATIONS.
5. WORK SHALL MEET THE REQUIREMENTS OF THE SPECIAL PROVISIONS, DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING, RESURFACING, AND PATCHING OPERATIONS).
6. THERE SHALL BE A MINIMUM OF 4' SIDEWALK CLEARANCE NEXT TO TRAFFIC SIGNAL FOUNDATIONS TO BE ADA COMPLIANT.
7. NO PROPOSED PEDESTRIAN POST SHALL EXCEED 10 FT FROM BACK OF CURB.

TS 7509

 <div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com</div>	USER NAME = ALane		DESIGNED - AMT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC SIGNAL MODERNIZATION PLAN IL 53 (BROADWAY ST) & INGALLS AVE				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			DRAWN - AMT	REVISED -						112	2025-1086-RS	WILL	51	35
	PLOT DATE = 1/6/2026		CHECKED - ACL	REVISED -		CONTRACT NO. 80B13								
	DATE = 09/12/2025		REVIS	REVISED -		SCALE: 1" = 20'				SHEET	OF	SHEETS	STA. 0+00	TO STA. 0+00

EXISTING AND PROPOSED
CONTROLLER SEQUENCE



LEGEND

- ← (⊙) → PROTECTED PHASE
- ← - (⊙) - PROTECTED/PERMITTED PHASE
- ← (⊙) → PEDESTRIAN PHASE

SCHEDULE OF QUANTITIES

DESCRIPTION	UNIT	TOTAL
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	22
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	934
ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	40
DRILL EXISTING HANDHOLE	EACH	4
DETECTOR LOOP, TYPE I	FOOT	529
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	254
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
REBUILD EXISTING HANDHOLE	EACH	4
PEDESTRIAN SIGNAL POST, 5 FT.	EACH	4
ACCESSIBLE PEDESTRIAN SIGNALS	EACH	8
CONCRETE FOUNDATION, TYPE A 12-INCH DIAMETER	FOOT	16
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1

TRAFFIC SIGNAL ELECTRICAL
SERVICE REQUIREMENTS

EQUIPMENT TYPE	QUANTITY	UNIT WATTAGE	TOTAL WATTAGE
SIGNAL HEAD 1 OR 3-SECTION	10	11	110
4-SECTION	-	14	-
5-SECTION	2	13	26
PROGRAMMABLE 3-SECTION	-	22	-
4-SECTION	-	32	-
5-SECTION	-	28	-
PEDESTRIAN SIGNAL	8	15	120
CONTROLLER	1	150	150
MASTER CONTROLLER	-	100	-
UPS	1	25	25
DETECTION RADAR OR VIDEO	-	20	-
BLANK-OUT SIGN	-	25	-
NETWORK SWITCH II OR III	-	35	-
CELLULAR MODEM	-	15	-
TOTAL UPS SIZING			431
UPS CHARGING	1	225	225
BATTERY HEATER MAT	1	180	180
CABINET HEATER	1	200	200
FLASHER	-	15	-
LED STREET NAME SIGN	-	120	-
LUMINAIRE	-	240	-
TOTAL SERVICE WIRE SIZING			1036

ENERGY COSTS TO:
ILLINOIS DEPARTMENT OF TRANSPORTATION

201 WEST CENTER COURT,
SCHAUMBERG, IL 60196

ENERGY SUPPLY:


CONTACT: NEW BUSINESS DEPARTMENT

PHONE: (866)639-3532

COMPANY: COMMONWEALTH EDISON

ACCOUNT NUMBER:

METER NUMBER:



CABLE PLAN

(NOT TO SCALE)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CABLE PLAN, PHASE DIAGRAM, & EMERG. VEH. PREEMPTION
IL 53 (BROADWAY ST) & INGALLS AVE

SCALE: NTS SHEET 1 OF 6 SHEETS STA. 0+00 TO STA. 0+00

TS 7509
ECONOLITE ASC/3-2100


MODEL: Default
FILE NAME: P:\P-22-22-4675-00 DOT Various Phase 2 (PTB 2016-02)\WO 34 80B13\DWG\CADD_Sheets\80B13-SHT-TS-013.dgn

INFRASTRUCTURE
ENGINEERING INCORPORATED
1 South Wacker | Suite 2650 | Chicago, IL 60606
P 312.475.9510 | F 312.475.9514 | www.infrastructure-inc.com

USER NAME	= ALane
DESIGNED	- AMT
DRAWN	- AMT
CHECKED	- ACL
DATE	- 09/12/2025
REVIS	-
REVIS	-
REVIS	-
REVIS	-
PLOT DATE	= 1/6/2026

DESIGNED	- AMT	REVISED	-
DRAWN	- AMT	REVISED	-
CHECKED	- ACL	REVISED	-
DATE	- 09/12/2025	REVISED	-

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	36
CONTRACT NO. 80B13				
ILLINOIS FED. AID PROJECT				



1. EXISTING BROKEN FRAMES AND LIDS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND LIDS WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.
2. IF THE EXISTING LIDS ARE OPEN, THE FRAME WILL BE ADJUSTED TO THE ELEVATION OF THE MILLED PAVEMENT SURFACE PRIOR TO THE MILLING OPERATION. THE FRAME WILL NOT BE REMOVED AND COVERED BY THE METAL PLATE.
3. CITY OF CHICAGO CASTINGS ARE THE PROPERTY OF THE CITY AND THE CONTRACTOR SHALL NOTIFY THE CITY FOR REMOVAL AND DISPOSITION OF THE CASTINGS.
4. THE METAL PLATE USED TO COVER THE STRUCTURE SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.
5. THE CONTRACTOR SHALL REMOVE ALL TRAFFIC CONTROL DEVICES BY THE END OF EACH WORK SHIFT.

1. REMOVING FRAMES AND LIDS ON DRAINAGE AND UTILITY STRUCTURES IN THE PAVEMENT PRIOR TO MILLING, AND ADJUSTING TO FINAL GRADE PRIOR TO PLACING THE SURFACE COURSE, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR "FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)."
2. THIS WORK WILL NOT BE PAID FOR WHEN DRAINAGE AND UTILITY STRUCTURES ARE SPECIFIED FOR PAYMENT AS STRUCTURE RECONSTRUCTION.
3. NEW FRAMES AND LIDS, WHEN SPECIFIED, WILL BE PAID FOR SEPARATELY.
4. WHEN STRUCTURES ARE TO BE ADJUSTED OR RECONSTRUCTED, THE LOWERING AND RAISING OF THE FRAMES AND LIDS WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE COST OF THE CORRESPONDING PAY ITEM.

SCALE: NONE	SHEET 1	OF 1	SHEETS	STA.	TO STA.
-------------	---------	------	--------	------	---------


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	37
BD600-03 (BD-08)		CONTRACT NO.80B13		
ILLINOIS		FED. AID PROJECT		

METHOD OF MEASUREMENT

REFER TO SECTION 442 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL."

BASIS OF PAYMENT

- 1. REFER TO SECTION 442 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL."
- 2. SAW CUT/SCORING OF EXISTING HMA OVERLAY IS INCLUDED IN THE COST OF PAVEMENT PATCHING.
- 3. SAW CUT/SCORING OF EXISTING PAVEMENT IS INCLUDED IN THE COST OF PAVEMENT PATCHING.



SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.


SEQUENCE OF CONSTRUCTION (MILLING FIRST)

- 1. MILL HMA FIRST IF THERE IS AT LEAST 4½ INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
- 2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

MODEL: Default
FILE NAME: o:\cadd\paw.bentley.com\paw\DOT\Documents\DOT Offices\District 1\Projects\DisH22\33\ACADData\CADsheets\bd22.dgn

<div><div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com</div></div>	USER NAME = Lawrence,DeManche	DESIGNED - R. SHAH	REVISED - R. BORO 01-01-07	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - R. BORO 09-04-07		112	2025-1086-RS	WILL	51	38				
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED - K. ENG 10-27-08		BD400-04 (BD-22)		CONTRACT NO.80B13						
	PLOT DATE = 11/18/2022	DATE - 10-25-94	REVISED - K. SMITH 11-18-22		ILLINOIS FED. AID PROJECT								
	SCALE: NONE		SHEET 1 OF 1 SHEETS		STA. TO STA.								



- * 3" (75) MINIMUM FROM TOP AND BOTTOM OF THE CONCRETE PAVEMENT OR BASE COURSE.
- ** IF THE FINAL SURFACE OF THE PAVEMENT IS CONCRETE, THE GUTTER IS TO BE FLUSH WITH THE PAVEMENT.

CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

MODE: Default
FILE: C:\Users\paulmcmahon\OneDrive\Documents\DOT\Office\District 1\Projects\DHHS\2223\CAD\Drawings\CD\Sheets\bd24.dgn

 INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com	USER NAME = footemj	DESIGNED - A. HOUSEH	REVISED - A. ABBAS 03-21-97	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
	PLOT SCALE = 50.0000' / in.	DRAWN -	REVISED - M. GOMEZ 01-22-01							112	2025-1086-RS	WILL	51	39			
	PLOT DATE = 7/11/2019	CHECKED -	REVISED - R. BORO 12-15-09							BD600-06 (BD-24)					CONTRACT NO.80B13		
		DATE - 03-11-94	REVISED - K. SMITH 07-11-19							ILLINOIS FED. AID PROJECT							
SCALE: NONE		SHEET 1	OF 1	SHEETS	STA.	TO STA.											

Model: Default
FILE NAME: \\w:\data-cw-bentley.com\PIV\DOT\Documents\DOT Offices\District 1\Projects\DH5422\3\ACADD\ha\CAD\sheet\bd3.dgn
8/3/2024 10:30:32 AM User: Shawn.Ley



INFRASTRUCTURE

ENGINEERING

INCORPORATED

1 South Wacker | Suite 2650 | Chicago, IL 60606

F 312.475.9500 | F 312.475.9594 | www.infrastructure-eng.com

USER NAME	= Shawn.Ley
PLOT SCALE	= 50.0000 ' / in.
PLOT DATE	= 1/23/2023

DESIGNED -	R. SHAH
DRAWN -	JIS
CHECKED -	A. ABBAS
DATE -	09-10-94


REVISED -	E. GOMEZ 12-21-00
REVISED -	R. BORO 01-01-07
REVISED -	JP CHANG 07-08-16
REVISED -	K. SMITH 11-18-22

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HMA TAPER AT
EDGE OF P.C.C. PAVEMENT


SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	41
BD400-06		BD-33	CONTRACT NO.80B13	
		ILLINOIS	FED. AID PROJECT	




ADA DETAIL FOR SINGLE PERPENDICULAR CURB RAMPS W/ EXIST. 5% OR LESS RUN. SLOPE


PD-01A



PD-01B



PD-01C



DESIGNER NOTES:

- 1) ALL CROSS SLOPES ARE PREFERRED 1.6% (1:64), MAXIMUM 2% (1:50).
- 2) SIDEWALK REALIGNMENT WILL REQUIRE DETAILED DESIGN.
- 3) AREAS SURROUNDED BY PCC/ASPHALT, BUILDINGS, OR ARE NEAR TO DRIVEWAYS, REALIGNED SIDEWALK, UTILITY AND SIGNAL POLES, OR WHEN PRIVATE SIDEWALK TIES IN, WILL REQUIRE DETAILED SURVEY AND DESIGN.
- 4) ALL BRICK CORNERS WILL REQUIRE SUPERVISOR APPROVAL BEFORE USING PROJECT DETAILS

LEGEND

	EXIST. GRASS
	PROPOSED SIDE CURB
	PROPOSED SIDEWALK
	DETECTABLE WARNINGS


CONSTRUCTION NOTES:

- 1) ALL CROSS SLOPES ARE PREFERRED 1.6% (1:64), MAXIMUM 2% (1:50) EXCEPT WHEN TRANSITIONING TO EXISTING SIDEWALK
- * MATCH EXISTING SIDEWALK WIDTH


FILE NAME = PLANPREP.SQUAD\Desig\Typical ADA details\Typical-ADA-shit-plan.dgn Default	USER NAME = ledezmar 1 South Wacker Suite 2650 Chicago, IL 60606 F 312.475.9500 F 312.475.9594 www.infrastructure-engineers.com	DESIGNED - --- --/--/---- DRAWN - RL 11/12/2019 CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROJECT DETAIL FOR SINGLE PERPENDICULAR CURB RAMPS (PD-01)	SCALE: SHEET OF SHEETS STA. TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
							112	2025-1086-RS	WILL	51	42
							PD-01				
							ILLINOIS FED. AID PROJECT				

ADA DETAIL FOR SINGLE PERPENDICULAR CURB RAMPS W/ EXIST. 5% OR GREATER RUN. SLOPE


PD-02A



PD-02B



PD-02C



DESIGNER NOTES:

- 1) ALL CROSS SLOPES ARE PREFERRED 1.6% (1:64), MAXIMUM 2% (1:50).
- 2) SIDEWALK REALIGNMENT WILL REQUIRE DETAILED DESIGN.
- 3) AREAS SURROUNDED BY PCC/ASPHALT, BUILDINGS, OR ARE NEAR TO DRIVEWAYS, REALIGNED SIDEWALK, UTILITY AND SIGNAL POLES, OR WHEN PRIVATE SIDEWALK TIES IN, WILL REQUIRE DETAILED SURVEY AND DESIGN.
- 4) ALL BRICK CORNERS WILL REQUIRE SUPERVISOR APPROVAL BEFORE USING PROJECT DETAILS

LEGEND

PROPOSED SIDE CURB



EXIST. GRASS



PROPOSED SIDEWALK



DETECTABLE WARNINGS

CONSTRUCTION NOTES:


- 1) ALL CROSS SLOPES ARE PREFERRED 1.6% (1:64), MAXIMUM 2% (1:50) EXCEPT WHEN TRANSITIONING TO EXISTING SIDEWALK

* MATCH EXISTING SIDEWALK WIDTH


<div><div></div><div>INFRASTRUCTURE ENGINEERS</div><div>1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9510 F 312.475.9511 www.infrastructure-eng.com</div></div>	FILE NAME =	PLANPREP.SQUAD\Details\Typical ADA details\Typical-ADA-shd-plan.dgn	USER NAME = ledezmarc	DESIGNED - --- --/--/----	DRAWN - RL 11/12/2019	REVIS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROJECT DETAIL FOR SINGLE PERPENDICULAR CURB RAMPS (PD-02)	SCALE: SHEET OF SHEETS STA. TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
												112	2025-1086-RS	WILL	51	43	
												PD-02		CONTRACT NO.80B13			
												ILLINOIS FED. AID PROJECT					

ADA DETAIL FOR SINGLE PERPENDICULAR CURB RAMPS W/ TURNING SPACE

PD-04A



PD-04B



DESIGNER NOTES:

- 1) ALL CROSS SLOPES ARE PREFERRED 1.6% (1:64), MAXIMUM 2% (1:50).
- 2) SIDEWALK REALIGNMENT WILL REQUIRE DETAILED DESIGN.
- 3) AREAS SURROUNDED BY PCC/ASPHALT, BUILDINGS, OR ARE NEAR TO DRIVEWAYS, REALIGNED SIDEWALK, UTILITY AND SIGNAL POLES, OR WHEN PRIVATE SIDEWALK TIES IN, WILL REQUIRE DETAILED SURVEY AND DESIGN.
- 4) ALL BRICK CORNERS WILL REQUIRE SUPERVISOR APPROVAL BEFORE USING PROJECT DETAILS

LEGEND

	EXIST. GRASS
	PROPOSED SIDEWALK
	DETECTABLE WARNINGS
	PROPOSED SIDE CURB

CONSTRUCTION NOTES:

- 1) ALL CROSS SLOPES ARE PREFERRED 1.6% (1:64), MAXIMUM 2% (1:50) EXCEPT WHEN TRANSITIONING TO EXISTING SIDEWALK

* MATCH EXISTING SIDEWALK WIDTH

<div><div></div><div>INFRASTRUCTURE ENGINEERING INCORPORATED</div><div>1 South Wacker Suite 2650 Chicago, IL 60606 P 312.425.9500 F 312.425.9504 www.infrastructure-eng.com</div></div>	FILE NAME =	USER NAME = ledezmarc	DESIGNED - --- --/--/----	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROJECT DETAIL FOR SINGLE PERPENDICULAR CURB RAMPS W/TURNING SPACE (PD-04)	SCALE:1	SHEET	OF	SHEETS	STA.	TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	details\Typical-ADA-shd-plan.dgn	DRAWN - RL	11/12/2019	REVISED -									112	2025-1086-RS	WILL	51	44
	PLOT SCALE = 10.0000' / 1 in.	CHECKED -		REVISED -									PD-04		CONTRACT NO.80B13		
	PLOT DATE = 12/17/2019	DATE -		REVISED -									ILLINOIS FED. AID PROJECT				

MODEL: Default
FILE: \\na101\dwg\csw-bentley.com\PIV\DOT\Documents\DOT Offices\District 1\Projects\Dist5\221234\CADD\Data\CAD\sheet\TC10.dgn



INFRASTRUCTURE

ENGINEERING

INCORPORATED

1 South Wacker | Suite 2650 | Chicago, IL 60606

F 312.475.9500 | F 312.475.9594 | www.infrastructure-eng.com


USER NAME = Lawrence,DeManche	DESIGNED - L.H.A.	REVISED - T. RAMMACHER 01-06-00
	DRAWN -	REVISED - A. SCHUETZE 07-01-13
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED - A. SCHUETZE 09-15-16
PLOT DATE = 5/3/2024	DATE - 06-89	REVISED - D. SENDERAK 05-03-24

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL AND PROTECTION FOR
SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS






SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

All dimensions are in inches (millimeters)
unless otherwise shown.



NOTES:

- SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
 - ONE "ROAD CONSTRUCTION AHEAD" SIGN 36 x 36 (900x900) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 200' (60 m) IN ADVANCE OF THE MAIN ROUTE.
 - THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
- SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
 - ONE "ROAD CONSTRUCTION AHEAD" SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500' (150 m) IN ADVANCE OF THE MAIN ROUTE.
 - THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION OF THE CLOSED PORTION.
- CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEIGHT.
- WHEN THE SIDE ROAD LIES BETWEEN THE BEGINNING OF THE MAINLINE
- SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).
- WHEN WORK IS BEING PERFORMED ON A SIDE ROAD OR DRIVEWAY, FOLLOW THE APPLICABLE STANDARD(S). THE DIRECTIONAL ARROW (M6-1 OR M6-4) SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE TRAFFIC CONTROL SET-UP.
- ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAYS UNLESS OTHERWISE SPECIFIED IN THE PLANS OR BY THE ENGINEER.
- THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.





- ## GENERAL NOTES


1. MARKERS USED WITH DASHED LINES SHALL BE CENTERED IN THE GAP BETWEEN SEGMENTS.
2. MARKERS USED ADJACENT TO SOLID LINES SHALL BE OFFSET 2 TO 3 (50 TO 75) TOWARD TRAFFIC AS SHOWN.
3. MARKERS THROUGH TANGENTS LESS THAN 500' (150 m) IN LENGTH BETWEEN CURVES SHALL BE INSTALLED AT THE LESSER OF THE TWO CURVE SPACINGS.
4. MARKERS ARE TO BE USED ADJACENT TO BOTH SOLID WHITE LINES IN DUAL LEFT TURN LANES

- ### LANE MARKER NOTES


- A. USE DOUBLE LANE LINE MARKERS SPACED AS SHOWN.
- B. REDUCE TO 40' (12 m) O.C. ON CURVES WHERE ADVISORY SPEEDS ARE 10 M.P.H (20 km/h) LOWER THAN POSTED SPEEDS.




 <div>INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.425.9500 F 312.425.9504 www.infrastructure-eng.com</div>	USER NAME = footemj	DESIGNED -	REVISED - T. RAMMACHER 03-12-99	<div>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</div>	<div>TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)</div>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000' = 1".	DRAWN -	REVISED - T. RAMMACHER 01-06-00			112	2025-1086-RS	WILL	51	46
	PLOT DATE = 3/4/2019	CHECKED -	REVISED - C. JUCIUS 09-09-09			TC-11 CONTRACT NO.80B13				
	DATE -	REVISED - C. JUCIUS 07-01-13	ILLINOIS FED. AID PROJECT							
						SCALE: NONE	SHEET 1 OF 1 SHEETS	STA.	TO STA.	



2-LANE ROADWAY




MULTI-LANE UNDIVIDED



MULTI-LANE DIVIDED WITH MEDIAN

TYPICAL LANE AND EDGE LINE MARKING




DETAIL "A"


DETAIL "B"

TYPICAL CROSSWALK MARKING

* MARKINGS SHALL BE INSTALLED PARALLEL TO THE CENTERLINE OF THE ROAD WHICH IT CROSSES




4' (1.2 m) WIDE MEDIANS ONLY



MEDIANS OVER 4' (1.2 m) WIDE


DIAGONAL LINE SPACING: 50' (15 m) C-C (LESS THAN 30MPH (50 km/h))
75' (25 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h))
150' (45 m) C-C (MORE THAN 45MPH (70 km/h))



A MINIMUM OF TWO PAIRS OF TURN ARROWS SHALL BE USED, WHITE IN COLOR. ADDITIONAL PAIRS SHALL BE PLACED AT 200' (60 m) TO 300' (90 m) INTERVALS.

MEDIAN WITH TWO-WAY LEFT TURN LANE

TYPICAL PAINTED MEDIAN MARKING




FULL SIZE LETTERS 8' (2.4 m) AND ARROWS SHALL BE USED.
AREA = 15.6 SQ. FT. (1.5 m²) ONLY AREA = 20.8 SQ. FT. (1.9 m²)


* TURN LANES IN EXCESS OF 400' (120 m) IN LENGTH MAY HAVE AN ADDITIONAL SET OF ARROW - "ONLY" INSTALLED MIDWAY BETWEEN THE OTHER TWO SETS OF ARROW - "ONLY".

TYPICAL LEFT (OR RIGHT) TURN LANE

TYPICAL TURN LANE MARKING




ISLAND OFFSET FROM PAVEMENT EDGE




ISLAND AT PAVEMENT EDGE

TYPICAL ISLAND MARKING



COMBINATION LEFT AND U-TURN



U-TURN

LANE REDUCTION TRANSITION

* LANE REDUCTION ARROWS REQUIRED AT SPEEDS OF 45 MPH OR GREATER OR WHEN SPECIFIED IN PLANS.

TYPE OF MARKING	WIDTH OF LINE	PATTERN	COLOR	SPACING / REMARKS
CENTERLINE ON 2 LANE PAVEMENT	4 (100)	SKIP-DASH	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE
CENTERLINE ON MULTI-LANE UNDIVIDED PAVEMENT	2 @ 4 (100)	SOLID	YELLOW	11 (280) C-C
NO PASSING ZONE LINES: FOR ONE DIRECTION FOR BOTH DIRECTIONS	4 (100) 2 @ 4 (100)	SOLID SOLID	YELLOW/ YELLOW	5½ (140) C-C FROM SKIP-DASH CENTERLINE 11 (280) C-C OMIT SKIP-DASH CENTERLINE BETWEEN
LANE LINES	4 (100) 5 (125) ON FREEWAYS	SKIP-DASH SKIP-DASH	WHITE WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE
DOTTED LINES (EXTENSIONS OF CENTER, LANE OR TURN LANE MARKINGS)	SAME AS LINE BEING EXTENDED	SKIP-DASH	SAME AS LINE BEING EXTENDED	2' (600) LINE WITH 6' (1.8 m) SPACE
EDGE LINES	4 (100)	SOLID	YELLOW-LEFT WHITE-RIGHT	OUTLINE MEDIANS IN YELLOW
TURN LANE MARKINGS	6 (150) LINE: FULL SIZE LETTERS & SYMBOLS (8' (2.4m))	SOLID	WHITE	SEE TYPICAL TURN LANE MARKING DETAIL
TWO WAY LEFT TURN MARKING	7 @ 4 (100) EACH DIRECTION 8' (2.4m) LEFT ARROW	SKIP-DASH AND SOLID IN PAIRS	YELLOW WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE FOR SKIP-DASH; 5½ (140) C-C BETWEEN SOLID LINE AND SKIP-DASH LINE SEE TYPICAL TWO-WAY LEFT TURN MARKING DETAIL
CROSSWALK LINES (PEDESTRIAN) A. DIAGONALS (BIKE & EQUESTRIAN) B. LONGITUDINAL BARS (SCHOOL)	2 @ 6 (150) 2' (600) APART @ 45° 2' (600) APART @ 90°	SOLID SOLID SOLID	WHITE WHITE WHITE	NOT LESS THAN 6' (1.8 m) APART 2' (600) APART 2' (600) APART SEE TYPICAL CROSSWALK MARKING DETAILS.
STOP LINES	24 (600)	SOLID	WHITE	PLACE 4' (1.2 m) IN ADVANCE OF AND PARALLEL TO CROSSWALK, IF PRESENT. OTHERWISE, PLACE AT DESIRED STOPPING POINT. PARALLEL TO CROSSROAD CENTERLINE, WHERE POSSIBLE
PAINTED MEDIANS	2 @ 4 (100) WITH 12 (300) DIAGONALS @ 45° NO DIAGONALS USED FOR 4' (1.2 m) WIDE MEDIANS	SOLID	YELLOW: TWO WAY TRAFFIC WHITE: ONE WAY TRAFFIC	11 (280) C-C FOR THE DOUBLE LINE SEE TYPICAL PAINTED MEDIAN MARKING.
GORE MARKING AND CHANNELIZING LINES	8 (200) WITH 12 (300) DIAGONALS @ 45°	SOLID	WHITE	DIAGONALS: 15' (4.5 m) C-C (LESS THAN 30MPH (50 km/h)) 20' (6 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h) 30' (9 m) C-C (OVER 45MPH (70 km/h))
RAILROAD CROSSING	24 (600) TRANSVERSE LINES: *RR* 15 6' (1.8 m) LETTERS; 16 (400) LINE FOR *X*	SOLID	WHITE	SEE STATE STANDARD 780001 AREA OF: *R* = 3.6 SQ. FT. (0.33 m ²) EACH *X* = 54.0 SQ. FT. (5.0 m ²)
SHOULDER DIAGONALS (REQUIRED FOR SHOULDERS ≥ 8')	12 (300) @ 45°	SOLID	WHITE - RIGHT YELLOW - LEFT	50' (15 m) C-C (LESS THAN 30MPH (50 km/h)) 75' (25 m) C-C (30 MPH (50 km/h) TO 45MPH (70 km/h)) 150' (45 m) C-C (OVER 45MPH (70 km/h))
U TURN ARROW	SEE DETAIL	SOLID	WHITE	16.3 SF
2 ARROW COMBINATION LEFT AND U TURN	SEE DETAIL	SOLID	WHITE	30.4 SF

FOR FURTHER DETAILS ON PAVEMENT MARKING REFER TO STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND STATE STANDARD 780001.

All dimensions are in inches (millimeters) unless otherwise shown.

MODE: Default
FILE: \Users\jw\OneDrive\Documents\DOT Offices\District 1\Projects\Dist1\2025\2025-1086-RS\CD\Sheets\TC13.dgn
C:\Users\jw\AppData\Local\Temp\AutoCAD\2025\2025-1086-RS\CD\Sheets\TC13.dgn

 INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com	USER NAME = footemj	DESIGNED - EVERS	REVISED - C. JUCIUS 09-09-09	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT ONE TYPICAL PAVEMENT MARKINGS	F.A.P. RTE. 112	SECTION 2025-1086-RS	COUNTY WILL	TOTAL SHEETS 51	SHEET NO. 47
	PLOT SCALE = 50.0000" = 1 in.	DRAWN -	REVISED - C. JUCIUS 07-01-13			TC-13		CONTRACT NO.80B13		
	PLOT DATE = 3/4/2019	CHECKED -	REVISED - C. JUCIUS 12-21-15			SCALE: NONE		ILLINOIS FED. AID PROJECT		
		DATE - 03-19-90	REVISED - C. JUCIUS 04-12-16			SHEET 1	OF 2 SHEETS	STA. TO STA.		

TURN BAY ENTRANCE AT START
OF LANE CLOSURE TAPER




FIGURE 1

LEGEND

- WORK AREA
- LANE OPEN TO TRAFFIC
- ARROW BOARD
- TYPE I OR II BARRICADE OR DRUM WITH STEADY BURN LIGHT
- DRUM WITH STEADY BURN LIGHT
- SIGN ASSEMBLY
- TYPE I OR II CHECK BARRICADE WITH FLASHING LIGHT

NOTES:

- A) WHEN "L" IS \leq THE STORAGE LENGTH OF THE TURN LANE (AS SHOWN IN FIG. 1), USE FIGURE 1.
B) WHEN "L" IS $>$ THE STORAGE LENGTH OF THE TURN LANE OR THE TURN LANE IS WITHIN THE LANE CLOSURE, USE FIGURE 2.
- CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEIGHT.
- LIGHTS WILL NOT BE REQUIRED ON BARRICADES OR DRUMS FOR DAY OPERATIONS. ALL LIGHTS SHALL BE MONODIRECTIONAL.
- REFLECTIVE TEMPORARY PAVEMENT MARKINGS SHALL BE PLACED THROUGHOUT THE BARRICADED AREAS OF EACH TURN BAY AS SHOWN WHERE THE CLOSURE TIME IS GREATER THAN FOURTEEN (14) DAYS.
- THIS APPLICATION ALSO APPLIES WHEN WORK IS BEING PERFORMED IN THE RIGHT LANE(S) AND THE RIGHT TURN BAY IS TO REMAIN OPEN. UNDER THIS CONDITION, "RIGHT TURN LANE" R3-I100R 24 x 24 (600 x 600) AND M6-2R 21 x 15 (530 x 380) SHALL BE USED.
- THESE CONTROLS SHALL SUPPLEMENT MAINLINE TRAFFIC CONTROL FOR LANE CLOSURES.
- THE SIGNS SHALL BE MOUNTED ABOVE THE BARRICADES/DRUMS ON SEPARATE SIGN SUPPORTS THAT MEET NCHRP 350 OR MASH PREQUIREMENTS.
- TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

TURN BAY ENTRANCE
WITHIN A LANE CLOSURE





FIGURE 2




DETAIL A

All dimensions are in inches (millimeters) unless otherwise shown.


MODE: Default
FILE: \Users\jwaller\OneDrive\Documents\DOT Office\District 1\Projects\BNSF\2221\CAD\Drawings\CD\Sheet\TC-14.dgn

 INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com	USER NAME = footemj	DESIGNED - T. RAMMACHER 09-08-94	REVISED - R. BORO 09-14-09	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)	SCALE: NONE		SHEET 1	OF 1	SHEETS	STA.	TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000' / 1"	DRAWN - A. HOUSEH 11-07-95	REVISED - A. SCHUETZE 07-01-13			112	2025-1086-RS	WILL	51	48							
	PLOT DATE = 3/4/2019	CHECKED - A. HOUSEH 10-12-96	REVISED - A. SCHUETZE 09-15-16			TC-14		CONTRACT NO.80B13									
		DATE - T. RAMMACHER 01-06-00	REVISED -			ILLINOIS FED. AID PROJECT											




QUANTITY

4 (100) LINE = 45.5 ft. (13.9 m)
15.2 sq. ft. (1.41 sq. m)



QUANTITY

4 (100) LINE = 64.1 ft. (19.5 m)
21.4 sq. ft. (1.99 sq. m)




QUANTITY

4 (100) LINE = 82.5 ft. (25.1 m)
27.5 sq. ft. (2.53 sq. m)

NOTE:

ALL QUANTITIES OF PLACEMENT ARE REPRESENTED IN LINEAR FEET OF 4" LINES TO MATCH THE 4" TEMPORARY TAPE PAY ITEM AND REPRESENTS THE TOTAL QUANTITY OF 4" TAPE REQUIRED.



QUANTITY

4 (100) LINE = 225.9 ft. (68.9 m)
75.3 sq. ft. (6.99 sq. m)

All dimensions are in inches (millimeters) unless otherwise shown.

Model: Default
FILE: C:\Users\jwaller\OneDrive\Documents\DOT_Offices\Illinois\Projects\DUHS42323\ACADData\CAD\Sheet\TC22.dgn
11/22/2019 10:48:10 AM jwaller



INFRASTRUCTURE

ENGINEERING

INCORPORATED

1 South Wacker | Suite 2650 | Chicago, IL 60606

F 312.475.9500 | F 312.475.9594 | www.infrastructure-eng.com

USER NAME	= footemj
DESIGNED	-
DRAWN	-
PLOT SCALE	= 50.0000 ' / in.
PLOT DATE	= 3/4/2019

DESIGNED	-
DRAWN	-
CHECKED	-
DATE	-

REVISED	-	R. MIRS	09-15-97
REVISED	-	R. MIRS	12-11-97
REVISED	-	T. RAMMACHER	02-02-99
REVISED	-	C. JUCIUS	01-31-07

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

ARTERIAL ROAD


INFORMATION SIGN

SCALE: NONE

SHEET 1 OF 1 SHEETS

STA. TO STA.


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2025-1086-RS	WILL	51	50
TC-22		CONTRACT NO.80B13		
ILLINOIS		FED. AID PROJECT		



NOTES:

- USE BLACK LETTERING ON ORANGE BACKGROUND.
- ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- ERECT SIGN①WITH INSTALLED PANEL②ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- REMOVE PANEL②SOON AFTER THE START OF CONSTRUCTION.
- SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.




3.0" RADIUS, 0.5" BORDER, WHITE ON GREEN; REFLECTORIZED
"DRIVEWAY" D; "ENTRANCE" D; STANDARD ARROW CUSTOM 12.0" x 5.0"

NOTES:

1. HALF OF THE SIGNS WILL REQUIRE A LEFT HAND FACING ARROW.
2. TWO SIGNS SHALL BE USED AT EACH COMMERCIAL ENTRANCE
PLACED BACK-TO-BACK: ONE WITH A RIGHT HAND ARROW (SHOWN)
SHALL BE PLACED ON THE NEAR RIGHT SIDE THE DRIVEWAY
AND ONE WITH A LEFT HAND ARROW SHALL BE PLACED ON THE
FAR LEFT SIDE OF THE DRIVEWAY.
3. SIGNS TO BE PAID FOR AS ITEM "TEMPORARY INFORMATION SIGNING".

MODE: Default
FILE: C:\Users\jwilliams\OneDrive\Documents\DOT_0ffices\Illinois\1\Projects\Illinois\2025-1086-RS\CD\Sheet126.dgn
26/06/2021 2:32:02 AM Jwilliams

 INFRASTRUCTURE ENGINEERING INCORPORATED 1 South Wacker Suite 2650 Chicago, IL 60606 P 312.475.9500 F 312.475.9594 www.infrastructure-eng.com	USER NAME = leysa	DESIGNED -	REVISED - C. JUCIUS 02-15-07	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DRIVEWAY ENTRANCE SIGNING					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000' / in.	DRAWN -	REVISED -							112	2025-1086-RS	WILL	51	51
	PLOT DATE = 8/6/2021	CHECKED -	REVISED -		SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.					TC-26		CONTRACT NO.80B13		
		DATE -	REVISED -							ILLINOIS FED. AID PROJECT				