

DRAINAGE REMOVAL SCHEDULE				
STATION(S)	STORM SEWER REMOV LIN. FT.	SIZE IN. DIA.	PLUG EXIST STORM SEWER CU. YD.	REMOVE INLETS EACH
SPRINGFIELD AVENUE				
RT 51+25			0.3	10
RT 51+25 - 51+67	54	10		
RT 51+67				1
RT 52+15	10	8		1
RT 52+15 - 52+52	37	12		
RT 52+37 - 52+52	24	15		
RT 52+52				1
GRANT DRIVE				
LT 60+47 - 60+54	8	12		
TOTAL =	133		0.3	3

REMOVAL SCHEDULE										
LOCATION	STATION	TO STATION	PAVT. REMOVAL AREA SQ. YD.	PATCHING CL D T II, 8 INCH SQ. YD.	HMA SURF REM BUTT JT SQ. YD.	PAVT. MARKING REMOVAL SQ. FT.	SIDEWALK SPECIAL REMOVAL SQ. FT.	CURB REMOVAL FOOT	GUTTER REMOVAL FOOT	TREE REMOVAL 6-15 UNIT
	50+90	51+15			52.8					
RT	51+00	52+98	295.0							
RT	51+67	52+54				495	56			
	51+69	51+88		6.9						
RT	51+53	53+37							106	
LT	52+00	52+75	31.0							
LT, 26 FT	53+09									12
LT	53+10	53+24		14.4						
LT, 30 FT	53+13									8
LT	53+20	53+30				48				
	53+42	53+57			54.2					
GRANT DRIVE										
LT	59+83	60+47			49.2				64	
LT	60+47	60+55				28				
LINCOLN'S TOMB PARKING LOT										
RT	102+99	103+93				144.6				
LT	103+33	104+03				133.2				
RT	103+90					23.0				
TOTAL			326.0	21.3	156.2	300.8	571	56	170	20

EARTHWORK SCHEDULE					
LOCATION	STATION	TO STATION	TOPSOIL	EARTH	GRADING
			FUR & PLACE VAR DEPTH SQ. YD.	EXCAVATION SPECIAL CU YD	& SHAPING DITCHES FOOT
SPRINGFIELD AVENUE					
	50+79	53+57	507	280	
RT	51+41	53+35			211
LT	51+54	51+67			20
LT	52+38	53+05			75
TOTAL			507	280	306

SIDEWALK SCHEDULE			
LOCATION	STATION	TO STATION	PC CONC
			SIDEWALK 5 SQ. FT.
SPRINGFIELD AVENUE			
LT	51+20	51+30	45
RT	51+25	52+77	1069
LT	53+20	53+30	48
TOTAL			1162

GUTTER SCHEDULE			
LOCATION	STATION	TO STATION	TYPE B FOOT
GRANT DRIVE			
LT	59+83	60+47	64.0
TOTAL			64.0

DRAINAGE SCHEDULE																			
STATION(S)	MANHOLE TYPE A			SPECIAL	END SECTIONS						PIPE		STORM SEWER						
	SANITARY		4 DIA		GRATING			FLAP			CULVERTS		TYPE 1		TYPE 1		SPECIAL		TRENCH
	4 DIA	SPECIAL	FR & G		NO. 1	CIP	15"	12"	15"	EQV 15"	12"	15"	EQV 15"	12"	15"	EQV 15"	6"	8"	BACKFILL
	TIF CL	TYPE A	TYPE A		TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A	TYPE A
SPRINGFIELD AVENUE																			
LT 51+85					1														
LT 51+85 - RT 51+85													40						5.3
RT 51+66 - RT 52+23																			1.4
RT 51+85									1										
RT 52+21 - RT 52+40																			1.8
RT 52+23																			
RT 52+23 - RT 52+37																			28
RT 52+23 - RT 52+40																			1.8
RT 52+37	1																		
RT 52+40 - RT 52+53																			24
LT 53+12																			
LT 53+12 - RT 53+38																			1.1
GRANT DRIVE																			
LT 59+83																			
LT 59+83 - 60+45																			6.8
LT 60+45																			
TOTAL =	1	1	1	1	1	1	1	1	1	1	1	2	40	16	56	74	53	52	22.7

FILE NAME: D:\46315-shs825-schedule.dgn	USER NAME: slava	DESIGNED: R.H.D.	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES LINCOLN'S TOMB SITE RENOVATIONS			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	Default	DRAWN: S.D.K.	REVISED: -		SCALE:	SHEET 5 OF 16 SHEETS	STA.	TO STA.	ILLINOIS	FEQ. ASD PROJECT	16	5
		CHECKED: -	REVISED: -									
		DATE: 12/19/13	REVISED: -									

JOB NO. 250-061-X3 VASCONECLES ENGINEERING CORP. DESIGN FIRM REGISTRATION NUMBER 184-002107