


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% MWRD	100% RIVER FOREST WATERMAIN	100% ELMWOOD PARK WATERMAIN	100% ELMWOOD PARK EMERGENCY PRE-EMPTION	
				ROADWAY 0004	BRIDGE 0011	TRAFFIC SIGNALS 0021	UTILITY 0043	UTILITY 0043	UTILITY 0043	TRAFFIC SIGNALS 0021	
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	60			60					
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	438			438					
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	384			184	200				
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	92			92					
* 81304350	JUNCTION BOX EMBEDDED IN STRUCTURE 14" X 16" X 6"	EACH	2			2					
* 81400100	HANDHOLE	EACH	8			7	1				
* 81400200	HEAVY-DUTY HANDHOLE	EACH	4			3	1				
* 81400300	DOUBLE HANDHOLE	EACH	2			2					
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2			2					
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	3			3					
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5265			5265					
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1180			1180					
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1900			1900					
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2058			2058					

* SPECIALTY ITEMS

 Bollinger, Lach & Associates, Inc. <small>ITASCA, ILLINOIS</small>	USER NAME : *USER*	DESIGNED - MTC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER SUMMARY OF QUANTITIES	F.A.P. RTE. 307	SECTION 541Y-3-B	COUNTY COOK	TOTAL SHEETS 143	SHEET NO. 110			
	PLOT SCALE : *SCALE*	CHECKED - JIP	REVISED -			SCALE: NONE	SHEET NO. 12 OF 18 SHEETS	STA.	TO STA.	CONTRACT NO. 60J11			
	PLOT DATE : *DATE*	DATE - 12/20/2013	REVISED -			ILLINOIS FED. AID PROJECT							