

Stage 1 - IL RTE 64 EARTHWORK QUANTITIES

Stage 2 - IL RTE 64 EARTHWORK QUANTITIES

ILLINOIS ROUTE 64 CUT					
CUT (SF)	AVE	LENGTH	TOTAL	TOT (CY)	
88+50	0.00	2.27	50.00	113.25	4.19
89+00	4.53	5.36	50.00	268.23	9.93
89+50	6.20	6.98	50.00	349.05	12.93
90+00	7.76	9.95	50.00	497.35	18.42
90+50	12.13	13.89	50.00	694.50	25.72
91+00	15.65	14.37	50.00	718.35	26.61
91+50	13.08	51.20	50.00	2559.84	94.81
92+00	89.31	87.97	50.00	4398.66	162.91
92+50	86.64	80.65	50.00	4032.33	149.35
93+00	74.66	63.80	50.00	3190.04	118.15
93+50	52.95	41.31	50.00	2065.30	76.49
94+00	29.67	16.88	50.00	843.89	31.26
94+50	4.09	3.47	50.00	173.57	6.43
95+00	2.85	2.56	50.00	128.19	4.75
95+50	2.27	2.78	50.00	139.23	5.16
96+00	3.29	2.41	50.00	120.70	4.47
96+50	1.53	2.22	50.00	110.79	4.10
97+00	2.90	2.76	50.00	137.80	5.10
97+50	2.61	2.61	4.00	10.46	0.39
97+54	2.61	1.31	46.00	---	---
98+00	0.00	0.00	50.00	0.00	0.00
98+50	0.00	0.00	50.00	0.00	0.00
99+00	0.00	0.00	50.00	0.00	0.00
99+50	0.00	0.00	50.00	0.00	0.00
100+00	0.00	0.00	50.00	0.00	0.00
100+50	10.87	5.43	50.00	271.71	10.06
101+00	21.41	16.14	50.00	806.94	29.89
101+50	20.04	20.73	50.00	1036.33	38.38
102+00	23.81	21.92	50.00	1096.23	40.60
102+50	16.33	20.07	50.00	1003.28	37.16
103+00	14.08	15.20	50.00	760.21	28.16
103+50	0.00	7.04	50.00	352.06	13.04
ABUT.	0.00	---	---	---	0.00
BRIDGE	1027.61	---	---	---	1027.61
TOTAL				1986	

ILLINOIS ROUTE 64 FILL					
FILL (SF)	AVE	LENGTH	TOTAL	TOT (CY)	
88+50	0.00	0.01	50.00	0.63	0.02
89+00	0.03	0.03	50.00	1.35	0.05
89+50	0.03	0.44	50.00	21.95	0.81
90+00	0.85	0.45	50.00	22.62	0.84
90+50	0.06	0.96	50.00	48.16	1.78
91+00	1.87	0.96	50.00	48.24	1.79
91+50	0.06	0.82	50.00	41.07	1.52
92+00	1.58	0.81	50.00	40.26	1.49
92+50	0.03	0.03	50.00	1.34	0.05
93+00	0.03	0.34	50.00	17.03	0.63
93+50	0.65	0.34	50.00	17.03	0.63
94+00	0.03	2.32	50.00	115.84	4.29
94+50	4.61	17.87	50.00	893.69	33.10
95+00	31.14	44.09	50.00	2204.54	81.65
95+50	57.04	72.93	50.00	3646.43	135.05
96+00	88.82	103.00	50.00	5150.17	190.75
96+50	117.19	130.90	50.00	6545.13	242.41
97+00	144.61	178.91	50.00	8945.63	331.32
97+50	213.21	213.21	4.00	852.84	31.59
97+54	213.21	106.61	46.00	---	---
98+00	0.00	0.00	50.00	0.00	0.00
98+50	0.00	0.00	50.00	0.00	0.00
99+00	0.00	0.00	50.00	0.00	0.00
99+50	0.00	0.00	50.00	0.00	0.00
100+00	15.80	7.90	50.00	394.89	14.63
100+50	0.01	7.90	50.00	395.08	14.63
101+00	0.00	0.00	50.00	0.19	0.01
101+50	0.00	0.00	50.00	0.00	0.00
102+00	0.96	0.48	50.00	24.03	0.89
102+50	1.86	1.41	50.00	70.56	2.61
103+00	1.15	1.51	50.00	75.33	2.79
103+50	0.00	0.58	50.00	28.80	1.07
ABUT.	24.06	---	---	---	24.06
BRIDGE	0.00	---	---	---	0.00
TOTAL				1120	

ILLINOIS ROUTE 64 UNSUITABLES					
UNSUITS(SF)	AVE	LENGTH	TOTAL	TOT (CY)	
88+50	0.00	0.82	50.00	40.96	1.52
89+00	1.64	2.04	50.00	102.08	3.78
89+50	2.44	2.19	50.00	109.42	4.05
90+00	1.93	3.30	50.00	164.77	6.10
90+50	4.66	5.64	50.00	282.06	10.45
91+00	6.62	5.74	50.00	287.03	10.63
91+50	4.86	6.52	50.00	326.18	12.08
92+00	8.19	7.23	50.00	361.54	13.39
92+50	6.27	5.52	50.00	275.87	10.22
93+00	4.76	5.42	50.00	271.11	10.04
93+50	6.08	5.43	50.00	271.42	10.05
94+00	4.77	5.99	50.00	299.70	11.10
94+50	7.21	8.11	50.00	405.68	15.03
95+00	9.01	7.34	50.00	367.23	13.60
95+50	5.67	7.17	50.00	358.51	13.28
96+00	8.67	18.49	50.00	924.34	34.23
96+50	28.31	17.84	50.00	892.01	33.04
97+00	7.37	7.39	50.00	369.40	13.68
97+50	7.40	7.40	4.00	29.61	1.10
97+54	7.40	3.70	46.00	---	---
98+00	0.00	0.00	50.00	0.00	0.00
98+50	0.00	0.00	50.00	0.00	0.00
99+00	0.00	0.00	50.00	0.00	0.00
99+50	0.00	0.00	50.00	0.00	0.00
100+00	0.00	0.97	50.00	48.35	1.79
100+50	1.93	1.55	50.00	77.72	2.88
101+00	1.17	1.27	50.00	63.70	2.36
101+50	1.37	0.69	50.00	34.32	1.27
102+00	0.00	1.61	50.00	80.56	2.98
102+50	3.22	2.89	50.00	144.43	5.35
103+00	2.55	1.28	50.00	63.87	2.37
103+50	0.00	---	---	---	0.00
ABUT.	0.00	---	---	---	0.00
BRIDGE	0.00	---	---	---	0.00
TOTAL				246	

ILLINOIS ROUTE 64 CUT					
CUT (SF)	AVE	LENGTH	TOTAL	TOT (CY)	
88+50	0.00	0.00	50.00	0.00	0.00
89+00	0.00	0.00	50.00	0.00	0.00
89+50	0.00	0.37	50.00	18.72	0.69
90+00	0.75	0.38	50.00	18.76	0.69
90+50	0.00	0.63	50.00	31.65	1.17
91+00	1.26	0.63	50.00	31.62	1.17
91+50	0.00	36.38	50.00	1818.95	67.37
92+00	72.76	75.19	50.00	3759.32	139.23
92+50	77.62	70.95	50.00	3547.30	131.38
93+00	64.28	54.70	50.00	2735.12	101.30
93+50	45.13	32.27	50.00	1613.30	59.75
94+00	19.40	9.71	50.00	485.75	17.99
94+50	0.03	0.01	50.00	0.73	0.03
95+00	0.00	0.00	50.00	0.17	0.01
95+50	0.00	0.01	50.00	0.25	0.01
96+00	0.01	0.01	50.00	0.26	0.01
96+50	0.00	0.00	50.00	0.17	0.01
97+00	0.00	9.24	50.00	461.83	17.10
97+50	18.47	18.47	4.00	73.88	2.74
97+54	18.47	9.23	46.00	---	---
98+00	0.00	0.00	50.00	0.00	0.00
98+50	0.00	0.00	50.00	0.00	0.00
99+00	0.00	0.00	50.00	0.00	0.00
99+50	0.00	0.00	50.00	0.00	0.00
100+00	0.00	1.59	50.00	79.60	2.95
100+50	3.18	16.13	50.00	806.48	29.87
101+00	29.08	38.02	50.00	1901.11	70.41
101+50	46.97	50.96	50.00	2547.90	94.37
102+00	54.95	58.75	50.00	2937.26	108.79
102+50	62.54	60.57	50.00	3028.74	112.18
103+00	58.61	29.30	50.00	1465.15	54.26
103+50	0.00	---	---	---	0.00
ABUT.	0.00	---	---	---	0.00
BRIDGE	1328.81	---	---	---	1328.81
TOTAL				2342	

ILLINOIS ROUTE 64 FILL					
FILL (SF)	AVE	LENGTH	TOTAL	TOT (CY)	
88+50	0.00	0.00	50.00	0.00	0.00
89+00	0.00	0.00	50.00	0.00	0.00
89+50	0.00	0.25	50.00	12.44	0.46
90+00	0.50	0.84	50.00	41.95	1.55
90+50	1.18	1.24	50.00	62.01	2.30
91+00	1.30	2.08	50.00	104.21	3.86
91+50	2.87	1.83	50.00	91.32	3.38
92+00	0.78	0.76	50.00	37.77	1.40
92+50	0.73	0.91	50.00	45.31	1.68
93+00	1.09	2.01	50.00	100.67	3.73
93+50	2.94	3.74	50.00	187.02	6.93
94+00	4.54	11.19	50.00	559.53	20.72
94+50	17.84	34.85	50.00	1742.73	64.55
95+00	51.87	70.64	50.00	3532.17	130.82
95+50	89.42	102.29	50.00	5114.40	189.42
96+00	115.16	146.66	50.00	7333.08	271.60
96+50	178.17	189.04	50.00	9452.13	350.08
97+00	199.92	226.99	50.00	11349.47	420.35
97+50	254.06	254.06	4.00	1016.24	37.64
97+54	254.06	127.03	46.00	---	---
98+00	0.00	0.00	50.00	0.00	0.00
98+50	0.00	0.00	50.00	0.00	0.00
99+00	0.00	0.00	50.00	0.00	0.00
99+50	0.00	0.00	50.00	0.00	0.00
100+00	23.63	11.81	50.00	590.63	21.88
100+50	5.61	14.62	50.00	730.76	27.07
101+00	0.64	3.12	50.00	156.13	5.78
101+50	0.28	0.46	50.00	22.94	0.85
102+00	0.00	0.14	50.00	6.94	0.26
102+50	0.00	0.00	50.00	0.04	0.00
103+00	1.64	0.82	50.00	41.10	1.52
103+50	0.00	0.82	50.00	41.06	1.52
ABUT.	24.06	---	---	---	24.06
BRIDGE	0.00	---	---	---	0.00
TOTAL				1593	

ILLINOIS ROUTE 64 UNSUITABLES					
UNSUITS(SF)	AVE	LENGTH	TOTAL	TOT (CY)	
8850	0.00	0.00	50.00	0.00	0.00
8900	0.00	0.00	50.00	0.00	0.00
8950	0.00	1.01	50.00	50.62	1.87
9000	2.02	1.72	50.00	85.99	3.18
9050	1.41	2.42	50.00	120.86	4.48
9100	3.42	2.82	50.00	141.20	5.23
9150	2.23	3.41	50.00	170.36	6.31
9200	4.59	5.18	50.00	259.17	9.60
9250	5.78	4.64	50.00	232.00	8.59
9300	3.50	3.19	50.00	159.75	5.92
9350	2.89	2.47	50.00	123.69	4.58
9400	2.06	2.9			