

**BEAM #17**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back of West Abut.	97+64.36	53.05	628.04	628.04
CL Brg. West Abut.	97+67.78	53.05	628.04	628.04
A	97+77.78	53.05	628.05	628.08
B	97+87.78	53.05	628.05	628.10
C	97+97.78	53.05	628.04	628.09
D	98+07.78	53.05	628.02	628.05
E	98+17.78	53.05	627.99	628.01
CL Brg. Pier 1	98+26.78	53.05	627.96	627.96
F	98+36.78	53.05	627.92	627.91
G	98+46.78	53.05	627.86	627.87
H	98+56.78	53.05	627.80	627.81
I	98+66.78	53.05	627.74	627.74
J	98+76.78	53.05	627.66	627.66
K	98+86.78	53.05	627.58	627.57
CL Brg. Pier 2	98+91.78	53.05	627.53	627.53
L	99+01.78	53.05	627.43	627.45
M	99+11.78	53.05	627.33	627.38
N	99+21.78	53.05	627.21	627.29
O	99+31.78	53.05	627.09	627.17
P	99+41.78	53.05	626.96	627.02
Q	99+51.78	53.05	626.83	626.85
CL Brg. East Abut.	99+56.78	53.05	626.76	626.76
Back of East Abut.	99+59.70	53.05	626.72	626.72

**BEAM #1a**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
At Bm. 1	99+51.78	-46.95	626.89	626.91
CL Brg. East Abut.	99+56.78	-49.83	626.77	626.77
Back of East Abut.	99+59.70	-51.52	626.69	626.69

**BEAM #17a**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
At Bm. 17	99+49.28	53.05	626.86	626.89
CL Brg. East Abut.	99+56.78	57.39	626.70	626.70
Back of East Abut.	99+59.70	59.07	626.64	626.63

FILE NAME = W:\191-130-1001-11.64\CADD\_Sheets\Structure\1160J11-11-11\_TopSlab.dgn



USER NAME =	DESIGNED - JJI	REVISED
	CHECKED - JMT	REVISED
PLOT SCALE =	DRAWN - GJE	REVISED
PLOT DATE = 8/15/2013	CHECKED - JMT	REVISED

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**TOP OF SLAB ELEVATIONS V  
STRUCTURE NO. 016-3035**  
SHEET NO. 14 OF 62 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	541Y-3-B	COOK	143	75
CONTRACT NO. 60J11				
ILLINOIS FED. AID PROJECT				