



- Ⓐ EXISTING STOCKPILE BY OTHERS-16017+50 TO 16021+11 RT  
APPROXIMATE VOLUME: 650 CU YD  
PAID FOR AS EARTH EXCAVATION
- Ⓑ EXISTING STOCKPILE BY OTHERS-16035+54 TO 16036+40 LT  
APPROXIMATE VOLUME: 265 CU YD  
PAID FOR AS EARTH EXCAVATION
- Ⓒ EXISTING STOCKPILE BY OTHERS-16036+86 TO 16040+05 LT  
APPROXIMATE VOLUME: 1325 CU YD  
PAID FOR AS EARTH EXCAVATION
- Ⓓ EXISTING STOCKPILE BY OTHERS-APPROX. 3660 CU YD  
VERIFY QUANTITY WITH ENGINEER  
PAID FOR AS FURNISHED EXCAVATION, SPECIAL

**SIGN NOTES:**  
 THE TRUCKS LEAVING HIGHWAY SIGN SHALL BE REMOVED OR TURNED AWAY FROM TRAFFIC AND THE EXIT AND ENTRY OPENINGS SHALL BE CLOSED WHEN THE FLAGGING OPERATIONS CEASES.  
 ALL VEHICLES SHALL ENTER THE WORK ZONE AT ENTRY OPENINGS, USING THEIR TURN SIGNALS TO WARN MOTORISTS.

<b>TYLIN INTERNATIONAL</b>	USER NAME	DESIGNED - JTP	REVISED - 06/21/2013
	PLT SCALE	DRAWN - JTP	REVISED - 10/18/2013
	PLT DATE	CHECKED - JPM	REVISED
		DATE - 05/10/2013	REVISED

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**STUENKEL ROAD AT I-57 RIDGELAND AVENUE TO CENTRAL AVENUE  
EXISTING STOCKPILE EXCAVATION LOCATIONS**

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE. 57	SECTION 99-148-R1	COUNTY WILL	TOTAL SHEETS 679	SHEET NO. 141
CONTRACT NO. 60L69				
ILLINOIS FED. AID PROJECT				