



NOTES:
 1. All steel rail elements shall be galvanized according to Article 509.05 of the Standard Specifications.

BILL OF MATERIAL

Item	Unit	Quantity
Bridge Fence Railing (Sidewalk)	Foot	57
Parapet Railing	Foot	53

TYLIN INTERNATIONAL USER NAME - PLOT SCALE - PLOT DATE -	DESIGNED - PK CHECKED - SP	REVISED - 1/6/2014 S.P. REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BRIDGE FENCE RAILING, SIDEWALK MOUNTED STRUCTURE NO. 099-0526 SHEET NO. SA-70P SA-10 SHEETS	F.A.I. RTE. 57 SECTION 99-1HD-R1 COUNTY WILL TOTAL SHEETS 679 SHEET NO. 359 CONTRACT NO. 60L69
	DRAWN - PK CHECKED - SP/PDF	REVISED - REVISED -			ILLINOIS FED. AID PROJECT
	(10'-0" Maximum Post Spacing)				
	In lieu of the cast-in-place anchor device shown, the Contractor has the option of drilling and setting 5/8" φ anchor rods according to Article 509.06 of the Standard Specifications. Embedment shall be according to the manufacturer's specifications.				

P:\602612(1-57_0-stuenkel)\structure\c-3(interchange)\bridge\C3.stuenkel.BridgeRail\Inq\Drawings\Sheet Revised 1/27/2014 PM