CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER
				90% FED		90% FED	90% FED	90% FED
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE
				0004	0004	0011	0021	0044
				URBAN	URBAN	016-1708	URBAN	URBAN
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1448	1448				
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	98	98				
35301200	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	10	10				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	68	68				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3				
40600300	AGGREGATE (PRIME COAT)	TON	0.2	0.2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	19	19				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	34	34				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	44	44	A			
42001200	PAVEMENT FABRIC	SQ YD	98	98				
42001300	PROTECTIVE COAT	SQ YD	133	133				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	28	28				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1290	1290				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4771	4771				
44000100	PAVEMENT REMOVAL	SQ YD	2158	2158				

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICPATING ITEM

A Rev. 2-18-14 Rev.

TranSystems

0160W29-sht-500.dgn	DESIGNED - JLV	REVISED -
USER NAME = JTRubley	DRAWN - BAW	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 11/6/2013	DATE - 10/30/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET 3 OF 17 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	8
		CONTRACT NO. 60W29		
	ILLINOIS	FED. AID PROJECT		

FILE PATH = pw:\\388939-pwmt-aecomonline.local:PWMEDCOM001\Documents\01 Projects\Transportation\60269938 Cicero\Phase I\0000 Contracts\60W29 Contract\0160W29-sht-500.dgn