CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER
				90% FED		90% FED	90% FED	90% FED
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE
				0004	0004	0011	0021	0044
				URBAN	URBAN	016-1708	URBAN	URBAN
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1448	1448				
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	98	98				
35301200	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	10	10				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	68	68				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3				
40600300	AGGREGATE (PRIME COAT)	TON	0.2	0.2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	19	19				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	34	34				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	39	39				
42001200	PAVEMENT FABRIC	SQ YD	98	98				
42001300	PROTECTIVE COAT	SQ YD	133	133				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	28	28				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1290	1290				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4771	4771				
44000100	PAVEMENT REMOVAL	SQ YD	2158	2158				

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICPATING ITEM

Rev.

TranSystems

D160W29-sht-500.dgn	DESIGNED - JLV	REVISED -
USER NAME = JTRubley	DRAWN - BAW	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 11/6/2013	DATE - 10/30/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET 3 OF 17 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	8

CONTRACT NO. 60W29

ILLINOIS FED. AID PROJECT

FILE PATH = pw:\\pbworld.aecom.com:Local#WSEC0089\Documents\01 Projects\Transportation\60264938 Curb&Ramps\IL60W29 Curb&Ramps\Sheets\60W29_Contract\D160W29-sht-500.dgn