


SANGAMON ST.

PEORIA ST.



EXISTING ITS CONDUIT AND CABLES TO BE ABANDONED.

EXISTING ITS CABINET G1 TO REMAIN. DISCONNECT AND REMOVE CABLES TO BE ABANDONED (INCIDENTAL TO MAINTAINING ITS DURING CONSTRUCTION ITEM)

EXISTING ITS CONDUIT AND CABLES AT5 TO BE ABANDONED

EXISTING ITS CONDUIT AND CABLES TO BE ABANDONED

EXISTING HAND HOLE TO BE REPLACED

EXISTING ITS CABLES TO BE REPLACED BY OTHERS

EXISTING HAND HOLE TO REMAIN

EXISTING LOOPS TO BE REPLACED BY OTHERS

125+00

345+00

350+00

WB I-290

EXISTING ITS CABLES TO BE ABANDONED

EXISTING ITS CABINET Z3 TO BE REMOVED BY OTHERS

345+00
100+00


EB I-290

350+00

105+00



DI60W29-sht-ITS-01
USER NAME = BAW:tor t
PLOT SCALE = 60.0000 ' / in.
PLOT DATE = 12/19/2013

DESIGNED - JML
DRAWN - JML
CHECKED - WDS
DATE - 10/30/2013
REVISED -  12/18/2013
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ITS REMOVAL PLAN
I-290

SCALE: 1" = 30' SHEET 1 OF 3 SHEETS STA. 342+26 TO STA. 351+80

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	130
CONTRACT NO. 60W29				
ILLINOIS FED. AID PROJECT				

FILE PATH = p:\388035\pmt\aecon\line\local\PEACEDM\Documents\01_Americas\Transportation\60269938_Circle\Phase_1\000_CAD\005_Roadway\Sheets\60W29_Contract\DI60W29-sht-ITS-01