

| SUMMARY OF QUANTITIES | | | URBAN 100% STATE TOTAL CONSTRUCTION TYPE CODE | | | | | | SUMMARY OF QUANTITIES | | | URBAN 100% STATE TOTAL CONSTRUCTION TYPE CODE | | | | | | |
|-----------------------|--|-------|---|-------|--|--|--|--|-----------------------|--|--------|---|-------|--|--|--|--|--|
| CODE NO | ITEM | UNIT | QUANTITIES | 0005 | | | | | CODE NO | ITEM | UNIT | QUANTITIES | 0005 | | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 25 | 25 | | | | | 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 4 | 4 | | | | | |
| 21400100 | GRADING AND SHAPING DITCHES | FOOT | 400 | 400 | | | | | 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 25 | 25 | | | | | 70100310 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701421 | L SUM | 1 | 1 | | | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 42 | 42 | | | | | 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | | | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 208 | 208 | | | | | 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 78 | 78 | | | | | 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 | | | | | |
| 40600827 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-A, 75, N50 | TON | 2040 | 2040 | | | | | 70102632 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602 | L SUM | 1 | 1 | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 3 | 3 | | | | | 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 454 | 454 | | | | | 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 17884 | 17884 | | | | | |
| 40603395 | HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 | TON | 5082 | 5082 | | | | | 70300210 | TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS | SQ FT | 510 | 510 | | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 34 | 34 | | | | | 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 50090 | 50090 | | | | | |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 51847 | 51847 | | | | | 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 1823 | 1823 | | | | | |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SQ YD | 440 | 440 | | | | | 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 263 | 263 | | | | | |
| 44201757 | CLASS D PATCHES, TYPE III, 9 INCH | SQ YD | 230 | 230 | | | | | 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 866 | 866 | | | | | |
| 44201759 | CLASS D PATCHES, TYPE IV, 9 INCH | SQ YD | 1154 | 1154 | | | | | 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 170 | 170 | | | | | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 420 | 420 | | | | | 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 19500 | 19500 | | | | | |

| | | | | | | | | | | | | | | | | | |
|---|--------------------|------------|---|---|--|--|--|-----------------------|--|--|--|---------------------|-------------------|----------------|-----------------------------|-------------------|--|
| FILE NAME * c:\pr\work\plan\joseph\0358445\040714-shi-plan.dgn | USER NAME * Joseph | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | | | | SUMMARY OF QUANTITIES | | | | F.A. RTE. 880 | SECTION 32RS-6 | COUNTY LAKE | TOTAL SHEET SHEETS 26 | SHEET NO. 3 | |
| PLOT SCALE * 1/8"=1'-0" | CHECKED - | REVISED - | SCALE: | | | | | | | | | SHEET NO. OF SHEETS | STA. | TO STA. | CONTRACT NO. 60X26 | | |
| PLOT DATE * 12/10/2013 | DATE - | REVISED - | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | | | | | | | | | | | |