

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0021			
				QUANTITY	QUANTITY	QUANTITY	QUANTITY
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	7	2	5		
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	2			
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1		
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2			
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	1			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	24	12	12		
88500100	INDUCTIVE LOOP DETECTOR	EACH	9		9		
88600100	DETECTOR LOOP, TYPE I	FOOT	878		878		
88700200	LIGHT DETECTOR	EACH	3			3	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1	
88800100	PEDESTRIAN PUSH BUTTON	EACH	4	4			
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1		
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	2				2
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1				1

14) \* SPECIALTY ITEMS

Rev. 2-18-14

FILE NAME *	USER NAME *	DESIGNED -	REVISED -
\\MICROST\352109\06-SUMMARY.DGN	JGC	BPT	-
		DRAWN -	REVISED -
		RDS/JGC	-
		CHECKED -	REVISED -
		BPT	-
		DATE -	REVISED -
		11-29-13	-

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
U.S. ROUTE 6 (159TH STREET) AT OAK PARK AVENUE AND 71ST COURT  
SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

PREPARED BY:  
**CEMCON, Ltd.**  
Consulting Engineers, Land Surveyors & Planners  
2280 White Oak Circle, Suite 100  
Aurora, Illinois 60504-9675  
Ph: 630.862.2100 Fax: 630.862.2199  
E-Mail: cadd@cemcon.com WebSite: www.cemcon.com

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	2013-061TS	COOK	30	6
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60X33	