

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE OO21
20101200	TREE ROOT PRUNING	EACH	6	6
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5	5
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	6	6
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27
20101500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	27	27
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	27
20200100	EARTH EXCAVATION	CU YD	498	498
20800150	TRENCH BACKFILL	CU YD	5	5
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	1450	1450
21400100	GRADING AND SHAPING DITCHES	FOOT	200	200
25000100	SEEDING, CLASS 1	ACRE	0.32	0.32
25100630	EROSION CONTROL BLANKET	SQ YD	1450	1450
28000400	PERIMETER EROSION BARRIER	FOOT	260	260
28000500	INLET AND PIPE PROTECTION	EACH	7	7
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1311 11795	1311 11795
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	11	11
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16	16

02/17/2014
PER IDOT
MODIFICATION

40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	8	8
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	8	8
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	11795	11795
42400800	DETECTABLE WARNINGS	SQ FT	8	8
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	53	53
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7	7
44000600	SIDEWALK REMOVAL	SQ FT	105	105
* 50901720	BICYCLE RAILING	FOOT	30	30
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	56	56
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	7	7
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	110	110
63200310	GUARDRAIL REMOVAL	FOOT	54	54
67100100	MOBILIZATION	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	70	70
* LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2	2
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	2	2
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	205.6	205.6

* SPECIALTY ITEMS

PLAN	SURVEYED	DATE
NO.	BY	
NOTE BOOK	PLOTTED	DATE
NO.	BY	
	CHECKED	DATE
	BY	
	DATE	

PROFILE	SURVEYED	DATE
NO.	BY	
NOTE BOOK	PLOTTED	DATE
NO.	BY	
	CHECKED	DATE
	BY	
	DATE	