

SUMMARY OF QUANTITIES

URBAN  
50%IL/50%IOWA

ITEM #	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0014
50102400	CONCRETE REMOVAL	CU YD	10.0		10.0
50157300	PROTECTIVE SHIELD	SQ YD	357		357
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.0		10.0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	29,322		29,322
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,240		1,240
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	94		94
52100540	ANCHOR BOLTS, 1 1/2"	EACH	4		4
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	1	1	
64300240	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3		3
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	553	553	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	184	184	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
X0321309	CONCRETE PAD	SQ YD	11		11
X0322559	BOLT REPLACEMENT	EACH	105		105
X0323391	STEEL BRIDGE RAIL POSTS	EACH	61		61
X0325583	REMOVE AND REINSTALL FINGER PLATE JOINT	EACH	2		2
X0090100	FURNISH AND INSTALL HANDRAIL	FOOT	3,404		3,404
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	28,769		28,769
Z0001905	STRUCTURAL STEEL REPAIR	POUND	49,140		49,140
Z0005880	BRIDGE HANDRAIL REMOVAL	FOOT	3,404		3,404
Z0010605	CLEANING DRAINAGE SYSTEM	L SUM	1	1	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	588		588
Z0018800	DRAINAGE SYSTEM	L SUM	1	1	
Z0021922	SILICONE JOINT SEALER	FOOT	14		14
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	22		22
Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	2		2
X0327943	CANOPY REPAIR	L SUM	1	1	
X0326233	GRINDING AND REMOVAL OF TACK WELDS	EACH	3		3
X0076001	TRAINERS TRAINING PROGRAM GRADUATE	HOOR	1000		1000

\* SPECIALTY ITEM

△ 0042

FILE NAME = I:\Projects\4015550\4015550\_0201\901\_CAD\_Models\_and\_Sheets\84\_Civil\Sheets\026428-500.dgn

USER NAME = shampard	DESIGNED - RDT/GC	REVISED -
DRAWN - RDT	CHECKED - JAC	DATE - 11-08-2013
PL0T SCALE = 20.0000' / in.		
PL0T DATE = 11/27/2013		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

US 67 OVER MISSISSIPPI RIVER STRUCTURE NO. 081-9905  
SUMMARY OF QUANTITIES 1

SCALE: SHEET NO. 3 OF 47 SHEETS STA. TO STA.

F.A.P. RTE. 308	SECTION 13BRM	COUNTY ROCK ISLAND	TOTAL SHEETS 47	SHEET NO. 3
C-92-090-12			CONTRACT NO. 64H28	
ILLINOIS FED. AID PROJECT HSIP-XXXX (XXX)				

△ Rev. 2-18-14

Rev.