

80% FED. / 20% STATE

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTR. CODE | |
|----------|---|--------|----------------|--------------|-------|
| | | | | ROADWAY | URBAN |
| 44000600 | SIDEWALK REMOVAL | 50 FT | 6898 | 6898 | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 506 | 506 | |
| 44200970 | CLASS B PATCHES, TYPE II, 10 INCH | 50 YD | 237 | 237 | |
| 44200974 | CLASS B PATCHES, TYPE III, 10 INCH | 50 YD | 20 | 20 | |
| 44200976 | CLASS B PATCHES, TYPE IV, 10 INCH | 50 YD | 167 | 167 | |
| 44201299 | DOWEL BARS 1 1/2" | EACH | 560 | 560 | |
| 44213200 | SAW CUTS | FOOT | 1524 | 1524 | |
| 44213204 | TIE BARS 3/4" | EACH | 62 | 62 | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 103 | 103 | |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 506 | 506 | |
| 66700205 | PERMANENT SURVEY MARKERS, TYPE I | EACH | 1 | 1 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | |

19

| | | | | | | | | | | | |
|-------------|--------------------|------------------|-----------------|---|---|--|---|-----------|--------|--------------|-----------|
| FILE NAME * | USER NAME * #USER# | DESIGNED - _____ | REVISED - _____ | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| #FILE# | | DRAWN - _____ | REVISED - _____ | | | | 697 | (17) RS-4 | FORD | 31 | 4 |
| #MODELNAME# | | CHECKED - _____ | REVISED - _____ | | SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____ | | ILLINOIS FED. AID PROJECT CONTRACT NO. 66A94 | | | | |
| | | DATE - _____ | REVISED - _____ | | | | | | | | |