

LOCATION: FAP 721 (IL 10)

PIATT COUNTY

RURAL

FUNDING BREAKOUT: 80% FEDERAL

20% STATE

CONSTRUCTION CODE: 0014

PAY ITEM CODE	PAY ITEM DESCRIPTION	UNIT	QTY.
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,644.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2.0
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1.0
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10.0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0
78300100	PAVEMENT MARKING REMOVAL	SO FT	260.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2.0
X5030305	CONCRETE WEARING SURFACE, 5"	SO YD	155.0
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	26.0
Z0004552	APPROACH SLAB REMOVAL	SO YD	187.0
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SO FT	23.0
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SO YD	375.0
Z0038700	PERMANENT BENCH MARKS	EACH	1.0

\* SPECIALTY ITEMS

**CB** Coombe-Bloxdorf P.C.  
 -CIVIL ENGINEERS-  
 -STRUCTURAL ENGINEERS-  
 -LAND SURVEYORS-  
 Design Firm License No. 184-002703

FILE NAME =	USER NAME = grazianoja	DESIGNED - MCB	REVISED -
c:\pwork\psidot\grazianoja\01345907	70432-ent-203-summary-quantities-201.dgn	DRAWN - CFC	REVISED -
	PLOT SCALE = 40.000000 ' / in.	CHECKED - MCB	REVISED -
CD PROJECT NO 08049-7	PLOT DATE = 10/25/2013	DATE - / /	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
721	(115BR) BR	PIATT	39	6
			CONTRACT NO. 70432	
ILLINOIS FED. AID PROJECT				