

FILE NAME =	USER NAME = keysrb	DESIGNED CME	REVISED -		BRINGE APPROACH
c:\pw_work\pwidot\keysrb\d0134590\07400	83-70432-008-ASD3.dgn	CHECKED GJB	REVISED -	STATE OF ILLINOIS	
	PLOT SCALE = 0:2.0000 ':' / in.	DRAWN MML	REVISED -	DEPARTMENT OF TRANSPORTATION	STRUCTURE NU
CB PROJECT NO. 08049-7	PLOT DATE = 1/24/2014	CHECKED MCB	REVISED -		SHEET NO. 8 OF

See sheets 6 and 7 of 18 for Detail A. Approach slab concrete shall be paid for as Concrete Superstructure. Approach footing concrete shall be paid for as Concrete Structures. Reinforcement shall be paid for as Reinforcement Bars, Epoxy Coated. For $v_1(E)$ bar details, see sheet 14 of 18, The approach footing maximum applied service bearing pressure (Qmax) = 2.0 ksf. For bar splicer details, see sheet 16 of 18. Cost of excavation for approach footing included with Concrete Structures.

* Tilt #9 $b_2(E)$ bars as required to maintain clearance.

TWO	APF	PROACHES
BILL	0F	MATERIAL

Bar	No.	Size	Length	Shape	
a ₂ (E)	50	#4	14′-0″		
a3(E)	92	#5	14'-0"		
04(E)	92	#5	18′-4″		
a5(E)	50	#4	18′-4″		
<i>b</i> 1(Ε)	54	#4	29'-8''		
b2(E)	158	#9	29'-9''	<u></u>	
t(E)	136	#4	9′-8′′		
w(E)	80	#5	14'-0"		
$w_I(E)$	80	#5	18′-4″		
Concrete	Concrete Superstructure			99.2	
Concrete	Concrete Structures Cu. Yd.			20.4	
Reinforcement Bars,			Pound	24.810	
Epoxy Co	area				

	Coombe-Bloxdorf P.C. -civil engineers- -structural engineers- -land surveyors-				7. 8-
of 3)	Design Firm License No. 184-002703				
SLAB DETAILS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
074_0003	721	(115BR)BR	PIATT	39	19
			CONTRACT	'NO.7	0432
18 SHEETS	ILLINOIS FED. AID PROJECT				