

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	M231 ACM	M232 ACRS	M231 ACM
				CONSTRUCTION CODE		
				STA. 97+55.22 TO STA. 142+00.00 FAU 7152 FED-80% STATE-20% ROADWAY 0004 URBAN	STA. 142+00.00 TO STA. 417+19.15 FAS 1512 FED-80% STATE-20% ROADWAY 0004 RURAL	COTTONWOOD DR. STA. 101+00.00 S. N. 010-2039 FED-80% STATE-20% BOX CULVERT 0011 URBAN
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	0.1	0.9	0.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	360.0	0.0	360.0	0.0
40600990	TEMPORARY RAMP	SQ YD	80.0	20.0	60.0	0.0
40603082	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N50	TON	4,608.0	2,409.0	2,199.0	0.0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	7,636.0	1,428.0	6,208.0	0.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	235.0	16.0	219.0	0.0
40800030	AGGREGATE (PRIME COAT)	TON	5.0	1.0	4.0	0.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	263.0	18.0	245.0	0.0
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	13.0	0.0	13.0	0.0
44000100	PAVEMENT REMOVAL	SQ YD	1,698.0	733.0	965.0	0.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	72,727.0	6,041.0	66,686.0	0.0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	13.0	0.0	13.0	0.0
44000400	GUTTER REMOVAL	FOOT	40.0	0	40	0
44004250	PAVED SHOULDER REMOVAL	SQ YD	77.0	38.0	39.0	0.0
44022051	PARTIAL DEPTH REMOVAL 8 1/2"	SQ YD	4,018.0	0.0	4,018.0	0.0

* SPECIALTY ITEM

CONT'D NEXT SHEET

FILE NAME *	USER NAME * sherec_jm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\p\dtd\sherec_jm\0120316\057263-sht-500.dgn		DRAWN -	REVISED -		SCALE: N/A	SHEET 3	OF 11	SHEETS	STA.	TO STA.	Champaign	551	9
		CHECKED -	REVISED -								* FAU 7152 & FAS 1512	CONTRACT NO. 70663	
		DATE -	REVISED -								ILLINOIS FED. AID PROJECT		