

M231  
ACM

M232  
ACRS

M231  
ACM

CONSTRUCTION CODE

STA. 97+55.22 TO STA. 142+00.00 FAU 7152 FED-80% STATE-20% ROADWAY	STA. 142+00.00 TO STA. 417+19.15 FAS 1512 FED-80% STATE-20% ROADWAY	COTTONWOOD DR. STA. 101+00.00 S.N. 010-2039 FED-80% STATE-20% BOX CULVERT
---	--	---

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				0004 URBAN	0004 RURAL	0011 URBAN
54011203	PRECAST CONCRETE BOX CULVERTS 12' X 3'	FOOT	156.0	0.0	0.0	156.0
54011204	PRECAST CONCRETE BOX CULVERTS 12' X 4'	FOOT	82.0	82.0	0.0	0.0
54213447	END SECTIONS 12"	EACH	8.0	0.0	8.0	0.0
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3.0	0.0	3.0	0.0
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2.0	0.0	2.0	0.0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2.0	0.0	2.0	0.0
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2.0	2.0	0.0	0.0
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2.0	2.0	0.0	0.0
54214290	END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	22.0	2.0	20.0	0.0
54214500	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	2.0	0.0	2.0	0.0
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	200.0	100.0	100.0	0.0
54248510	CONCRETE COLLAR	CU YD	2.0	0.0	2.0	0.0
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	31.0	0.0	31.0	0.0
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	50.0	0.0	50.0	0.0
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	37.5	37.5	0.0	0.0

\* SPECIALTY ITEM

CONT'D NEXT SHEET

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
er:\pwork\p\idot\shererjm\id0120316\0570663-akt-500.dgn	shererjm	-	-		SCALE: N/A	SHEET 6	OF 11 SHEETS	STA.	TO STA.	12X3RS-3 & 2RS-4	Champaign	551	12
		DRAWN	REVISED							FAU 7152 & FAS 1512			
		CHECKED	REVISED								CONTRACT NO. 70663		
		DATE	REVISED										

ILLINOIS FED. AID PROJECT