

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	M231	M232	M231
				ACM	ACRS	ACM
				CONSTRUCTION CODE		
				STA. 97+55.22 TO STA. 142+00.00 FAU 7152 FED-80% STATE-20% ROADWAY	STA. 142+00.00 TO STA. 417+19.15 FAS 1512 FED-80% STATE-20% ROADWAY	COTTONWOOD DR. STA. 101+00.00 S. N. 010-2039 FED-80% STATE-20% BOX CULVERT
				0004 URBAN	0004 RURAL	0011 URBAN
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	76.0	76.0	0.0	0.0
542A5470	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	37.0	0.0	37.0	0.0
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	147.0	0.0	147.0	0.0
542D5470	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	420.0	40.0	380.0	0.0
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	191.0	0.0	191.0	0.0
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	50.0	30.0	20.0	0.0
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3.0	0.0	3.0	0.0
60500050	REMOVING CATCH BASINS	EACH	3.0	0.0	3.0	0.0
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	66.0	5.0	61.0	0.0
60602500	CONCRETE GUTTER, TYPE A	FOOT	1,117.0	0.0	1,117.0	0.0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	911.0	0.0	911.0	0.0
60615400	PAVED DITCH, TYPE A-15	FOOT	105.0	70.0	35.0	0.0
61101030	STORM SEWERS PROTECTED, CLASS A, 30"	FOOT	177.0	85.0	92.0	0.0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,050.0	437.5	612.5	0.0
* 63000007	STEEL PLATE BEAM GUARDRAIL, TYPE B, 6 FOOT POSTS	FOOT	300.0	200.0	100.0	0.0

* SPECIALTY ITEM

CONT'D NEXT SHEET

FILE NAME = c:\pwwork\pudot\shorer\j\0120316\0572063-shr-500.dgn	USER NAME = shorerjm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 48,0000 1/4 in.	PLOT DATE = 10/18/2013	DRAWN -	REVISED -						• (2X,3RS-3 & 2RS-4	Champaign	951	13	
		CHECKED -	REVISED -		• FAU 7152 & FAS 1512	CONTRACT NO. 70663							
		DATE -	REVISED -		SCALE: N/A	SHEET 7	OF 11 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				