STORM SEWER, CLASS A, TYPE 1 12" = 41.0'

204+28.67 ℄ CEMETERY ENTR. HMA SURFACE

204+91.90 ℄ PR. F.E. AGG. SURFACE

PIPE CULV. CLASS D, TYPE 1 ERS - 15" = 39.0'
STA. 204+72.41, 28.90' LT, ELEV = 695.02
STA. 205+11.41, 28.90' LT, ELEV = 694.22
END SECTIONS ERS - 15" = 2 EA.

SEC. 7, T. 19 N, R. 10 E.

28-22-07-300-002
HERSHBARGER, MAX L.
AS TRUSTEE
57300010

209+94.00 A.R. PIPE CULVERT
PIPE CULVERT, CLASS A, TYPE 1 18" = 50.0'
U.S.F.L. 25.00' RT, 209=94.00, ELEV = 689.78
D.S.F.L. 25.00' LT, 209+94.00, ELEV = 689.63
PCC REINFORCED CONC. FLRD. ES, 18" = 2.0 EA.

N

210+00.00
40.00' LT

204+34.66
40.00' LT

24.0'

PROPOSED R.O.W.

EXISTING R.O.W.

MATCH LINE STA. 204+00

MATCH LINE STA. 210+00

204+45.33 LT

204+12.15 LT

204 | 205+00 | 206 | ℄ FAS 1512 (U.S. 150) | 207 | 208 | 209

12' 3' 3' 28'-0" 12' 3' 3' 18.79'

40' 40'

EXISTING R.O.W.

PERMANENT EASEMENT

204+46.80, 26.95' LT, ELEV. = 694.58
P.C. REINF. CONC. FLRD. ES 12" = 1 EA.

CSX TRANSPORTATION, INC.
5730001

AGG SHOULDERS-TYPE B, 6"

AGGREGATE SURFACE COURSE, TYPE B

HMA SHOULDERS, 6"

INCIDENTAL HMA SURFACING

SEC. 18, T. 19 N, R. 10 E.

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
NOTE BOOK
NO.
BY
DATE

PROFILE
CONTOURS PLOTTED
GRADES CHECKED
NOTE BOOK
NO.
STRUCTURE NOTATIONS CKD

700
698
696
694
692
690
688
686
684

-2.71%
-1.70%
-2.71%
-1.38%
-1.80%
-1.38%
-1.25%
-1.80%
-0.56%
-0.56%
-1.25%
-0.57%
-1.05%
-0.57%
-1.22%
-0.21%
-1.05%
-0.21%
-0.29%
-1.22%
+0.14%
+0.14%
-0.29%

℄ FAS 1512 (US 150)

PROP. RIGHT DITCH

PROP. LEFT DITCH

EXIST. RIGHT DITCH

EXIST. LEFT DITCH

	204+00	204+50	205+00	205+50	206+00	206+50	207+00	207+50	208+00	208+50	209+00	209+50	210+00
LEFT DITCH	696.11	695.19	694.27	693.34	692.41	691.79	691.18	690.78	690.39	690.14	689.90	689.94	689.98
	696.50	695.14	693.79	693.10	692.41	691.79	691.16	690.63	690.11	690.00	689.90	689.76	689.63
RIGHT DITCH	695.56	694.69	693.82	693.01	692.20	691.65	691.11	690.59	690.06	688.95	687.85	688.09	688.33
	695.50	694.65	693.80	692.90	692.00	691.72	691.44	691.15	690.87	690.26	689.65	689.72	689.78
	697.73	697.05	696.33	695.61	694.91	694.27	693.63	692.99	692.74	692.71	692.68	692.82	693.04
	697.80	697.12	696.40	695.68	694.98	694.34	693.70	693.06	692.81	692.78	692.75	692.89	693.11

FILE NAME =	USER NAME = aaerlock.jd	DESIGNED JMS	REVISED -
c:\pw_work\pwidot\aaerlock.jd\d0120316\D5706603-sht-plnprf.dgn		DRAWN JMS	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/18/2013	DATE 081610	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 150 MAINLINE
PLAN AND PROFILE SHEET

SCALE: 1" = 20' | SHEET NO. 19 OF 54 SHEETS | STA. 204+00 TO STA. 210+00.00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(2X,3)RS-3 & 2RS-4	Champaign	551	100
*	F.A.U. 7152 & F.A.S. 1512	CONTRACT NO. 70663		
	ILLINOIS FED. AID PROJECT			