

EARTHWORK SCHEDULE

COUNTY	LOCATION	EARTH EXCAVATION (CUT)	EARTH EXCAV. ADJUSTED FOR SHRINKAGE*	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD
DEWITT	LT 775+75.1 TO LT 137+99.8	1,055	791	82	709
	RT 753+88.9 TO RT 137+99.8	929	697	140	557
	DEWITT SUBTOTAL	1,985	1,488	223	1,266
MCLEAN	LT 145+91.3 TO LT 442+51.7	1,867	1,400	1,620	-220
	RT 145+19.9 TO RT 440+32.4	1,806	1,354	959	395
	MCLEAN SUBTOTAL	3,672	2,754	2,579	175
ACTUAL TOTAL		5,657	4,243	2,801	1,441
USED TOTAL		5,660			

*BASED ON SHRINKAGE FACTOR OF 25%

DEWITT / MCLEAN

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\keysrb\0313174\057094	4-sht-schedule.dgn	DRAWN -	REVISED -					71	(122,121)I	*	199	7
\$MODELNAME\$	PLOT SCALE = 80.0000' / in.	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 70984				
	PLOT DATE = 1/9/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							