

## SUMMARY OF QUANTITIES

LOCATION OF WORK: FAI-57 / (I-57)  
 INTERSTATE  
 URBAN  
 COUNTY: CHAMPAIGN  
 FUNDING BREAKOUT: 90% FED  
 10% STATE  
 CONSTRUCTION TYPE CODE: 0021

LOCATION OF WORK: FAI-57 / (I-57)  
 INTERSTATE  
 URBAN  
 COUNTY: CHAMPAIGN  
 FUNDING BREAKOUT: 90% FED  
 10% STATE  
 CONSTRUCTION TYPE CODE: 0021

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	98.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	45.0
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	224.0
44200612	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	146.0
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	3387.0
44213000	PATCHING REINFORCEMENT	SQ YD	3757.0
44213200	SAW CUTS	FOOT	7554.0
44213204	TIE BARS 3/4"	EACH	1560.0
45100200	CRACK FILLING	POUND	1235.0
67100100	MOBILIZATION	L SUM	1.0
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4226.0
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	19116.0

\* SPECIALTY ITEMS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
* 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	908.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	174.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6978.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	174.0
* 87502720	TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	4.0
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12.0
* X0326852	RADAR SPEED SIGN	EACH	4.0
* X0327693	HIGH FRICTION SURFACE TREATMENT	SQ YD	17800.0
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	121.0
Z0016702	DETOUR SIGNING	L SUM	1.0

\* SPECIALTY ITEMS