

SCHEDULE OF QUANTITIES

SHEET 1 OF 4

CLASS A PATCHING SCHEDULE, 13"

| LOCATION | STATION TO | STATION | PLAN LENGTH | ACTUAL LENGTH | AVERAGE WIDTH | 44200610 | 44200612 | 44200614 | 44213200 | 44213204 | 44213000 | 70300220 |
|-------------|------------|-----------|-------------|---------------|---------------|--------------|---------------|--------------|----------|---------------|------------------------|--------------------------------------|
| | | | | | | TYPE II, 13" | TYPE III, 13" | TYPE IV, 13" | SAW CUTS | TIE BARS 3/4" | PATCHING REINFORCEMENT | TEMPORARY PAVEMENT MARKING - LINE 4" |
| | | | | | | (SQ YD) | (SQ YD) | (SQ YD) | (FT) | (EACH) | (SQ YD) | (FT) |
| RAMP I-CA | 212+83.00 | 213+05.00 | 22.00 | 22.40 | 16.00 | | | 39.82 | 108.80 | 30.0 | 39.82 | 44.80 |
| RAMP I-CA | 216+97.00 | 217+03.00 | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-CA | 217+74.00 | 217+80.00 | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-CA | 222+00.00 | 222+06.00 | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-CA | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-CA | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-BD | 44+40.00 | 44+95.00 | 55.00 | 56.70 | 16.00 | | | 100.80 | 177.40 | 30.0 | 100.80 | 113.40 |
| RAMP I-BD | 47+12.00 | 49+77.00 | 265.00 | 273.60 | 16.00 | | | 486.40 | 611.20 | 30.0 | 486.40 | 547.20 |
| RAMP I-BD | 51+34.00 | 52+00.00 | 66.00 | 67.90 | 16.00 | | | 120.71 | 199.80 | 30.0 | 120.71 | 135.80 |
| RAMP I-BD | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-BC | 167+60.00 | 167+70.00 | 10.00 | 10.20 | 16.00 | | 18.13 | | 84.40 | 30.0 | 18.13 | 20.40 |
| RAMP I-BC | 170+44.00 | 170+54.00 | 10.00 | 10.20 | 16.00 | | 18.13 | | 84.40 | 30.0 | 18.13 | 20.40 |
| RAMP I-BC | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-BC | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-BC | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-BC | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-DA | 21+64.00 | 23+00.00 | 136.00 | 140.50 | 16.00 | | | 249.78 | 345.00 | 30.0 | 249.78 | 281.00 |
| RAMP I-DA | 24+35.00 | 24+50.00 | 15.00 | 15.50 | 16.00 | | | 27.56 | 95.00 | 30.0 | 27.56 | 31.00 |
| RAMP I-DA | 24+80.00 | 25+40.00 | 60.00 | 62.10 | 16.00 | | | 110.40 | 188.20 | 30.0 | 110.40 | 124.20 |
| RAMP I-DA | 25+80.00 | 26+05.00 | 25.00 | 25.90 | 16.00 | | | 46.04 | 115.80 | 30.0 | 46.04 | 51.80 |
| RAMP I-DA | 29+35.00 | 30+00.00 | 65.00 | 67.00 | 16.00 | | | 119.11 | 198.00 | 30.0 | 119.11 | 134.00 |
| RAMP I-DA | 30+68.00 | 31+06.00 | 38.00 | 38.90 | 16.00 | | | 69.16 | 141.80 | 30.0 | 69.16 | 77.80 |
| RAMP I-DA | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-DA | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-DA | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-DB | 131+95.00 | 132+05.00 | 10.00 | 10.20 | 16.00 | | 18.13 | | 84.40 | 30.0 | 18.13 | 20.40 |
| RAMP I-DB | 135+00.00 | 137+00.00 | 200.00 | 200.00 | 16.00 | | | 355.56 | 464.00 | 30.0 | 355.56 | 400.00 |
| RAMP I-DB | 138+50.00 | 139+00.00 | 50.00 | 50.70 | 16.00 | | | 90.13 | 165.40 | 30.0 | 90.13 | 101.40 |
| RAMP I-DB | 140+85.00 | 141+50.00 | 65.00 | 66.20 | 16.00 | | | 117.69 | 196.40 | 30.0 | 117.69 | 132.40 |
| RAMP I-DB | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-DB | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-DB | MISC | | 6.00 | 6.00 | 16.00 | 10.67 | | | 76.00 | 30.0 | 10.67 | 12.00 |
| RAMP I-AC | 2+75.00 | 3+38.00 | 63.00 | 65.30 | 16.00 | | | 116.09 | 194.60 | 30.0 | 116.09 | 130.60 |
| RAMP I-AC | 4+57.00 | 5+35.00 | 78.00 | 80.80 | 16.00 | | | 143.64 | 225.60 | 30.0 | 143.64 | 161.60 |
| RAMP I-AC | 6+30.00 | 7+19.00 | 89.00 | 92.50 | 16.00 | | | 164.44 | 249.00 | 30.0 | 164.44 | 185.00 |
| RAMP I-AC | 7+76.00 | 8+47.00 | 71.00 | 73.90 | 16.00 | | | 131.38 | 211.80 | 30.0 | 131.38 | 147.80 |
| RAMP I-AC | 9+35.00 | 11+84.00 | 249.00 | 256.90 | 16.00 | | | 456.71 | 577.80 | 30.0 | 456.71 | 513.80 |
| SUB-TOTAL = | | | | | | 170.72 | 54.39 | 2945.42 | 5934.80 | 1110.00 | 3170.53 | 3566.80 |
| | | | | | | SQ YD | SQ YD | SQ YD | FT | EACH | SQ YD | FT |