

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, GENERAL NOTES, HIGHWAY STANDARDS
- 3-6 SUMMARY OF QUANTITIES
- 7 EXISTING SITE PLAN, ACCESS AND MAINTENANCE OF TRAFFIC PLAN
- 8 WASTEWATER TREATMENT SYSTEM - EXISTING AND DEMOLITION PLAN
- 9 WASTEWATER TREATMENT SYSTEM - RENOVATION PLAN
- 10 SAND FILTER - SECTIONS AND DETAILS
- 11 LAGOON AND SAND FILTER STRUCTURE DETAILS
- 12 ALTERNATING DOSING SIPHON STRUCTURE DETAILS
- 13 LAGOON 2 - HDPE COVER SYSTEM DETAILS
- 14 EFFLUENT AERATION & METERING STRUCTURE DETAILS
- 15 EXISTING CHLORINATION MANHOLE MODIFICATION DETAILS
- 16 GENERAL ELECTRICAL INFORMATION AND ONE LINE DIAGRAM
- 17 ELECTRICAL SITE PLAN

HIGHWAY STANDARDS

- 000001-06 STANDARDS SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-02 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL EQUIVALENTS OF AN INCH AND FOOT
- 280001-07 TEMPORARY EROSION CONTROL SYSTEMS
- 601001-04 DRAINS, SUB-SURFACE
- 602401-03 MANHOLE, TYPE A
- 602601-03 FLAT SLAB TOP, PRECAST REINFORCED CONCRETE
- 602701-02 MANHOLE STEPS
- 664001-02 CHAIN LINK FENCE

GENERAL NOTES

1. G.N. 100:
ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.
2. G.N. 100A
ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION, INCLUDING CAD FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.
3. G.N. 280
TEMPORARY EROSION CONTROL SEEDING IS INCLUDED IN THE CONTRACT TO SEED DISTURBED AREAS DURING TIMES WHEN PERMANENT SEEDING IS NOT ALLOWED. SOME OR ALL OF THE TEMPORARY EROSION CONTROL SEEDING WILL BE DELETED IF IT IS POSSIBLE TO PLACE THE PERMANENT SEEDING AS THE WORK IS COMPLETED.
4. G.N. 550
THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING PIPE LENGTHS AND INVERTS PRIOR TO DEMOLITION. DISCREPANCIES FROM THE DRAWINGS SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY.
5. G.N. 1004J
COARSE AGGREGATE CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARDS SPECIFICATIONS.
6. EXISTING UTILITY LINES, SHOWN ON THE PLANS BASED ON RECORD INFORMATION, ARE LOCATED TO INDICATE THEIR PRESENCE AND APPROXIMATE LOCATIONS. THE CONTRACTOR SHALL NOTIFY THE DISTRICT OPERATIONS ENGINEER TWO WEEKS PRIOR TO COMMENCING ANY EXCAVATION THE STATE WILL LOCATE AND MARK THE HORIZONTAL LOCATION AND INDICATE THE DEPTH, WHERE THIS INFORMATION IS AVAILABLE. SHOULD ANY OF THE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATIONS, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF THE ENGINEER AND AT NO COST TO THE STATE.
7. THE EXISTING VERTICAL DATUM IS TEMPORARY BENCH MARK (TBM), FROM THE 1998 PROJECT. IT IS AN "X" CHISELED INTO THE TOP OF THE EXISTING SAND FILTER DOSING STRUCTURE AT REFERENCE GRADE 100.00. THE CONTRACTOR SHALL LOCATE A NEW TBM (RELATIVE TO THIS REFERENCE GRADE) PRIOR TO THE START OF ANY DEMOLITION TO AN AREA OUTSIDE OF THE DISTURBANCE LIMITS.
8. GRADING SHALL BE DONE BY HAND AROUND LIGHT POLES, UTILITY POLES, SIGN POSTS, SHRUBS, TREES OR OTHER NATURAL OR MAN-MADE OBJECTS WHERE SHALLOW FILLS OR CUTS ARE ADJACENT TO THE ITEMS. IT IS THE INTENT THAT THE LIMITS OF CONSTRUCTION BE SUCH AS TO PRESERVE IN THE ORIGINAL STATE AS MUCH AREA OF TEMPORARY EASEMENTS AS POSSIBLE. THE DECISION AS TO ITEMS TO REMAIN IN PLACE SHALL BE AS DIRECTED BY THE ENGINEER.

THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE PER CUBIC YARD FOR EARTH EXCAVATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
9. CLEARING OF VEGETATION PRIOR TO THE REMOVAL OF ANY EARTH EXCAVATION SHALL BE DONE IN ACCORDANCE WITH SECTION 201 OF THE STANDARD SPECIFICATIONS.
10. PRIOR TO THE PLACEMENT OF ANY EARTH EXCAVATION OR FURNISHED EXCAVATION, EXISTING GROUND SURFACES SHALL BE PREPARED IN ACCORDANCE WITH SECTION 205.03 OF THE STANDARD SPECIFICATIONS.



FILE NAME = 0570053-shu-gennote.dgn	USER NAME = tkoo	DESIGNED - WWS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES AND HIGHWAY STANDARDS	P.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 1:3000' / in.	DRAWN - TDK	REVISED -			55	FUNKS GROVE RA IMP. 2014-	MC LEAN	17	2	
	PLOT DATE = 1/15/2014	CHECKED - BEP	REVISED -			CONTRACT NO. 70A53					
		DATE - 12-13-2013	REVISED -			SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	