

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE ROADWAY 0004 ADAMS CO.	80% FEDERAL 20% STATE ROADWAY 0004 PIKE CO.	80% FEDERAL 20% STATE BRIDGE 0040 PIKE CO.
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	174		174	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	275		275	
20100500	TREE REMOVAL, ACRES	ACRE	12.5		12.5	
20200100	EARTH EXCAVATION	CU YD	20713	3125	17588	
20800150	TRENCH BACKFILL	CU YD	74	7	67	
25000100	SEEDING, CLASS 1	ACRE	2		2	
25000200	SEEDING, CLASS 2	ACRE	10	1.2	8.8	
25000350	SEEDING, CLASS 7	ACRE	0.5		0.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1117	135	982	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1117	135	982	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1117	135	982	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	24.8	2.9	21.9	
25100115	MULCH, METHOD 2	ACRE	12	1.2	10.8	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SO YD	2703		2703	

* SPECIALTY ITEM

FILE NAME : Z:\N\2010\18-013\12.IL-96 Pike Co to IL	USER NAME : mikel	DESIGNED - PSBA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57\MSV8\Design\SUMMARY OF QUANTITIES.dgn	DRAWN - NEL	REVISED -	1597			14 (W, RS-7)	ADAMS/PIKE	152	3	
PLOT SCALE : 100.0000 ' / in.	CHECKED - DBS	REVISED -	CONTRACT NO. 72781							
PLOT DATE : 0/22/2013	DATE - 08/15/2013	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE:	SHEET 1 OF 10 SHEETS		STA.	TO STA.	