

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | | |
|-------------------|--|--------------|----------------|--|---|--|
| | | | | 80% FEDERAL 20% STATE ROADWAY 0004 ADAMS CO. | 80% FEDERAL 20% STATE ROADWAY 0004 PIKE CO. | 80% FEDERAL 20% STATE BRIDGE 0040 PIKE CO. |
| | | | | | | |
| 542D0223 | PIPE CULVERTS, CLASS D, TYPE 1 18" | FOOT | 162 | | 162 | |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 69 | | 69 | |
| 550A0090 | STORM SEWERS, CLASS A, TYPE 1 18" | FOOT | 245 | 51 | 194 | |
| X4401198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | 50 YD | 18750 | 2254 | 16496 | |
| Z0005010 | HOT-MIX ASPHALT FOR PATCHING POTHOLES (COLD MIX) | TON | 100 | 9 | 91 | |
| Z0013200 | CONCRETE REFERENCE MARKERS | EACH | 6 | 3 | 3 | |
| Δ Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 0.5 | 0.5 | |
| * Z0016702 | DETOUR SIGNING | L SUM | 1 | | 1 | |
| Z0023602 | GRANULAR CULVERT BACKFILL | CU YD | 888 | | 865 | 23 |
| * Z0054517 | ROCK FILL - FOUNDATION | TON | 500 | 46 | 454 | |
| Z0064505 | SECTION CORNER MARKERS | EACH | 2 | 1 | 1 | |
| ∅ Z0076600 | TRAINEES | HOURS | 1000 | 500 | 500 | |
| Z0065796 | RIPRAP SLURRY | 50 YD | 533 | | 533 | |
| ∅ Z0076604 | TRAINEES - TRAINING PROGRAM GRADUATE | HOURS | 1000 | 500 | 500 | |

14

* SPECIALTY ITEM
∅ 0042

| | | | | | | | | | | | | |
|---|---|--|--|---|-----------------------|---------------------|-------------------------|----------------------|---------------------|-----------------|--------------------|---------------------------|
| FILE NAME * Z:\R\2010\VA-10-013.12.IL-16 Pike Co to IL | USER NAME * mikel 57\MSVB\Design\SUMMARY OF QUANTITIES.dgn | DESIGNED - PSBA DRAWN - NEL CHECKED - DBS DATE - 08/15/2013 | REVISED - Δ 10/28/2013 REVISED - REVISED - REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.S. RTE. 1597 | SECTION 14 (W, RS-7) | COUNTY ADAMS/PIKE | TOTAL SHEETS 152 | SHEET NO. 12 | CONTRACT NO. 72781 | ILLINOIS FED. AID PROJECT |
| | | | | SCALE: | SHEET 10 OF 10 SHEETS | STA. | TO STA. | | | | | |