

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY BRRP	BOX CULVERT BRRP	OVERFLOW BRIDGE BRRP	BRIDGE REPAIR BRRP
				80 FED / 20 ST RURAL 0004	80 FED / 20 ST S. N. 054-7069 0040	80 FED / 20 ST S. N. 054-0515 0011	80 FED / 20 ST S. N. 054-0009 0014
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	104	104			
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	137			137	
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	64	64			
54200253	PIPE CULVERTS, CLASS D, TYPE 1 48"	FOOT	71	71			
54201063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	249	249			
54213453	END SECTIONS 18"	EACH	8	8			
54213483	END SECTIONS 48"	EACH	2	2			
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2			
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1			1	
54261348	CONCRETE END SECTION, STANDARD 542001, 48", 1:3	EACH	2			2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	66			66	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	3,850	2,100	575	1,175	
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	50		50		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6			

14

\* SPECIALTY ITEM

FILE NAME :	USER NAME : sparkgr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\dot\sparkgr\10219896\0072882-411-500.dgn	DRAWN -	REVISED -	717						102B-1,102CR,102BR-21RS-5	LOGAN	218	9	
PLOT SCALE * 100.000 ' / in.	CHECKED -	REVISED -	CONTRACT NO. 72882										
PLOT DATE * Dec-04-2013 08:51:02AM	DATE -	REVISED -	SCALE:		SHEET NO. 6 OF 10 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT				