


PLAN



SECTION THRU CURB

- NOTES: 1) QUANTITIES FOR CURB REPAIR ARE ESTIMATED.

 EXACT LOCATIONS AND QUANTITIES SHALL BE
 DETERMINED BY THE ENGINEER.
 - 2) A MINIMUM LENGTH OF 4' SHALL BE USED FOR ALL CURB REPAIR AREAS.
 - 3) A MINIMUM DISTANCE OF 4' OF EXISTING CURB AND GUTTER SHALL REMAIN BETWEEN CURB REPAIR AREAS.



CURB REPAIR

NO. 6 TIE BARS SHALL BE INSTALLED AS SPECIFIED IN ARTICLE 420.10 (b) OF THE STANDARD SPECIFICATIONS

NO. 6 TIE BARS SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST FOR CURB REPAIR

| FILE NAME = | USER NAME = sparksgw | DESIGNED - | REVISED - | |
|---|------------------------------------|------------|-----------|---|
| c:\pw_work\pwidot\sparksgw\d0306018\D67 | F50-sht-details.dgn | DRAWN - | REVISED - | l |
| | PLOT SCALE = 40.0000 '/ in. | CHECKED - | REVISED - | l |
| Default | PLOT DATE = Dec-06-2013 09:55:17AM | DATE - | REVISED - | ı |

| STATE OF ILLINOIS | | | | | | |
|------------------------------|--|--|--|--|--|--|
| DEPARTMENT OF TRANSPORTATION | | | | | | |

| CURB REPAIR | | | | | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-------------|-------|----|--------|------|---------|----------------|---------------------------|----------|-----------------|--------------|
| | | | | | 666 | (26)RS,I | SANGAMON | 116 | 61 | |
| | | | | | | | | CONTRACT | NO. 7 | 72F50 |
| SCALE: | SHEET | OF | SHEETS | STA. | TO STA. | | ILLINOIS FED. AID PROJECT | | | |