

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MACOUPIN COUNTY		MENARD Co.
				CONSTRUCTION CODE		
				100% STATE IL 4	100% STATE IL 111	100% STATE IL 123
				PIPE CULVERT 0044 RURAL	BOX CULVERT 0044 URBAN	BOX CULVERT 0044 RURAL
20200100	EARTH EXCAVATION	CU YD	147			147
20400800	FURNISHED EXCAVATION	CU YD	358			358
44201365	CLASS C PATCHES, TYPE II, 11 INCH	SO YD	17	17		
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	2		1
50105220	PIPE CULVERT REMOVAL	FOOT	46	46		
50800105	REINFORCEMENT BARS	POUND	92			92
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16			16
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	40		40	
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	36			36
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	46	46		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2			2
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2		
54248510	CONCRETE COLLAR	CU YD	1.5			1.5
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	5	5		