

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FED 20% ST		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	189	189		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19810	19810		
40600300	AGGREGATE (PRIME COAT)	TON	396	396		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	231	231		
40600990	TEMPORARY RAMP	SO YD	173	173		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	16640	16640		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	133	133		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	18169	18169		
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SO YD	40	40		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	1693	1693		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	69	69		
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	153	153		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2758	2758		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FED 20% ST		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	13571	13571		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2262	2262		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	173871	173871		
*78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	50	50		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	971	971		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	179932	179932		
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28		

14

12

* SPECIALTY ITEM

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\p\work\pwidot\staffennk\08249366\0	74512-ahtr-000.dgn	DRAWN -	REVISED -			328	18,910RS-2	Wayne	23	3	
	PLOT SCALE = 1/8" = 1' / in.	CHECKED -	REVISED -			CONTRACT NO. 74512					
	PLOT DATE = 12/5/2013	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
						SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		