

URBAN

ILLINOIS DEPARTMENT OF TRANSPORTATION

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	
			10% STATE	90% FEDERAL
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	30	30
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3615	3615
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	404	404
X0323583	SPEED INDICATOR SIGN	CAL DA	302	302
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	676	676
X4420553	CLASS A PATCHES, TYPE II, 10 INCH (SPECIAL)	SQ YD	84	84
X4420557	CLASS A PATCHES, TYPE III, 10 INCH (SPECIAL)	SQ YD	27	27
X6050310	FILLING INLETS, SPECIAL	EACH	8	8
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	4	4
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	300	300
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
X5200212	FINGER PLATE EXPANSION JOINT, 4 1/2"	FOOT	116	116
∅ Z0076600	TRAINEES	HOUR	1000	1000
∅ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1000	1000

∅ 0042

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#	PLOT SCALE = *SCALE*	DRAWN -	REVISED -			255	82-4HVB-1	ST. CLAIR	46	5A	
	PLOT DATE = *DATE*	CHECKED -	REVISED -			CONTRACT NO. 76051		ILLINOIS FED. AID PROJECT			
		DATE -	REVISED -			SCALE:	SHEET NO. 4 OF 4 SHEETS	STA.	TO STA.		