

INDEX OF SHEETS

- 1. COVER SHEET
- 2. INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES & COMMITMENTS
- 3.,4. SUMMARY OF QUANTITIES
- 5.,6. TYPICAL SECTIONS
- 7.-10. SCHEDULES
- 11.-13. PLAN & PAVEMENT MARKING, & EROSION CONTROL SHEETS
- 14.,15. DETAILS
- 16.-28. CROSS SECTIONS

COMMITMENTS

NONE

STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001006 DECIMALS OF AN INCH AND OF A FOOT
- 280001-07 TEMPORARY EROSION CONTROL SYSTEMS
- 406201-01 MAILBOX TURNOUT
- 442101-07 CLASS B PATCHES
- 442201-03 CLASS C AND D PATCHES
- 642006 SHOULDER RUMBLE STRIPS, 8 INCH
- 701001-02 OFF-RD OPERATIONS, 2L,2W, MORE THAN 15' AWAY
- 701006-05 OFF-RD OPERATIONS, 2L,2W, 15' TO 24" FROM PAVEMENT EDGE
- 701011-04 OFF-RD MOVING OPERATIONS, 2L,2W, DAY ONLY
- 701201-04 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
- 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701306-03 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH
- 701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
- 701326-04 LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH
- 701336-06 LANE CLOSURE, 2L, 2W, WORK AREAS IN SERIES, FOR SPEEDS ≥ 45 MPH
- 701901-03 TRAFFIC CONTROL DEVICES
- 780001-04 TYPICAL PAVEMENT MARKINGS
- 781001-03 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

GENERAL NOTES

- 1. NO OVERNIGHT LANE CLOSURES SHALL BE ALLOWED ON THE PROJECT.
- 2. SIDEROADS AND ENTRANCES SHALL BE OPEN TO TRAFFIC AT ALL TIMES.
- 3. THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT MIXTURE IS PLACED.
- 4. THE PROPOSED PAVEMENT MARKING SHALL MATCH THE LOCATIONS OF THE EXISTING PAVEMENT MARKING, AS DIRECTED BY THE ENGINEER.
- 5. THE CONTRACTOR SHALL ONLY REMOVE THE EXISTING GUTTER ON ONE SIDE OF IL 3 AT A TIME AND SHALL PLACE THE HMA SHOULDERS, 8" WITHIN 10 DAYS OF THE GUTTER REMOVAL.
- 6. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 7. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

UTILITY	ABOVE GROUND	BELOW GROUND
* AMEREN ILLINOIS	X	X
* FRONTIER NORTH, INC.	X	X
* CITY OF CHESTER		X
* VILLAGE OF ELLIS GROVE		X

MEMBERS OF J.U.L.I.E. CALL TOLL FREE (800) 892-0123 OR 811 AND ARE INDICATED BY *. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- 8. A QUANTITY OF 100 SQ YDS OF PARTIAL DEPTH PATCHING (SPECIAL) AND PARTIAL DEPTH REMOVAL 2 1/2", HAVE BEEN INCLUDED IN THE PLANS TO BE USED AT THE DISCRETION OF THE RESIDENT ENGINEER.
- 9. EXISTING RIGHT OF WAY WAS DRAWN FROM MICROFILM AND SHOULD BE CONSIDERED APPROXIMATE.
- 10. FLAGGERS SHALL BE REQUIRED AT ALL TIMES DURING PATCHING OPERATIONS.
- 11. THE RESIDENT ENGINEER SHALL VERIFY THE EXISTENCE OF HIGHWAY LIGHTING AND/OR I.T.S. UTILITIES WITHIN THE PROJECT LIMITS. IF HIGHWAY LIGHTING AND/OR I.T.S. EXISTS WITHIN THE PROJECT LIMITS, AND IF THESE ITEMS REQUIRE LOCATING, THE CONTRACTOR SHALL BE DIRECTED TO DO SO ACCORDING TO SECTION 803 OF THE STANDARD SPECIFICATIONS. THIS WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
- 12. THE PROPOSED SLOPES ARE TO BE GRADED ONLY TO ACHIEVE POSITIVE DRAINAGE OF NEW 4' SHOULDER SLOPE PROFILE, NOT TO REGRADE THE ENTIRE FORESLOPE.
- 13. ALL AREAS DISTURBED FOR ANY REASON SHALL BE PERMANENTLY SEEDED AS DIRECTED BY THE ENGINEER. ALL AREAS DISTURBED BY THE CONTRACTOR OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE SEEDED AT THE CONTRACTOR'S EXPENSE.
- 14. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.
- 15. A NOTCHED WEDGE LONGITUDINAL JOINT SHALL BE USED BETWEEN SUCCESSIVE PASSES OF HMA SURFACE COURSE THAT HAS A DIFFERENCE IN ELEVATION OF GREATER THAN 2 IN. BETWEEN LANES ON PAVEMENT THAT IS OPEN TO TRAFFIC. THE LONGITUDINAL JOINT SHALL BE CONSTRUCTED ACCORDING TO ARTICLE 406.06 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

FILE NAME =	USER NAME = dntalmn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, & COMMITMENTS			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\p\work\pudot\dntalmn\140301166\076f89\hst-plan.dgn		DRAWN -	REVISED -		312	74-IRS-1	RANDOLPH	28	2			
PLOT SCALE = 100.0000 ' / 1"		CHECKED -	REVISED -		CONTRACT NO. 76F89							
PLOT DATE = 12/5/2013		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							
				SCALE: N/A		SHEET NO. 1 OF 1 SHEETS		STA. TO STA.				