

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		CODE NO	ITEM	UNIT		80% FED 20% STATE 0005	
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	10490	10490	* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15758	15758		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	14	14		
67100100	MOBILIZATION	L SUM	1	1	* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	74	74		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	* 78200300	PRISMATIC CURB REFLECTOR	EACH	10	10		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	74	74		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	X0556100	PARTIAL DEPTH PATCHING (SPECIAL)	SQ YD	100	100		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	* Z0036200	PAINT CURB	FOOT	54	54		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	595	595	Ø Z0076600	TRAINEES	HOUR	1000	1000		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15758	15758	Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1000	1000		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	14	14							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	198	198							

* SPECIALTY ITEM Ø 0042

FILE NAME =	USER NAME = dntselmanjn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
o:\p\work\pudot\dntselmanjn\0301166\0376F89-4ht-plan.dgn	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -			312	74-JRS-1	RANDOLPH	28	4	
PLOT DATE = 12/5/2013	DATE -	CHECKED -	REVISED -			CONTRACT NO. 76F89					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					