

RESURFACING SCHEDULE

STATION		AGG. PRIME COAT (TON)	BIT. MAT'L PRIME COAT (TON)	HMA SURF. COURSE, MIX "D", N90 (TON)	INCIDENTAL			HMA SHOULDERS 11" (SQ YD)	HMA SHOULDERS 2 1/4" (TON)	AGGREGATE SHOULDER TYPE B 8" (SQ YD)	AGGREGATE SHOULDER TYPE B (TON)	STRIP REFL. CRACK CONTROL TREATMENT (FT)	CONCRETE CURB, TYPE B (FT)	HMA SURFACE REMOVAL, 2 1/4 (SQ YD)	PAVED SHOULDER REMOVAL (SQ YD)	TEMPORARY RAMP (SQ YD)	SHOULDER RUMBLE STRIPS, 8 INCH (FT)
					AGG. PRIME COAT (TON)	BITUMINOUS MATERIAL PRIME COAT (TON)	HMA SURFACING (TON)										
661+00.00 RT/LT TO 661+45.00 RT/LT	MAINLINE															120	
661+00.00 RT/LT TO 699+00.00 RT/LT	MAINLINE	15.20	3.17	1276.80										10133.33			
662+65.50 RT TO 670+00.00 RT	SHOULDER									621.61							
8+23.00 RT TO 664+00.00 LT	SHOULDER							83.92									
0+37.75 LT TO 666+00.00 RT	SHOULDER							161.34							83.92		
666+00.00 RT TO 673+00.00 RT	SHOULDER								39.20			700.00		311.11			700.00
668+55.87 LT TO 673+00.00 LT	SHOULDER								24.87			444.13		197.39			444.13
673+00.00 RT/LT TO 699+00.00 RT/LT	SHOULDER								218.40			5200.00		1733.33			5200.00
699+00.00 RT/LT TO 700+00.00 RT/LT	MAINLINE & SHLD	0.42	0.09	35.00					7.00			200.00		305.56			
700+00.00 RT/LT TO 707+00.00 RT/LT	MAINLINE	3.03	0.63	254.80								1400.00		2022.22			
700+00.00 LT TO 707+12.90 LT	SHOULDER								19.96					158.42			
700+00.00 RT TO 707+23.10 RT	SHOULDER								20.25					160.69			
707+00.00 RT/LT TO 708+00.00 RT/LT	MAINLINE	0.42	0.09	35.00								100.00		277.78			
708+00.00 RT/LT TO 760+12.79 RT/LT	MAINLINE	20.85	4.35	1755.39								5212.79		13900.77			
760+12.79 RT/LT TO 822+75.00 RT/LT	MAINLINE	25.05	5.23	2104.10								12524.42		16699.23			
760+12.79 RT/LT TO 808+61.00 RT/LT	SHOULDER								407.25					3232.14			
764+00.00 RT/LT TO 773+00.00 RT/LT	SHOULDER																1800.00
MINTON RD RT/LT	SIDEROAD				0.70	0.15	59.04				6.06			468.57			
777+00.00 RT/LT TO 821+00.00 RT/LT	SHOULDER																8800.00
808+61.00 RT/LT TO 822+61.00 RT/LT	SHOULDER								156.80					1244.44			
822+30.00 RT/LT TO 822+75.00 RT/LT	MAINLINE															120	
824+67.59 RT/LT TO 826+00.00 RT/LT	MAINLINE	0.55	0.12	46.34								264.82		367.81		120	
824+82.00 RT/LT TO 852+17.97 RT/LT	SHOULDER								229.82					1823.98			
826+00.00 RT/LT TO 852+00.00 RT/LT	MAINLINE	11.27	2.35	946.40								5200.00		7511.11			
852+00.00 RT/LT TO 854+00.00 RT/LT	MAINLINE	0.95	0.20	79.63								400.00		631.98			
849+15.00 RT TO 851+15.00 RT												200.00					
850+70.00 RT/LT TO 851+15.00 RT/LT	MAINLINE															145	
TOTAL		77.73	16.22	6533.47	0.70	0.15	59.04	245.25	1123.55	621.61	6.06	31646.16	*200.00	61179.87	245.25	505.00	16944.13

*EXCAVATION IS INCLUDED IN THE COST OF CONCRETE CURB, TYPE B

TEMP. PAVEMENT MARKING & REMOVAL SCHEDULE

STATION				TEMP. PVMT MARKING LINE 4" (FT)	SHORT TERM PAVEMENT MARKING (FT)	WORK ZONE PAVEMENT REMOVAL (SQ FT)	RAISED REFL. PVMT MARKER REMOVAL (SQ FT)
661+00.00	TO	854+00.00	RT/LT	EDGE LINES	38214.00	11580	16598.0
661+00.00	TO	854+00.00	CL	CENTER LINE	4718.00	5790	3502.7
661+00.00	TO	854+00.00	CL	CENTER LINE	10177.50		3392.5
TOTAL					53109.5	17370.0	23493.2