

February 21, 2017

SUBJECT: FAP Route 307 (IL 64) Project ACNHPP-0307(042) Section 2015-041B Kane County Contract No. 62B02 Item No. 4, March 3, 2017 Letting Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Table of Contents to the Special Provisions
- 2. Revised pages 36-39 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E. Engineer of Design and Environment

Setter abechlyon A.E.

By: Ted B. Walschleger, P. E. Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Tim Kell; D. Carl Puzey; Estimates

MS/ck

FAP Route 307 (IL 64) Project ACNHPP-0307 (042) Section 2015-041B Kane County Contract No. 62B02

# TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D-1)	2
RECLAIMED ASPHALT PAVEMENT FOR NON-POROUS EMBANKMENT AND BACKFIL	L (D-
1)	2
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D-1)	3
TRAFFIC CONTROL PLAN	4
COARSE AGGREGATE FOR BACKFILL, TRENCH BACKFILL AND BEDDING (D-1)	7
EMBANKMENT I	8
FRICTION AGGREGATE (D-1)	10
GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1)	13
HMA MIXTURE DESIGN REQUIREMENTS (D-1)	15
PUBLIC CONVENIENCE AND SAFETY (D-1)	23
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (D1)	24
ROCK FILL - REPLACEMENT	35
LONG-SPAN GUARDRAIL OVER CULVERT (SPECIAL)	35
CENTERLINE - RUMBLE STRIP	36
STATUS OF UTILITIES (D-1)	36
TEMPORARY PAVEMENT	40
TEMPORARY LIGHTING FOR SINGLE LANE STAGING	41
PIPE UNDERDRAINS FOR STRUCTURES	45
WEEP HOLE DRAINS FOR ABUTMENTS, WINGWALLS, RETAINING WALLS	AND
CULVERTS	46
MEMBRANE WATERPROOFING FOR BURIED STRUCTURES	46
TEMPORARY INFORMATION SIGNING	50
45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING	52
TRAFFIC SIGNAL GENERAL REQUIREMENTS	61
TEMPORARY TRAFFIC SIGNAL INSTALLATION	73
TEMPORARY TRAFFIC SIGNAL TIMING	80
TEMPORARY PAVEMENT MARKING	81
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	84
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	85

FAP Route 307 (IL 64) Project ACNHPP-0307 (042) Section 2015-041B Kane County Contract No. 62B02

CONSTRUCTION AIR QUALITY - DIESEL RE	TROFIT (BDE)	87
DISADVANTAGED BUSINESS ENTERPRISE	PARTICIPATION (BDE)	
HOT-MIX ASPHALT - DENSITY TESTING OF	LONGITUDINAL JOINTS (BDE)	
HOT-MIX ASPHALT – TACK COAT (BDE)		
PAVEMENT MARKING REMOVAL (BDE)		
PROGRESS PAYMENTS (BDE)		
STEEL PLATE BEAM	GUARDRAIL	(BDE)
		104
TRAINING SPECIAL PROVISIONS (BDE)		106
IDOT TRAINING PROGRAM GRADUATE C	N-THE-JOB TRAINING SPECI	AL PROVISION
(TPG)		
TRAFFIC BARRIER TERMINAL, TYPE 1 SPE	CIAL (BDE)	111
WARM MIX ASPHALT (BDE)		112
WEEKLY DBE TRUCKING REPORTS (BDE)		114
WORKING DAYS (BDE)		114
FUEL COST ADJUSTMENT (BDE) (RETURN	FORM WITH BID)	115
STEEL COST ADJUSTMENT (BDE) (RETURN	I FORM WITH BID)	119

## **CENTERLINE - RUMBLE STRIP**

This work consists of the placement of centerline rumble strip as shown on District Detail BD-55. All work shall be in accordance with Section 642 of the Standard Specifications except as modified by BD-55.

This work will be measured and paid for at the contract unit price for CENTER LINE- RUMBLE STRIP - 16".

#### STATUS OF UTILITIES (D-1)

Effective: June 1, 2016

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information in regard to their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department's contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

#### UTILITIES TO BE ADJUSTED

Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain the necessary permits to complete their work; in some instances resolution will be a function of the construction staging. The responsible agency must relocate or complete new installations as noted in the action column; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

Pre-Stage				
STAGE / LOCATION	ТҮРЕ	DESCRIPTION	RESPONSIBLE AGENCY	ACTION
North Side of Ferson Creek Culvert	Underground Cable TV	Possible Underground conflict	Comcast	(2) Weeks
South of Mill Creek Culvert	Underground Cable TV	Possible Underground conflict	Comcast	(2) Weeks
South Side of Mill Creek Culvert	Underground Telephone	Splicing and Wrecking, 4" Poly from sta. 748+90, 40' Rt. To sta. 754+92, 40' Rt.	AT&T	10 Days
South of Mill Creek Culvert	4" Gas main	Conflict between the existing 4" steel gas main and proposed culvert	Nicor Gas	15 Days

No conflicts to be resolved (or if there are conflicts they are to be listed as noted above)

# Pre-Stage: <u>45</u> Days Total Installation

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Company	Name of	Address	Phone	E-mail Address
Responsible to	contact			
Resolve Conflict				
Comcast	Tony Delvaux	688 Industrial Drive Elmhurst, IL 60126	(224)-229- 6589	Tony.delvaux@comcast.com
AT&T	Steve Larson	1000 Commerce Drive Oak Brook, IL 60523	(630)-573- 6484	<u>SI2971@att.com</u>
Nicor Gas	Bruce Koppang	1844 Ferry Road Naperville, IL 60563-9600	(630)-388- 3046	bkoppan@southernco.com

## UTILITIES TO BE WATCHED AND PROTECTED

The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owners part can be secured.

#### Pre-Stage

STAGE / LOCATION	TYPE	DESCRIPTION	OWNER	ACTION
North Side of Ferson Creek Culvert	Overhead Distribution Electric Lines (34,000 Volts, more or less).	No adjustment anticipated	ComEd	Watch and Protect
North Side of Mill Creek Culvert	Overhead Distribution Electric Lines (34,000 Volts, more or less).	No adjustment anticipated	ComEd	Watch and Protect
North Side of Mill Creek Culvert	Power Pole	Bracing of one pole due to the proposed culvert at sta. 750+90, 40' Lt.	ComEd	Watch and Protect
2 Lines on North Side of Mill Creek Culvert	Undergroun d Telephone	No Conflict	AT&T	Watch and Protect

The following contact information is what was used during the preparation of the plans as provided by the owner of the facility.

Agency/Company Responsible to Resolve Conflict	Name of contact	Address	Phone	e-mail address
AT&T	Steve Larson	1000 Commerce Drive Oak Brook, IL 60523	(630)-573- 6484	<u>SI2971@att.com</u>
ComEd	Angela Harrell	One Lincoln Center, Suite 6 <sup>th</sup> Floor Oakbrook Terrace, IL 60181	(630)-576- 6185	Angela.harrell@comed.com

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be taken into account in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided in the action column for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation dates must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor and the utility companies. The Department's contractor is responsible for contacting J.U.L.I.E. prior to any and all excavation work.