

SUMMARY OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-1	COOK	452	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62113		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	RETAINING WALLS	SURVEIL- LANCE	LIGHTING- ILLINOIS	INDIANA	BRIDGE OVER HOHMAN	BRIDGE OVER LITTLE CALUMET	BRIDGE OVER HARRISON	LIGHTING- INDIANA	CONSTRUCTION TYPE CODE			
				1000-2A	Y007	Y032-IF	Y032-IE									
M4428320	CLASS D PATCHES, TYPE III, 200MM	SQ M	18	0	0	0	0	18	0	0	0	0				
M4428450	CLASS D PATCHES, TYPE IV, 350MM	SQ M	850	375	0	0	0	475	0	0	0	0				
M4820150	BITUMINOUS SHOULDERS 150MM	SQ M	394	315	0	0	0	79	0	0	0	0				
M4830360	PORTLAND CEMENT CONCRETE SHOULDERS - 360MM	SQ M	826	826	0	0	0	0	0	0	0	0				
M5010240	CONCRETE REMOVAL	CU M	275.5	0	0	0	0	0	50.9	186.5	38.1	0				
M5010522	PIPE CULVERT REMOVAL	METER	4	0	0	0	0	4	0	0	0	0				
M5020100	STRUCTURE EXCAVATION	CU M	5423	0	5423	0	0	0	0	0	0	0				
M5030350	CONCRETE STRUCTURES	CU M	2046.2	0	2046.2	0	0	0	0	0	0	0				
M5030360	CONCRETE SUPERSTRUCTURE	CU M	83.4	0	0	0	0	0	15.7	56.2	11.5	0				
M5030380	RUSTICATION FINISH	SQ M	3679	0	999	0	0	2680	0	0	0	0				
M5030450	PROTECTIVE COAT	SQ M	2563	0	2563	0	0	0	0	0	0	0				
M5050305	ERECTING STRUCTURAL STEEL	L SUM	1	0	0	0	0	0	0	1	0	0				
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	150470	0	138350	0	0	0	2320	8100	1700	0				
M5120900	TEMPORARY SHEET PILING	SQ M	575	0	575	0	0	0	0	0	0	0				
M542B112	REINFORCED CONCRETE PIPE ELBOW 300MM	EACH	7	7	0	0	0	0	0	0	0	0				
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	2	2	0	0	0	0	0	0	0	0				
M542H020	PIPE CULVERTS, CLASS A, TYPE 1 300MM	METER	13	13	0	0	0	0	0	0	0	0				
M5500620	STORM SEWERS, CLASS B, TYPE 2 200MM	METER	65	65	0	0	0	0	0	0	0	0				
M5502840	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 300MM	METER	674.8	438.8	0	0	0	236	0	0	0	0				
M5502920	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 900MM	METER	4.5	0	0	0	0	4.5	0	0	0	0				
M5503050	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 300MM	METER	161.5	84.6	0	0	0	76.9	0	0	0	0				
M5503060	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 375MM	METER	73.8	73.8	0	0	0	0	0	0	0	0				
M5503070	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 450MM	METER	147.6	147.6	0	0	0	0	0	0	0	0				
M5503090	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 600MM	METER	28.2	28.2	0	0	0	0	0	0	0	0				
M5510080	STORM SEWER REMOVAL 900MM	METER	6	0	0	0	0	6	0	0	0	0				
M5510100	STORM SEWER REMOVAL 1350MM	METER	100	100	0	0	0	0	0	0	0	0				
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	3608	0	1040	0	0	2568	0	0	0	0				
M6010610	PIPE UNDERDRAINS 150MM	METER	275.3	275.3	0	0	0	0	0	0	0	0				
M6011105	PIPE UNDERDRAINS FOR STRUCTURES 150MM	METER	441.5	0	441.5	0	0	0	0	0	0	0				
M6020105	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	24	11	0	0	0	13	0	0	0	0				
M6020170	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 20 FRAME AND GRATE	EACH	4	4	0	0	0	0	0	0	0	0				
M6021605	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2	0	0	0	0	0	0	0	0				

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SUMMARY OF QUANTITIES

SCALE: _____ DRAWN BY: ACE/CAD
DATE: 07/04 CHECKED BY: TAE

AMERICAN
CONSULTING ENGINEERS

Rev. 10-19-04