

# SUMMARY OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-1	COOK	452	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62113		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE											
				ROADWAY 1000-2A	RETAINING WALLS Y007	SURVEIL-LANCE Y032-IF	LIGHTING-ILLINOIS Y038-IE	INDIANA	BRIDGE OVER HOHMAN	BRIDGE OVER LITTLE CALUMET	BRIDGE OVER HARRISON	LIGHTING-INDIANA			
M6021610	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	2	0	0	0	0	2	0	0	0	0		
M6060070	CONCRETE CURB, TYPE B	METER	9.5	9.5	0	0	0	0	0	0	0	0	0		
* M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	138.2	121.5	0	0	0	16.7	0	0	0	0	0		
M6320030	GUARDRAIL REMOVAL	METER	950	261	0	0	0	689	0	0	0	0	0		
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	21.4	0	0	0	0	21.4	0	0	0	0	0		
* M6643400	TEMPORARY FENCE	METER	495	429	0	0	0	66	0	0	0	0	0		
* M6690100	BACKFILL PLUGS	CU M	2	2	0	0	0	0	0	0	0	0	0		
* M6690400	SPECIAL WASTE GROUND WATER DISPOSAL	LITER	3960	3960	0	0	0	0	0	0	0	0	0		
M7030240	TEMPORARY PAVEMENT MARKING LINE - 150	METER	4908	2541	0	0	0	2367	0	0	0	0	0		
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	1779.8	1687.6	0	0	0	92.2	0	0	0	0	0		
M7030530	PAVEMENT MARKING TAPE, TYPE III 125MM	METER	446.8	424	0	0	0	22.8	0	0	0	0	0		
M7040100	TEMPORARY CONCRETE BARRIER	METER	1013	1013	0	0	0	0	0	0	0	0	0		
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	3029	1318	0	0	0	1711	0	0	0	0	0		
M7240330	REMOVE SIGN PANEL - TYPE 3	SQ M	32	14	0	0	0	18	0	0	0	0	0		
* M7800605	EPOXY PAVEMENT MARKING - LINE 100MM	METER	12,521.8	4866.5	0	0	0	7655.3	0	0	0	0	0		
* M7800610	EPOXY PAVEMENT MARKING - LINE 125MM	METER	3819	1216.5	0	0	0	2602.5	0	0	0	0	0		
* M7800620	EPOXY PAVEMENT MARKING - LINE 200MM	METER	1703	0	0	0	0	1703	0	0	0	0	0		
* M7800625	EPOXY PAVEMENT MARKING - LINE 300MM	METER	560	133	0	0	0	427	0	0	0	0	0		
M7830100	PAVEMENT MARKING REMOVAL	SQ M	1996	448	0	0	0	1548	0	0	0	0	0		
* M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50 MM DIA. PVC	METER	75	0	0	75	0	0	0	0	0	0	0		
* M8130203	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 300MM X 610MM X 200MM	EACH	3	0	0	0	0	0	0	0	0	0	3		
* M8131400	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 525MM X 275MM X 200MM	EACH	7	0	0	7	0	0	0	0	0	0	0		
MX030128	REMOVAL OF EXISTING NOISE ABATEMENT WALL	SQ M	4883	0	0	0	0	4883	0	0	0	0	0		
MX030144	CATCH BASINS, 1.2M BY 0.9M SPECIAL, TYPE 20 FRAME AND GRATE	EACH	12	12	0	0	0	0	0	0	0	0	0		
MX030199	TEMPORARY PAVEMENT	SQ M	293	64	0	0	0	229	0	0	0	0	0		
MX030257	ERECTING FLOATING BEARINGS, GUIDED EXPANSION, 1250KN	EACH	7	0	0	0	0	0	0	7	0	0	0		
MX030388	CONCRETE MEDIAN BARRIER AND BASE REMOVAL	METER	1066.5	340.6	0	0	0	725.9	0	0	0	0	0		
MX030495	SHORT-TERM PAVEMENT SUPERPAVE (FULL DEPTH)	SQ M	22124	13844	0	0	0	8280	0	0	0	0	0		
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	50	13.6	0	0	0	36.4	0	0	0	0	0		
MX033226	WHITEWASHING FOR CONCRETE PAVEMENT	SQ M	3106	3106	0	0	0	0	0	0	0	0	0		
MX033269	PIPE ELBOW 200MM	EACH	9	9	0	0	0	0	0	0	0	0	0		
MX033290	SEDIMENT CONTROL, SILT FENCE	METER	356	23	0	0	0	333	0	0	0	0	0		
MX033291	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	METER	712	47	0	0	0	665	0	0	0	0	0		
MX033292	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ M	265	14	0	0	0	251	0	0	0	0	0		

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-80/94/US 6  
KINGERY-BORMAN EXPRESSWAY  
BURNHAM ROAD TO US 41  
**SUMMARY OF QUANTITIES**

SCALE: DATE 07/04 DRAWN BY: ACE/CAD CHECKED BY: TAE



Rev. 10-19-04

Rev.